STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
U-3621A	X-1B

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L Summary 4 (RT) Con't.	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
70+00.00	157	17
70+50.00	181	5
71+00.00	119	4
71+50.00	58	6
72+00.00	107	4
72+50.00	151	5
73+00.00	132	7
73+50.00	90	3
74+00.00	90	0
74+50.00	73	10
75+00.00	28	35
75+50.00	15	43
76+00.00	19	34
76+50.00	23	31
77+00.00	21	38
77+50.00	22	42
78+00.00	17	61
78+50.00	7	94
79+00.00	10	67
79+50.00	15	45
80+00.00	20	86
80+50.00	17	115
81+00.00	10	87
81+50.00	8	77
82+00.00	8	101
82+50.00	9	117
83+00.00	10	64
83+50.00	10	3
84+00.00	8	5
84+50.00	7	6
85+00.00	7	7
85+18.00	4	4

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+25.00	0	0
11+50.00	8	5
11+75.00	8	2
12+00.00	12	0
12+18.81	11	1

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+37.54	0	0
10+50.00	0	25
10+75.00	2	30
11+00.00	4	10
11+25.00	2	4

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+20.00	0	0
10+25.00	0	1
10+50.00	7	2
10+75.00	4	0
11+00.00	1	14
11+25.00	0	54
11+35.42	0	34

Station Y4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+30.00	0	0
12+50.00	20	0
12+75.00	50	7
13+00.00	51	8
13+25.00	42	10
13+50.00	38	16
13+75.00	49	26
14+00.00	52	40
14+25.00	25	68
14+50.00	0	106
14+75.00	0	106
14+87.95	0	45

Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+37.55	0	0
10+50.00	1	10
10+75.00	36	12
11+00.00	63	2
11+25.00	55	1
11+50.00	49	2
11+75.00	42	3

Station Y6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+49.67	0	0
10+75.00	42	12
11+00.00	31	24
11+25.00	15	29
11+50.00	7	33
11+75.00	13	38
12+00.00	21	40
12+25.00	24	40
12+50.00	23	35
12+75.00	23	26
13+00.00	13	23

Station Y7	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+25.00	7	13
11+50.00	12	15
11+75.00	15	18
12+00.00	21	19
12+25.00	30	17
12+50.00	31	19
12+75.00	29	28
13+00.00	28	32
13+25.00	14	44
13+50.00	1	57
13+75.00	2	62
14+00.00	5	37
14+10.53	3	9

Station Y8	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+37.51	0	0
10+50.00	0	25
10+75.00	12	28
11+00.00	20	4
11+20.00	7	1

Station Y9	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+34.00	0	0
10+50.00	0	52
10+75.00	0	72
11+00.00	0	39
11+25.00	1	7