

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.14.01.10751.1, ETC.	29	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	STAMPED AND STAINED ASPHALT CROSSWALKS SY	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	INCIDENTAL MILLING SY	ASPHALT CONCRETE WEDGE COURSE, TYPE I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	MILLED RUMBLE STRIPS (CENTER LINE) LF	MILLED RUMBLE STRIPS (EDGE LINE) LF	REMOVE AND REPLACE ASPHALT CURB LF	CURB RAMPS (STD 848.06 or details) EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	INDUCTIVE LOOP LF				
2018CPT.14.01.10751.1	Polk	1	NC 9	FROM NC 108 TO RUTHERFORD CO LINE	1	2	2WU	NO	NO	7.93	25		200	15.86		835		10,949		657	2,808	2,087	83,741						176			
		2	US 176	FROM NC 108 TO RAILROAD TRACK	2	2	2WU	NO	NO	0.60	51	250	20		20,100	1,500		1,972		118	210				18		15		3,162			
		3	US 176	FROM RAILROAD TRACK TO SC STATE LINE	3	2	2WU	NO	NO	1.00	36		50	2.00	3,300	1,500		2,080		125	210						6					
TOTAL FOR PROJ NO. 2018CPT.14.01.10751.1										9.53		250	270	17.86	23,400	3,835		15,001		900	3,228	2,087	83,741		18		21		3,338			
2018CPT.14.01.20451.1	Henderson	4	SR1123 (LITTLE RIVER RD)	FROM SR 1127 TO NC 225	4	2	2WU	NO	NO	3.96	22		200					4,639	311	3,260					1	1	8					
		5	SR 1569 (HOOPERS CREEK)	FROM SR 1565 TO SR 1591	4	2	2WU	NO	NO	7.07	21				200		481		7,229	484	4,700											
		6	SR 1380 (BRADLEY RD)	NC 191 TO EOM	4	2	2WU	NO	NO	0.35	19				20				384	26												
		7	SR 1460 (COUNTRY RD)	FROM SR 1380 TO SR 1381	4	2	2WU	NO	NO	0.5	20				25				537	36	25											
		8	SR 1919 (OLD HOWARD GAP RD)	FROM SR 1834 TO EOP	4	2	2WU	NO	NO	0.98	19				50				1,007	67	455											
		9	SR 2125 (ANN DR)	FROM SR 1127 TO EOM	4	2	2WU	NO	NO	0.29	20				15				312	21												
		10	SR 2171 (KANUGA FOREST DR)	FROM SR 1127 TO EOM	4	2	2WU	NO	NO	0.46	20				25		261		488	33	76						2					
		11	SR 1497 (MANSFIELD ST)	FROM SR 1393 TO SR 1456	4	2	2WU	NO	NO	0.16	18				10				150	10	108											
		12	SR 1188 (DAVIS MTN RD)	FROM LAUREL PARK CITY LIMIT TO STONEGATE LN	5	2	2WU	NO	NO	0.77	19				20				838	56	130				7,200							
13	SR 1498 (MORRIS RD)	FROM SR 1335 TO DEAD END	4	2	2WU	NO	NO	0.21	20				10				225	15	47													
TOTAL FOR PROJ NO. 2018CPT.14.01.20451.1										14.75			575			742		15,809	1,059	8,801			7,200	1	3	8						
2018CPT.14.01.20751.1	Polk	14	SR 1326 (PEA RIDGE RD)	FROM SR 1005 TO TIP R-5756	4	2	2WU	NO	NO	1.8	24		110					2,352	158	553												
		15	SR 1326 (PEA RIDGE RD)	FROM SR 1373 TO BRIDGE #223	7	2	2WU	NO	NO	0.5	24				50		700		749	50	300											
		16	SR 1330 (JOHN SHEHAN)	FROM .01 MI. EAST OF NC 9 TO SR 1332	4	2	2WU	NO	NO	2.8	23				140				3,434	230	630											
		17	SR 1136 (WHITE OAK MTN. DR)	FROM MM 5.3 TO SR 1137	4	2	2WU	NO	NO	2.8	21				140		235		3,113	209	76											
TOTAL FOR PROJ NO. 2018CPT.14.01.20751.1										7.9			440			935		9,648	647	1,559												
2018CPT.14.01.20881.1	Transylvania	18	SR 1529 (JETER MTN RD)	FROM SR 1528 TO HENDERSON CO LINE	6	2	2WU	NO	NO	2.02	21		100				300	2,305	169	935												
		19	SR 1318 (OLD QUEBEC RD)	FROM SR 1304 TO SR 1309	4	2	2WU	NO	NO	1.3	22				65		547		1,432	96	935											
		20	SR 1374 (GAYLORS BRANCH)	FROM NC 215 TO EOM	4	2	2WU	NO	NO	0.53	19				25				541	36	689											
		21	SR 1103 (WALNUT HOLLOW)	FROM SR 1109 TO SR 1110	4	2	2WU	NO	NO	0.49	21				25				551	37	674											
TOTAL FOR PROJ NO. 2018CPT.14.01.20881.1										4.34			215			547	300	4,829	338	3,233												
GRAND TOTAL													36.52			250	1,500	17.86	23,400	6,059	300	15,001	30,286	2,944	16,821	2,087	83,741	7,200	19	3	29	3,338