

PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.08.29.10771	5	
2017CPT.08.29.20771		

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	SURFACE COURSE, S4.75A TONS	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	LATEX MODIFIED MICROSURFACING, TYPE II SY	ASPHALT SURFACE TREATMENT, SINGLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	VACUUM TRUCK WK	
2017CPT.08.29.10771	Richmond	1	NC 38	FROM SC LINE TO BEG. DIVIDE	1	2	2WU	NO	NO	3.47	21	971.00	6.94		100	3,975			238						
<b>TOTAL FOR MAP NO. 1</b>										<b>3.47</b>		<b>971.00</b>	<b>6.94</b>		<b>100</b>	<b>3,975</b>			<b>238</b>						
2017CPT.08.29.10771	Richmond	2	NC 381	FROM SCOTLAND CO LINE TO SR 1615	3A	2	2WU	NO	NO	2.92	21										36,200				
<b>TOTAL FOR MAP NO. 2</b>										<b>2.92</b>												<b>36,200</b>			
<b>TOTAL FOR PROJ NO. 2017CPT.08.29.10771</b>										<b>6.39</b>		<b>971.00</b>	<b>6.94</b>		<b>100</b>	<b>3,975</b>			<b>238</b>			<b>36,200</b>			
2017CPT.08.29.20771	Richmond	3	SR 1606 (FOX RD)	FROM NC 177 TO US 1	2	2	2WD	NO	NO	3.33	20	933.00	6.66		60		2,960		198	25		39,083.00	13,680	1	
<b>TOTAL FOR MAP NO. 3</b>										<b>3.33</b>		<b>933.00</b>	<b>6.66</b>		<b>60</b>		<b>2,960</b>		<b>198</b>	<b>25</b>		<b>39,083.00</b>	<b>13,680</b>	<b>1</b>	
2017CPT.08.29.20771	Richmond	4	SR 1605 (COGNAC RD)	FROM NC 177 TO US 1	3	2	2WD	NO	NO	1.94	20	544.00	3.88		60	2,105			126	12		22,727.00	7,955	1	
<b>TOTAL FOR MAP NO. 4</b>										<b>1.94</b>		<b>544.00</b>	<b>3.88</b>		<b>60</b>	<b>2,105</b>			<b>126</b>	<b>12</b>		<b>22,727.00</b>	<b>7,955</b>	<b>1</b>	
2017CPT.08.29.20771	Richmond	5	SR 1808 (MCGIRT RD)	FROM SR 1615 (E. MAIN ST) TO SR 1807 (OAK RIDGE CH. RD)	2	2	2WU	NO	NO	1.25	21	350.00	2.50		60		1,170		78			15,459.00	5,411	1	
<b>TOTAL FOR MAP NO. 5</b>										<b>1.25</b>		<b>350.00</b>	<b>2.50</b>		<b>60</b>		<b>1,170</b>		<b>78</b>			<b>15,459.00</b>	<b>5,411</b>	<b>1</b>	
2017CPT.08.29.20771	Richmond	6	SR 1623 (CAMPBELL RD)	FROM SR 1608 (MANHATTAN ST) TO SR 1688 (ATKINSON ST)	4	2	2WD	NO	NO	1.16	20	325.00	2.32		150			570	39	287					
<b>TOTAL FOR MAP NO. 6</b>										<b>1.16</b>		<b>325.00</b>	<b>2.32</b>		<b>150</b>			<b>570</b>	<b>39</b>	<b>287</b>					
2017CPT.08.29.20771	Richmond	7	SR 1475 (MCDONALD CH RD)	FROM JOINT AT US 1 TO PAVEMENT CHANGE	5	2	2WD	NO	NO	0.92	22			12,667	239	1,175			71						
<b>TOTAL FOR MAP NO. 7</b>										<b>0.92</b>				<b>12,667</b>	<b>239</b>	<b>1,175</b>			<b>71</b>						
2017CPT.08.29.20771	Richmond	8	SR 1442 (LEDBETTER RD)	FROM PAVEMENT JOINT NEAR US 1 TO SR 1489 (GRAHAM BRIDGE RD)	6	2	2WU	NO	NO	0.12	22	34.00	0.24		183		165		11						
<b>TOTAL FOR MAP NO. 8</b>										<b>0.12</b>		<b>34.00</b>	<b>0.24</b>		<b>183</b>		<b>165</b>		<b>11</b>						
2017CPT.08.29.20771	Richmond	9	SR 1003 (CADDELL RD)	FROM SR 1475 (MCDONALD CH RD) TO CITY LIMITS OF HOFFMAN	7	2	2WD	NO	NO	0.62	24	175.00	1.24		151	815			49	1					
<b>TOTAL FOR MAP NO. 9</b>										<b>0.62</b>		<b>175.00</b>	<b>1.24</b>		<b>151</b>	<b>815</b>			<b>49</b>	<b>1</b>					
<b>TOTAL FOR PROJ NO. 2017CPT.08.29.20771</b>										<b>9.34</b>		<b>2,361.00</b>	<b>16.84</b>	<b>12,667</b>	<b>903</b>	<b>4,095</b>	<b>4,295</b>	<b>570</b>	<b>572</b>	<b>325</b>		<b>77,269.00</b>	<b>27,046</b>	<b>3</b>	
<b>GRAND TOTAL</b>										<b>15.73</b>		<b>3,332.00</b>	<b>23.78</b>	<b>12,667</b>	<b>1,003</b>	<b>8,070</b>	<b>4,295</b>	<b>570</b>	<b>810</b>	<b>325</b>		<b>36,200.00</b>	<b>77,269.00</b>	<b>27,046</b>	<b>3</b>