PROJECT NO.	SHEET NO.	TOTAL NO.
I-5812	6	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCI-DENTAL STONE BASE TONS	MILLING ASPHALT PAVE-MENT, 1½" DEPTH SY	ASPHALT CONC SURFACE COURSE, TYPE S9.5C TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5D TON	ASPHALT BINDER FOR PLANT MIX TONS	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TONS	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED TON	FOG SEAL SY	FLOW-ABLE FILL (EXCAVATABLE) CY	FRAME WITH TWO GRATES, STD 840.22 EA	REMOVE & REPLACE CONC APRON EA	REPAIR OF DROP INLET EA	SEQUENTIAL FLASHING WARNING LIGHTS EA	WORK ZONE DIGITAL SPEED LIMIT SIGNS EA	WORK ZONE PRESENCE LIGHTING EA	PORT-ABLE LIGHT-ING LS	TRENCH-ING (UN-PAVED) (1) (2") LF	JUNC-TION BOX (STAN-DARD SIZE) EA	INDUC-TIVE LOOP SAW CUT LF
50455.3.1	Guilford	1	I-40 EB/ I-85 NB	FROM E OF SR 3037 (E. LEE STREET) TO E OF SR 3056 (ROCK CREEK DAIRY ROAD)	1	3	MD	NO	NO	1.638	36		34,595		2,916		264	1,603	22,102	8	1	4	3	21	5	15	*			
					1	3	MD	NO	NO	0.069	47		1,903		160		14	88	769											
					1	3	MD	NO	NO	0.035	56		1,150		97		9	53	678											
					1	3	MD	NO	NO	0.277	36		5,850		493		45	271	3,738											
					1	3	MD	NO	NO	0.038	51		1,137		96		9	52	624											
					1	3	MD	NO	NO	0.204	48		5,745		484		44	264	2,753											
					1	3	MD	NO	NO	0.051	48		1,436		121		11	66	1,406											
					1	3	MD	NO	NO	0.246	36		5,196		438		40	241	3,319											
					1	3	MD	NO	NO	0.049	49		1,409		119		11	65	1,006											
					1	3	MD	NO	NO	0.079	48		2,225		187		17	102	1,066											
				BRIDGE - SKIP	1	3	MD	NO	NO	0.066	36																			
					1	4	MD	NO	NO	0.098	48		2,760		232		21	127	1,322											
					1	4	MD	NO	NO	0.11	49		3,162		266		24	145	2,388											
					1	3	MD	NO	NO	0.185	36		3,907		329		30	181	2,171											
					2	6	MD	NO	NO	0.113	72		4,773		402		36	218	2,320											
					2	6	MD	NO	NO	0.139	72		5,871		494		45	268	1,712											
					2	5	MD	NO	NO	0.129	66		4,995		420		38	228	1,589											
					2	5	MD	NO	NO	0.274	60		9,645		812		73	442	3,376											
					2	6	MD	NO	NO	0.042	73		1,799		151		14	82	813											
					2	6	MD	NO	NO	0.169	72		7,139		601		54	326	2,082											
					2	5	MD	NO	NO	0.057	66		2,207		186		17	101	702											
					2	5	MD	NO	NO	0.275	60		9,680		815		73	443	3,388											
					2	5	MD	NO	NO	0.103	54		3,263		275		25	150	1,269											
					2	4	MD	NO	NO	2.04	48		57,446		4,838		437	2,642	24,534											
					2	4	MD	NO	NO	0.058	54		1,837		155		14	84	698											
					2	5	MD	NO	NO	0.079	60		2,781		234		21	127	742											
					2	5	MD	NO	NO	0.034	63		1,257		106		10	58	638											
					2	4	MD	NO	NO	0.148	48		4,168		351		32	192	1,823											
					2	5	MD	NO	NO	0.045	62		1,637		138		12	75	713											
					2	5	MD	NO	NO	0.168	60		5,914		498		45	271	1,774											
					2	4	MD	NO	NO	0.079	54		2,503		211		19	115	973											
					2	4	MD	NO	NO	0.103	48		2,901		244		22	133	1,239											
TOTAL FOR MAP NO. 1										**7.2**			**200,291**		**16,869**		**1,526**	**9,213**	**93,727**	**8**	**1**	**4**	**3**	**21**	**5**	**15**	**1**			
50455.3.1	Guilford	2	OFF RAMP	FROM I-40 EB TO SR 3000 (MCCONNELL ROAD)	3	1		NO	NO	0.117	18	56	1,236	105		6			1,100											
					3	1		NO	NO	0.01	50		293	25		1			49											
TOTAL FOR MAP NO. 2										**0.127**		**56**	**1,529**	**130**		**7**			**1,149**											
50455.3.1	Guilford	3	ON RAMP	FROM SR 3000 (MCCONNELL ROAD) TO I-40 EB	3	1		NO	NO	0.024	33	47	465	39		2			113	1											
					3	1		NO	NO	0.122	17		1,217	103		6			572											
TOTAL FOR MAP NO. 3										**0.146**		**47**	**1,682**	**142**		**8**			**685**	**1**											
50455.3.1	Guilford	4	I-85 NB	I-85 NB MERGE INTO I-40 EB	4	1		NO	NO	0.347	36		7,329		618		35		4,173											
TOTAL FOR MAP NO. 4										**0.347**			**7,329**		**618**		**35**		**4,173**											
50455.3.1	Guilford	5	OFF RAMP	FROM I-40 EB TO SR 3045 (MT HOPE CHURCH ROAD)	3	1		NO	NO	0.161	14		1,649	139		8			1,725			1						50	1	225
					3	2		NO	NO	0.099	26		1,510	127		8			1,563											
					3	2		NO	NO	0.454	24		6,392	540		32			3,594											
					3	2		NO	NO	0.029	19		598	50		3			176											
TOTAL FOR MAP NO. 5										**0.743**			**10,149**	**856**		**51**			**7,058**			**1**						**50**	**1**	**225**
50455.3.1	Guilford	6	ON RAMP	FROM SR 3045 (MT HOPE CHURCH ROAD) TO I-40 EB/I-85 NB	3	1		NO	NO	0.094	14	37	772	65		4			994											
TOTAL FOR MAP NO. 6										**0.094**		**37**	**772**	**65**		**4**			**994**											
50455.3.1	Guilford	7	OFF RAMP	FROM I-40 EB/I-85NB TO SR 3056 (ROCK CREEK DAIRY ROAD)	3	1		NO	NO	0.09	18	32	950	80		5			211											225
TOTAL FOR MAP NO. 7										**0.09**		**32**	**950**	**80**		**5**			**211**											**225**
50455.3.1	Guilford	8	ON RAMP	FROM SR 3045 (ROCK CREEK DAIRY ROAD) TO I-40 EB/I-85 NB	2	1		NO	NO	0.177	17	71	1,765	149		9			2,594											
TOTAL FOR MAP NO. 8										**0.177**		**71**	**1,765**	**149**		**9**			**2,594**											