

## REFORESTATION

□ TREE REFORESTATION SHALL JE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

**REFORESTATION** MIXTURE, TYPE, SIZE, AND FURNISH SHALL

34% PLATANUS OCCIDENTALIS

33% LIRIODENDRON TULIPIFERA

33% FRAXINUS PENNSYLVANICA

| PROJECT REFERENCE NO.      |  | SHEET NO.              |
|----------------------------|--|------------------------|
| B-5348                     |  | RF-I                   |
| RW SHEET NO.               |  |                        |
| ROADWAY DESIGN<br>ENGINEER |  | HYDRAULICS<br>ENGINEER |

| CONFORM TO THE FOLLOWING: |                          |  |  |
|---------------------------|--------------------------|--|--|
| AMERICAN SYCAMORE         | 12 in – 18 in <i>3</i> R |  |  |
| YELLOW POPLAR             | 12 in – 18 in <b>3</b> R |  |  |
| GREEN ASH                 | 12 in – 18 in 3R         |  |  |
|                           |                          |  |  |

## **REFORESTATION DETAIL SHEET**

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT