

|                             |           |
|-----------------------------|-----------|
| PROJECT NO.                 | SHEET NO. |
| 2017CPT.02.16.10521.1, ETC. | 9         |

**SUMMARY OF QUANTITIES**

| PROJECT NO                                      | COUNTY | MAP NO | ROUTE       | DESCRIPTION                              | TYP | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH MI    | WIDTH FT | HAULING NCDOT SUPPLIED SHOULDER MATERIAL EA | INCIDENTAL STONE BASE TONS | SHOULDER RECONSTRUCTION SMI | 3" MILLING SY | 2.5" MILLING SY | 1.5" MILLING SY | 0" TO 1.5" MILLING SY | INCIDENTAL MILLING SY | 6" DEPTH MILL PATCHING (B25.0B) TON | INTER-MEDIATE COURSE, I19.0C TONS | SURFACE COURSE, S9.5C TONS | ASPHALT BINDER FOR PLANT MIX TONS | PORTABLE LIGHTING LS | TEMPORARY SILT FENCE LF | WATTLE LF  | SEED & MULCHING AC | RESPONSE FOR EROSION CONTROL EA |   |
|---|--------|--------|-------------|--|-----|-------|-----------|--------------------------------|---------------------------|--------------|----------|---|----------------------------|-----------------------------|---------------|-----------------|-----------------|-----------------------|-----------------------|-------------------------------------|-----------------------------------|----------------------------|-----------------------------------|----------------------|-------------------------|------------|--------------------|---------------------------------|---|
| 2017CPT.02.17.10541.1                           | Lenoir | 1      | US 70 EB    | MT VERNON PARK ROAD TO 5 LANE SECTION    | 1   | 2     | MD        | NO                             | NO                        | 3.27         | 29       | 164   | 25                         | 6.54                        |               |                 |                 |                       | 400                   | 100                                 |                                   | 10,087                     | 595                               | 0.25                 | 50                      | 25         | 4.09               | 2                               |   |
|   |        | 2      | US 70 WB    | MT VERNON PARK ROAD TO 5 LANE SECTION    | 1   | 2     | MD        | NO                             | NO                        | 3.28         | 29       | 164   | 50                         | 6.56                        |               |                 |                 |                       | 400                   | 100                                 |                                   | 10,401                     | 614                               | 0.25                 | 50                      | 25         | 4.10               |                                 |   |
|   |        | 3      | US 70 EB/WB | BEGIN 5 LANE SECTION TO NC 58            | 3   | 2     | MU        | NO                             | NO                        | 0.92         | 86       |   |                            |                             | 46,417        |                 |                 |                       |                       |                                     |                                   |                            | 8,446                             | 498                  | 0.30                    |            |                    | 0.20                            |   |
|   |        | 4      | US 70 EB    | NC 58 TO JONES COUNTY LINE               | 1   | 2     | MD        | NO                             | NO                        | 3.39         | 30       | 170   | 50                         | 6.78                        |               |                 |                 |                       | 400                   |                                     |                                   |                            | 10,916                            | 644                  |                         | 100        | 50                 | 4.24                            | 1 |
|   |        | 5      | US 70 WB    | NC 58 TO JONES COUNTY LINE               | 1,5 | 2     | MD        | NO                             | NO                        | 3.38         | 30       | 169   | 50                         | 6.76                        |               |                 | 31,000          |                       |                       | 600                                 |                                   | 4,628                      | 7,223                             | 648                  |                         | 100        | 50                 | 4.22                            |   |
|   |        | 6      | US 70 RAMP  | US 70 WB TO 4 LANE SECTION               | 2   | 2     | M2        | NO                             | NO                        | 0.40         | 60       | 20  |                            | 0.80                        |               |                 |                 | 6,000                 |                       |                                     |                                   |                            | 2,423                             | 143                  | 0.05                    |            |                    | 0.50                            |   |
|   |        | 7      | US 70 RAMP  | 4 LANE SECTION TO US 70 EB               | 4   | 2     | M2        | NO                             | NO                        | 0.42         | 30       | 11  |                            | 0.42                        |               |                 |                 |                       | 1,725                 |                                     |                                   |                            | 1,277                             | 75                   | 0.05                    |            |                    | 0.32                            |   |
|   |        | 8      | RAMP 708    | US 70 TO US 70                           | 2   | 2     | M2        | NO                             | NO                        | 0.14         | 25       | 4   |                            | 0.14                        |               |                 |                 |                       |                       |                                     |                                   |                            | 355                               | 21                   | 0.05                    |            |                    | 0.11                            |   |
|   |        | 9      | RAMP 710    | US 70 TO US 70                           | 2   | 2     | M2        | NO                             | NO                        | 0.15         | 25       | 4   |                            | 0.15                        |               |                 |                 |                       |                       |                                     |                                   |                            | 381                               | 22                   | 0.05                    |            |                    | 0.11                            |   |
| <b>TOTAL FOR PROJ NO. 2017CPT.02.17.10541.1</b> |        |        |             |  |     |       |           |                                |                           | <b>15.35</b> |          | <b>706</b>                                  | <b>175</b>                 | <b>28.15</b>                | <b>46,417</b> | <b>31,000</b>   | <b>6,000</b>    | <b>1,725</b>          | <b>1,800</b>          | <b>200</b>                          | <b>4,628</b>                      | <b>51,509</b>              | <b>3,260</b>                      | <b>1.00</b>          | <b>300</b>              | <b>150</b> | <b>17.88</b>       | <b>3</b>                        |   |
| 2017CPT.02.16.10521.1                           | Jones  | 10     | US 70 EB    | LENOIR COUNTY LINE TO CRAVEN COUNTY LINE | 1   | 2     | MD        | NO                             | NO                        | 3.90         | 32       | 195   | 200                        | 7.80                        |               |                 |                 |                       | 500                   |                                     |                                   | 13,264                     | 783                               |                      | 250                     | 75         | 4.88               | 1                               |   |
|   |        | 11     | US 70 WB    | LENOIR COUNTY LINE TO CRAVEN COUNTY LINE | 1   | 2     | MD        | NO                             | NO                        | 3.92         | 32       | 196   | 200                        | 7.84                        |               |                 |                 |                       | 500                   |                                     |                                   | 13,332                     | 787                               |                      | 250                     | 75         | 4.90               |                                 |   |
| <b>TOTAL FOR PROJ NO. 2017CPT.02.16.10521.1</b> |        |        |             |  |     |       |           |                                |                           | <b>7.82</b>  |          | <b>391</b>                                  | <b>400</b>                 | <b>15.64</b>                |               |                 |                 |                       | <b>1,000</b>          |                                     |                                   | <b>26,596</b>              | <b>1,570</b>                      |                      | <b>500</b>              | <b>150</b> | <b>9.78</b>        | <b>1</b>                        |   |
| <b>GRAND TOTAL</b>                              |        |        |             |  |     |       |           |                                |                           | <b>23.17</b> |          | <b>1,097</b>                                | <b>575</b>                 | <b>43.79</b>                | <b>46,417</b> | <b>31,000</b>   | <b>6,000</b>    | <b>1,725</b>          | <b>2,800</b>          | <b>200</b>                          | <b>4,628</b>                      | <b>78,105</b>              | <b>4,830</b>                      | <b>1.00</b>          | <b>800</b>              | <b>300</b> | <b>27.66</b>       | <b>4</b>                        |   |