

PROJECT NO.	SHEET NO.
2018CPT.03.02.10821, ETC.	30

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	INC. STONE BASE TON	SHOULDER RECONST. SMI	1 1/2" MILLING SY	3" MILLING SY	INC. MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TON	SURFACE COURSE, S4.75A TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT (MILL) TON	ASPHALT FOR PAVEMENT INTERLAYER (S4.75A) TON
2018CPT.03.02.10821	Sampson	1	US 13 (FAYETTEVILLE HWY.)	FROM CUMBERLAND CO. TO US 421 AT SPIVEY'S CORNER (MP 0.000 - MP 9.309) (NO WORK SAMPSON BRIDGE #9)	1	2	2WU	NO	NO	9.309	28	1,585	480	18.61	3,095		1,150		14,331	25		861	250	
		2	US 701 (N. INGOLD AVE./ GARLAND HWY)	FROM PVMT. SEAM NORTH OF 7TH ST. IN GARLAND TO OVERPASS AT US 421 (MP 2.336 - MP 15.771)	2, 3	2	2WU	YES	NO	13.435	24	2,285	900	26.87	198,750				32,934			1,976		500
		3	US 701 BUS (SOUTHEAST & NORTHEAST BLVD./ HOBBS HWY.)	FROM OVERPASS AT US 421 TO US 701 GARLAND HWY (MP 0.00 - MP 5.704)	2, 4	2 - 5	MU	NO	NO	5.704	26 - 64	415	310	4.50	54,875	120,175	200		29,600			1,776		300
		4	NC 242 (ELIZABETH TOWN HWY.)	FROM CUMBERLAND CO TO NC 411 (MP 0.00 - MP 3.710)	1	2	2WU	NO	NO	3.71	22	645	225	7.42	49,660				4,160	20		251		
TOTAL FOR PROJ NO. 2018CPT.03.02.10821										32.158		4,930	1,915	57.40	306,380	120,175	1,350		81,025	45		4,864	250	800
2018CPT.03.02.20821	Sampson	5	SR 1742 (GOVERNOR MOORE RD.)	FROM SR 1751 TO SR 1746 (MP 0.000 - MP 5.854) NO ASPHALT WORK SAMPSON BRIDGE # 224	5, 6	2	2WU	NO	NO	5.854	18						500	677	5,653			369		
		6	SR 1451 (BAPTIST CHAPEL RD.)	FROM SR 1002 TO US 13 (MP 0.000 - MP 4.669)	6	2	2WU	NO	NO	4.669	20							330	4	4,661			280	
		7	SR 1441 (WELCOME SCHOOL RD.)	FROM SR 1431 TO SR 1006 (MP 0.000 - MP 2.420)	6	2	2WU	NO	NO	2.42	20							330	40	2,416			147	
		8	SR 1100 (IVANHOE RD.)	FROM SR 1007 TO SR 1105 (MP 0.000 - MP 4.938)	5, 6	2	2WU	NO	NO	4.938	19							320	2,919	5,771			475	
		9	SR 1258 (HAIRR ST.)	FROM SR 1233 TO END MAINTENANCE (MP 0.000 - MP 0.490)	6	2	2WU	NO	NO	0.49	20							330		510			31	
		10	SR 1002 (DUNN RD.)	FROM SR 1233 (AUTRYVILLE RD.) MP 4.361 TO SR 1006 (MAXWELL RD.) MP 11.705	5, 6	2	2WU	NO	NO	7.344	18							300	4,555	8,512	60		715	
		11	SR 1006 (MAXWELL RD.)	FROM SR 1440 (BUTLER RD.) MP 11.520 TO CUMBERLAND COUNTY LINE MP 18.059	6	2	2WU	NO	NO	6.539	22								370	8	8,268			496
TOTAL FOR PROJ NO. 2018CPT.03.02.20821										32.254							2,480	8,203	35,791	60		2,513		
2018CPT.03.02.20822	Sampson	12	SR 1492 (JACKSON ST./ OLD FAYETTEVILLE ST.)	FROM PVMT. SEAM AT OLD FAYETTEVILLE ST./W. PINE ST TO SR 1501 (MP 1.170 TO MP 1.480)	7	2	2WU	NO	NO	0.31	19						320				196	13		
		13	SR 1703 (CHURCH ST./OLD GOLDSBORO RD)	FROM NC 50 (RALEIGH ST) TO SR 1701 (MP 10.046 - MP 12.342) (NO WORK MP 10.41 - MP 10.51 & NO ASPHALT WORK SAMPSON BRIDGE # 348)	7	2	2WU	NO	NO	2.296	19							530				1,418	95	
		14	SR 1704 (IRWIN RD.)	FROM US 13 (GOLDSBORO ST.) TO SR 1703 [MP 0.000 - MP 0.453]	7	2	2WD	NO	NO	0.453	19							320				286	19	
		15	SR 1317 (FREDRICK RD.)	FROM SR 1311 TO SR 1315 (MP 0.000 - MP 1.630)	7	2	2WU	NO	NO	1.63	20							330				1,091	73	
		16	SR 1910 (HUDSON RD.)	FROM SR 1919 TO SR 1909 (MP 0.000 - MP 1.360)	7	2	2WU	NO	NO	1.36	20							330				910	61	
TOTAL FOR PROJ NO. 2018CPT.03.02.20822										6.049							1,830				3,901	261		
GRAND TOTAL										70.461		4,930	1,915	57.40	306,380	120,175	5,660	8,203	116,816	105	3,901	7,638	250	800