

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	CONCRETE JOINT REPAIR TON	PAVEMENT INTERLAYER SY	2'-6" CONCRETE CURB & GUTTER LF	CONCRETE CURB RAMP EA	6" CONCRETE DRIVEWAY SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) SY	REMOVE MONOLITHIC CONC. ISLAND SY	REMOVE AND REPLACE 4" CONCRETE SIDEWALK SY	REMOVE & REPLACE 2'-6" CURB & GUTTER LF	REMOVE & REPLACE CURB RAMPS EA	REMOVE CONCRETE CURB RAMPS EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	CONVERT EXISTING DROP INLET TO OPEN THROAT CATCH BASIN EA	GR END UNITS, TYPE TL-3 EA	GR ANCHOR UNITS, TYPE B-83 EA		
2018CPT.03.02.10821	Sampson	1	US 13 (FAYETTEVILLE HWY.)	FROM CUMBERLAND CO. TO US 421 AT SPIVEY'S CORNER (MP 0.000 - MP 9.309) (NO WORK SAMPSON BRIDGE #9)	1	2	2WU	NO					50	75	100											
		2	US 701 (N. INGOLD AVE./ GARLAND HWY)	FROM PVMT. SEAM NORTH OF 7TH ST. IN GARLAND TO OVERPASS AT US 421 (MP 2.336 - MP 15.771)	2, 3	2	2WU	YES	300.00	194,265				150							1			2	2	
		3	US 701 BUS (SOUTHEAST & NORTHEAST BLVD./ HOBBS HWY.)	FROM OVERPASS AT US 421 TO US 701 GARLAND HWY (MP 0.00 - MP 5.704)	2, 4	2-5	MU	NO	450.00	166,850	20	1					10	85	1	1	47	19	1	3	2	
		4	NC 242 (ELIZABETHTOWN HWY.)	FROM CUMBERLAND CO TO NC 411 (MP 0.00 - MP 3.710)	1	2	2WU	NO						20												
<b>TOTAL FOR PROJ NO. 2018CPT.03.02.10821</b>								<b>750.00</b>	<b>361,115</b>		<b>20</b>	<b>1</b>	<b>220</b>	<b>75</b>	<b>100</b>	<b>10</b>	<b>85</b>	<b>1</b>	<b>1</b>	<b>48</b>	<b>19</b>	<b>1</b>	<b>5</b>	<b>4</b>		
2018CPT.03.02.20821	Sampson	5	SR 1742 (GOVERNOR MOORE RD.)	FROM SR 1751 TO SR 1746 (MP 0.000 - MP 5.854) NO ASPHALT WORK SAMPSON BRIDGE # 224	5, 6	2	2WU	NO																		
		6	SR 1451 ( BAPTIST CHAPEL RD.)	FROM SR 1002 TO US 13 (MP 0.000 - MP 4.669)	6	2	2WU	NO																		
		7	SR 1441 ( WELCOME SCHOOL RD.)	FROM SR 1431 TO SR 1006 (MP 0.000 - MP 2.420)	6	2	2WU	NO																		
		8	SR 1100 ( IVANHOE RD.)	FROM SR 1007 TO SR 1105 (MP 0.000 - MP 4.938)	5, 6	2	2WU	NO																		
		9	SR 1258 (HAIRR ST.)	FROM SR 1233 TO END MAINTENANCE (MP 0.000 - MP 0.490)	6	2	2WU	NO																		
		10	SR 1002 (DUNN RD.)	FROM SR 1233 (AUTRYVILLE RD.) MP 4.361 TO SR 1006 (MAXWELL RD.) MP 11.705	5, 6	2	2WU	NO																		
<b>TOTAL FOR PROJ NO. 2018CPT.03.02.20821</b>																										
2018CPT.03.02.20822	Sampson	12	SR 1492 (JACKSON ST./ OLD FAYETTEVILLE ST.)	FROM PVMT. SEAM AT OLD FAYETTEVILLE ST./W. PINE ST TO SR 1501 (MP 1.170 TO MP 1.480)	7	2	2WU	NO																		
		13	SR 1703 (CHURCH ST./OLD GOLDSBORO RD)	FROM NC 50 (RALEIGH ST) TO SR 1701 ( MP 10.046 - MP 12.342) (NO WORK MP 10.41 - MP 10.51 & NO ASPHALT WORK SAMPSON BRIDGE # 348)	7	2	2WU	NO																		
		14	SR 1704 (IRWIN RD.)	FROM US 13 (GOLDSBORO ST.) TO SR 1703 [MP 0.000 - MP 0.453]	7	2	2WD	NO																		
		15	SR 1317 (FREDRICK RD.)	FROM SR 1311 TO SR 1315 (MP 0.000 - MP 1.630)	7	2	2WU	NO																		
		16	SR 1910 (HUDSON RD.)	FROM SR 1919 TO SR 1909 (MP 0.000 - MP 1.360)	7	2	2WU	NO																		
<b>TOTAL FOR PROJ NO. 2018CPT.03.02.20822</b>																										
<b>GRAND TOTAL</b>								<b>750.00</b>	<b>361,115</b>		<b>20</b>	<b>1</b>	<b>220</b>	<b>75</b>	<b>100</b>	<b>10</b>	<b>85</b>	<b>1</b>	<b>1</b>	<b>48</b>	<b>19</b>	<b>1</b>	<b>5</b>	<b>4</b>		