COMPUTED BY: BNE DATE: 3/29/2017

CHECKED BY: JMB DATE: 5/19/2017

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

PROJECT NO.	SHEET NO.
U-2579C	3D-1

NPC0EP.A3R3AL

Note: Invert Elevations indicated are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48 INCHES & UNDER)

| STATION | LOCATION (LT, RT, OR CL) | STRUCTURE NO. FROM | STRUCTURE NO. TO | TOP ELEVATION | INVERT ELEVATION | INVERT ELEVATION | MIN. REQUIRED SLOPE % | SIDE DRAIN PIPE (RCP, CSP, CAAP, HDPE, or PVC) SIZE 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | DO NOT USE RCP | DO NOT USE CSP | DO NOT USE CAAP | DO NOT USE HDPE | C.S. PIPE SIZE 12" THICKNESS OR GAUGE .064 | 15" .064 | 18" .064 | 24" .064 | 30" .079 | 36" .079 | 42" .109 | 48" .109 | R.C. PIPE CLASS III SIZE 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | R.C. PIPE CLASS IV SIZE 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | 24" R.C. PIPE (CLASS V) | 30" R.C. PIPE (CLASS V) | 36" R.C. PIPE (CLASS V) | 42" R.C. PIPE CULVERTS, CONTRACTOR DESIGN | | ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CU. YARDS R.C.P. | C.S.P. | QUANTITIES FOR DRAINAGE STRUCTURES PER EACH (0' THRU 5.0') | LIN. FT. A 5.0' THRU 10.0' | LIN. FT. B 10.0' AND ABOVE | TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (1.3 X COL. 'B') | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES, AND HOOD STANDARD 840.03 TYPE OF GRATE E | F | G | CONCRETE TRANSITIONAL SECTION DROP INLET | CATCH BASIN | D.I. STD. 840.14 OR STD. 840.15 | D.I. FRAME AND GRATE STD. 840.16 | G.D.I. TYPE "A" STD. 840.17 OR 840.26 | G.D.I. TYPE "B" STD. 840.18 OR 840.27 | G.D.I. TYPE "D" STD. 840.19 OR 840.28 | G.D.I. (W.S. FLAT) FRAME W/ 2 GRATES STD. 840.20 | G.D.I. (W.S. SAG) FRAME W/ GRATE STD. 840.22 | G.D.I. (W.S. SAG) FRAME W/ 2 GRATES STD. 840.22 | G.D.I. (N.S. SAG) FRAME W/ 2 GRATES STD. 840.24 | G.D.I. (N.S. FLAT) FRAME W/ 2 GRATES STD. 840.29 | T.B.D.I. STD. 840.35 | T.B.J.B. STD. 840.34 | J.B. STD. 840.31 OR 840.32 | M.H. FRAME AND COVER STD. 840.54 | DRY DETENTION BASIN DRAWDOWN STRUCTURE SEE DETAIL SHEET 2D-2 | 8" SLUICE GATE - SEE SHEET 2D-2 | 15" SIDE DRAIN PIPE ELBOWS | 18" SIDE DRAIN PIPE ELBOWS | 24" SIDE DRAIN PIPE ELBOWS | 30" SIDE DRAIN PIPE ELBOWS | 36" SIDE DRAIN PIPE ELBOWS | BERM DITCH OUTLET STD. 840.10 | BERM DITCH OUTLET STD. 850.11 | CONCRETE AND BRICK PIPE PLUG STD. 840.71 | FLOWABLE FILL C.Y. | CONC. COLLARS CL. "B" C.Y. STD. 840.72 | PIPE REMOVAL LIN. FT. | REMARKS |
|---|---|---