



DEFAULT PHASING DIAGRAM



ALTERNATE PHASING DIAGRAM



DEFAULT PHASING TABLE OF OPERATION

SIGNAL FACE	PHASE		
	02	07	FLASH
21,22,23	G	R	Y
71,72	(f)	(f)	(f)

ALTERNATE PHASING TABLE OF OPERATION


SIGNAL FACE	PHASE		
	02	07	FLASH
21,22,23	G	R	Y
71,72	(R)	(f)	(f)

OASIS 2070 LOOP & DETECTOR INSTALLATION CHART

LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	DETECTOR PROGRAMMING									
				NEW LOOP	PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD	
2A	6X6	300	4	Y	2	Y	Y	-	-	-	-	-	Y
2B	6X6	300	4	Y	2	Y	Y	-	-	-	-	-	Y
2C	6X6	300	4	Y	2	Y	Y	-	-	-	-	-	Y
7A	6X40	0	2-4-2	Y	7	Y	Y	-	-	-	★15	-	Y


*Disable delay during Alternate Phasing operation.

SIGNAL FACE I.D.



PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- ◄ UNDETECTED MOVEMENT (OVERLAP)
- ◄ UN SIGNALIZED MOVEMENT
- ◄ PEDESTRIAN MOVEMENT



2 Phase Fully Actuated Wilmington Signal System

NOTES

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
3. Set all detector units to presence mode.
4. The Division Traffic Engineer will determine the hours of use for each phasing plan.
5. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
6. Pedestal mounted signal heads shall be mounted a minimum of 8' above the high point of the roadway surface elevation.
7. Maximum times shown in timing charts are for free-run operation only. Coordinated signal timing values supersede these values.
8. Signal System data: controller asset #1100.

LEGEND

- | PROPOSED | EXISTING |
|--|----------|
| ○ → Traffic Signal Head | ● → N/A |
| ◐ → Modified Signal Head | N/A |
| ◑ → Sign | N/A |
| ◑ → Pedestrian Signal Head With Push Button & Sign | ■ → |
| ○ → Type II Signal Pedestal | ● → |
| ○ → Signal Pole with Guy | ● → |
| ○ → Signal Pole with Sidewalk Guy | ● → |
| ⊠ → Inductive Loop Detector | ⊠ → |
| □ → Controller & Cabinet | □ → |
| □ → Junction Box | ■ → |
| --- 2-in Underground Conduit | --- |
| N/A Right of Way | --- |
| → Directional Arrow | → |
| —•— Directional Drill | N/A |
| ⊠ → Metal Pole with Mastarm | ⊠ → |
| N/A Guardrail | — — |
| N/A Concrete Barrier | — — |
| N/A Noise Wall | — — |

OASIS 2070E TIMING CHART

FEATURE	PHASE	
	2	7
Min Green 1 *	12	5
Extension 1 *	6.0	3.0
Max Green 1 *	100	30
Yellow Clearance	4.5	3.0
Red Clearance	1.6	3.5
Red Revert	2.0	2.0
Walk 1 *	-	-
Don't Walk 1	-	-
Seconds Per Actuation *	1.5	-
Max Variable Initial *	34	-
Time Before Reduction *	15	-
Time To Reduce *	30	-
Minimum Gap	3.0	-
Recall Mode	MIN RECALL	-
Vehicle Call Memory	YELLOW	-
Dual Entry	-	-
Simultaneous Gap	ON	ON

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

New Installation

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for the Offices of:

SR 1409 (Military Cutoff Road) at U-Turn South of Putman Drive

Division 3 New Hanover County Wilmington

PLAN DATE: March 2017 REVIEWED BY: M B Toth

PREPARED BY: G B Spell REVIEWED BY:

REVISIONS INIT. DATE

SCALE 1"=40'

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 160 RALEIGH, NORTH CAROLINA 27609 (919) 876-8888 NCBEES #F-0326

SEAL NORTH CAROLINA PROFESSIONAL ENGINEER MELISSA B. TOTH 025892

6/6/2017

SIG. INVENTORY NO. 03-1100

06-JUN-2017 13:48 D:\Projects\170701\170701\00053591 - U-4751 Military Cutoff\402-Signal\03-1100.dgn