PROJECT REFERENCE NO.	SHEET NO.
U - 4751	Sig. 9.4

ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT. PHASING DURING <u>COORDINATION</u> — SELECT ALL PAGE CHANGES (AS SHOWN BELOW) WITHIN COORDINATION PLAN PROGRAMMING.

TO RUN ALT, PHASING DURING <u>free run</u> — program page changes (shown below) in separate time of day EVENTS. IF PAGE 1 IS USED, NO EVENT PROGRAMMING IS NECESSARY FOR THAT PARTICULAR PAGE.

PHASING	INPUTS PAGE	OVERLAPS PAGE
ACTIVE PAGES REQUIRED TO RUN <u>DEFAULT PHASING</u>	1	1
ACTIVE PAGES REQUIRED TO RUN <u>ALTERNATE PHASING</u>	2	2

NOTE: PAGES NOT SHOWN (i.e. sequence, phase control, etc.) SHOULD REMAIN AS '1', OR AS DEFINED BY TIMING ENGINEER.

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY PAGE CHANGE EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX. FREE RUN PAGE CHANGE EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

ALTERNATE PHASING PAGE CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN THESE OVERLAP/INPUT PAGE CHANGES ACTIVATE TO CALL THE "ALTERNATE PHASING":

OVERLAPS PAGE 2: Modifies overlap parent phases for heads 71 and 72 to run

protected turns only.

INPUTS PAGE 2: Reduces delay time for phase 7


call on loop 7A to 0 seconds.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 03-1100 DESIGNED: April 2017 SEALED: REVISED:

Electrical Detail - Sheet 4 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

025892



DETAILS FOR: SR 1409 (Military Cutoff Road) U-Turn South of Putman Drive

Division 3 New Hanover County Wilmington PLAN DATE: April 2017 REVIEWED BY: M B Toth PREPARED BY: G B Spell REVIEWED BY: REVISIONS

INIT. DATE SIG. INVENTORY NO. 03-1100