


PILE SPLICE DETAILS



BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE FOR THE SEVERAL PAY ITEMS.

## TEMPORARY DRAINAGE AT END BENT

PLANS PREPARED BY K. E. LOFTON DATE : 6–17 5540 Centerview Drive, Suite 217 Raleigh, NC 27606-3386 D. PRETORIUS DATE : 7-17

**PARSONS** NC LICENSE No. F-0246 OR NORTH CAROLINA DEPARTMENT OF TRANSPORTA

I-4729A PROJECT NO. **POLK** COUNTY 22 + 87.20 -RP E-STATION:

SHEET 3 OF 3

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

SEAL SEAL

029979

Doodstyned by INE

8/16/2017

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH

> SUBSTRUCTURE END BENT 2

SHEET No. **REVISIONS** S1-20 TOTAL SHEETS 24

CHECKED BY : DESIGN ENGINEER: <u>A. D. SHAH</u> DATE: <u>8–17</u>