

SUMMARY OF QUANTITIES

ASPHALT PAVEMENT REMOVAL SUMMARY

LINE	STATION	STATION	LOCATION	AREA	SQUARE YARDS
L	18+19.00	19+04.00	LT	987.7	110
L	20+62.00	22+48.00	LT	2,179.70	242
L	22+79.00	23+48.00	LT	808.30	90
L	24+02.00	26+30.00	LT	987.60	110
L	26+93.00	30+69.00	LT	1,853.90	206
L	31+07.00	33+87.00	LT	1,481.00	165
L	34+24.00	35+07.00	LT	402.00	45
L	35+39.00	38+36.00	LT	1,569.00	174
L	38+76.00	39+69.00	LT	319.15	35
L	40+19.00	42+87.00	LT	1,519.00	169
L	45+39.00	43+98.00	LT	154.19	17
L	44+25.00	46+00.00	LT	591.60	66
L	47+11.00	47+83.00	LT	269.00	30
L	48+17.00	53+13.00	LT	2842.00	316
L	53+48.00	60+05.00	LT	3555.00	395
L	64+74.00	65+58.00	LT	405.00	45
L	65+87.00	68+13.00	LT	1382.00	154
L	68+46.00	70+58.00	LT	1,401.00	156
L	71+01.00	73+35.00	LT	1,849.00	205
L	73+77.00	76+66.00	LT	1,647.00	183
L	77+13.00	83+30.00	LT	2431.70	270
L	17+90.00	19+82.00	RT	693.96	77
L	20+55.00	22+39.00	RT	443.00	49
L	23+59.00	25+96.00	RT	1137.00	126
L	26+29.00	30+15.00	RT	1795.16	199
L	30+57.00	34+77.00	RT	1918.92	213
L	35+29.00	39+60.00	RT	1897.00	211
L	39+90.00	47+42.00	RT	5825.00	647
L	47+82.00	53+57.00	RT	2690.58	299
L	53+90.00	55+91.00	RT	638.75	71
L	57+15.00	59+73.00	RT	508.69	57
L	60+68.00	63+00.00	RT	2376.30	264
L	63+27.00	68+07.00	RT	1963.00	218
L	68+36.00	70+58.00	RT	998.71	111
L	70+89.00	73+04.00	RT	914.80	102
L	73+71.00	76+77.00	RT	1043.06	116
L	77+37.00	79+57.00	RT	837.14	93
EY17	42+67.00	43+13.00	LT	1,125.00	125
EY20	35+60.00	38+63.00	RT	964.00	107
EY20	39+38.00	42+10.00	RT	1,005.00	112
TOTAL					6,379
SAY					6,380

MILLING ASPHALT PAVEMENT 0" TO 3" DEPTH

LINE	STATION	STATION	LOCATION	LENGTH	WIDTH	SQUARE YARDS
L	16+20	18+50	LT	230.00	25	639
L	16+20	18+00	RT	180.00	25	500
L	20+50	28+00	LT	750.00	14.5	1208
L	21+85	30+00	RT	815.00	13.5	1223
L	36+50	42+10	LT	560.00	27	1680
L	37+50	40+50	RT	300.00	16	533
L	44+00	46+90	RT	290.00	19	612
L	45+70	49+00	LT	330.00	28.5	1045
L	49+00	58+00	RT	900.00	18	1800
L	52+50	56+50	LT	400.00	19.5	867
L	58+00	60+50	LT	250.00	14	389
L	60+95	70+50	RT	955.00	15	1592
L	67+00	68+50	LT	150.00	15	250
L	71+50	75+50	LT	400.00	12	533
L	73+50	82+50	RT	900.00	17.5	1750
L	79+50	87+50	LT	800.00	13	1156
L	85+64	87+50	RT	186.00	17	351
TOTAL						16,128
SAY						16,130

GUARDRAIL REMOVAL

LINE	STATION	STATION	LOCATION	LENGTH
L	59+60.00	59+92.00	LT	40
TOTAL				40
SAY				45

1'-6" CURB & GUTTER

LINE	STATION	STATION	SIDE	GROSS LENGTH	DEDUCTIONS		NET LENGTH
					DRIVES	OTHERS	
L	16+22.43	21+71.08	MD.LT	553			553
L	25+24.06	28+82.52	MD.LT	359			359
L	32+45.64	38+35.46	MD.LT	589			589
L	41+22.57	46+34.36	MD.LT	511			511
L	49+30.55	58+39.70	MD.LT	919			919
L	62+28.11	64+53.52	MD.LT	225			225
L	65+85.00	67+93.69	MD.LT	210			210
L	71+33.38	75+21.89	MD.LT	389			389
L	78+93.26	79+90.45	MD.LT	97			97
L	80+21.86	81+21.86	MD.LT	101			101
L	16+22.43	21+71.08	MD.RT	560			560
L	25+24.03	30+08.41	MD.RT	485			485
L	32+45.64	38+35.67	MD.RT	590			590
L	41+22.39	46+38.92	MD.RT	518			518
L	49+30.55	58+39.70	MD.RT	912			912
L	62+28.11	64+53.58	MD.RT	225			225
L	65+53.43	67+93.69	MD.RT	242			242
L	71+33.38	75+21.89	MD.RT	389			389
L	78+82.74	79+90.45	MD.RT	108			108
TOTAL							7,985
SAY							7,990

MILLING ASPHALT PAVEMENT 1.5" DEPTH

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
EY20	35+59.49	38+62.46	CL	15739.39		1749
EY20	39+37.70	57+08.48	CL	14252.52		1584
EY20	5+50	7+09.77	CL	7726.33		858
EY20	7+76.87	13+42.96	CL	28170.35		3130
EY17	7+60	13+35	CL	36617.75		4069
TOTAL						11,390
SAY						11,500

CHAIN LINK RESET

LINE	STATION	STATION	SIDE	LENGTH
-EY10-	10+93.670	11+42.810		49.140
TOTAL				49.140
SAY				50

5/14/99

P:\05-JUL-2017 13:45-5935-RDY_SHT_03B.dgn