# ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	<u>TITLE</u>
901.50	ARROWS AND SHIELDS
901.70	SIGN STRINGERS AND SUPPORT SPACING
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

ITEM N	10.	SUMMARY OF QUANTITIES		
DESC. NO.	SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4025000000-E	904	CONTRACTOR FURNISHED, TYPE D SIGN	355.25	SF
4025000000-E	905	CONTRACTOR FURNISHED, TYPE E SIGN	130.19	SF
4025000000-E	906	CONTRACTOR FURNISHED, TYPE F SIGN	397.13	SF
4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	4324.13	LF
4096000000-N	904	SIGN ERECTION, TYPE D	28	EA
4102000000-N	904	SIGN ERECTION, TYPE E	130	EA
4108000000-N	904	SIGN ERECTION, TYPE F	20	EA
4116100000-N	905	SIGN ERECTION, RELOCATE, TYPE 'D' (GROUND MOUNTED)	8	EA
4116100000-N	906	SIGN ERECTION, RELOCATE, TYPE 'E' (GROUND MOUNTED)	23	EA
4116100000-N	907	SIGN ERECTION, RELOCATE, TYPE 'F' (GROUND MOUNTED)	1	EA
4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	4	EA
4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	116	EA
4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	23	EA
4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	24	EA
4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	4	EA

# GENERAL NOTES

- . ALL SIGNS FURNISHED BY CONTRACTOR
- . ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- . IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- . WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- . ALL EXISTING REGULATORY, WARNING AND GUIDE SIGNS WITHIN THE PROJECT LIMITS WHICH ARE
- NOT NOTED TO BE RETAINED OR REMOVED & RESET, SHALL BE DISPOSED OF BY THE CONTRACTOR. . WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL
- IMMEDIATELY FOLLOW THE REMOVAL. . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . ALL U-POSTS SHALL BE DRIVEN TO THE REQUIRED DEPTH (PER STD. SPEC. SECTION 903 (D)(1).
- AUGERING WILL NOT BE ALLOWED.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

# SHEET NO. SIGN-1A U-5935 DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PROJECT REFERENCE NO.

INTERNATIONAL

Michael Baker

# SIGN NUMBERING

#### NEW SIGNS

TYPE	D	SIGNS300	SERIES
TYPE	Ε	SIGNS400	SERIES
TYPE	F	SIGNS500	SERIES

EXISTING SIGNS

GROUND MOUNTED SIGNS RELOCATED TO NEW SUPPORTS......900 SERIES

### EXISTING SIGNING NOTES

- DISPOSAL OF SIGN SYSTEM, U-CHANNEL
- 2 DISPOSAL OF SIGN SYSTEM, WOOD
- 3 SIGN ERECTION, RELOCATE SIGN TYPE D
- SIGN ERECTION, RELOCATE SIGN TYPE E
- 5 SIGN ERECTION, RELOCATE SIGN TYPE F
- DISPOSAL OF SUPPORT, U-CHANNEL DISPOSAL OF SUPPORT. WOOD
- 8 DISPOSAL OF SIGN D, E, F

ROADWAY STD DRAWINGS GENERAL NOTES EXISTING SIGN NOTES SIGN NUMBERING SUMMARY OF QUANTITIES