STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
U-5935	X-1A

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

CROSS-SECTION SUMMARY

PHASE I CONSTRUCT -L- (MED) SUMMARY NO. 1

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+20.00	0	0
16+50.00	4	34
17+00.00	8	78
17+50.00	9	86
18+00.00	7	97
18+50.00	5	101
19+00.00	4	95
19+50.00	4	75
20+00.00	4	53
20+50.00	2	35
21+00.00	1	22
21+50.00	1	17
22+00.00	1	8
23+00.00	0	0
23+50.00	0	0
24+00.00	0	0
24+50.00	0	0
25+00.00	0	0
25+50.00	1	16
26+00.00	1	36
26+50.00	1	39
27+00.00	1	38
27+50.00	1	29
28+00.00	1	31
28+50.00	0	53
29+00.00	0	43
29+50.00	0	17
30+00.00	0	8
30+50.00	0	2
31+00.00	0	0
31+50.00	0	10
32+00.00	0	23
32+50.00	0	42
33+00.00	0	63
33+50.00	0	70
34+00.00	0	70
34+50.00	0	68
35+00.00	0	62
35+50.00	1	60
36+00.00	2	56
36+50.00	3	45
37+00.00	3	34
37+50.00	3	23
38+00.00	4	17
38+50.00	3	8
39+00.00	8	0
39+50.00	8	0
40+00.00	4	0
40+50.00	5	0
41+00.00	6	0
41+50.00	4	10
42+00.00	2	23
42+50.00	0	30

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
43+00.00	0	38
43+50.00	0	39
44+00.00	1	29
44+50.00	2	24
45+00.00	4	27
45+50.00	5	24
46+00.00	7	19
46+50.00	8	9
47+00.00	17	1
47+50.00	13	0
48+00.00	0	0
48+50.00	11	0
49+00.00	17	1
49+50.00	7	17
50+00.00	3	34
50+50.00	3	45
51+00.00	3	60
51+50.00	3	70
52+00.00	3	80
52+50.00	2	90
53+00.00	2	94
53+50.00	2	93
54+00.00	3	94
54+50.00	2	97
55+00.00	1	97
55+50.00	1	98
56+00.00	1	84
56+50.00	1	62
57+00.00	1	57
57+50.00	0	55
58+00.00	0	49
58+50.00	0	36
59+00.00	1	22
59+50.00	1	14
60+00.00	0	4

SUMMARY NO. 2 (MED)

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
60+00.00	0	0
60+50.00	0	4
61+00.00	0	0
62+00.00	0	0
62+50.00	1	15
63+00.00	2	27
63+50.00	3	24
64+00.00	3	24
64+50.00	2	30
65+00.00	1	28
65+50.00	0	9
66+00.00	0	0
66+50.00	0	9
67+00.00	0	17

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
67+50.00	0	15
68+00.00	0	7
68+50.00	0	0
69+00.00	0	6
69+50.00	0	13
70+00.00	0	16
70+50.00	0	19
71+00.00	0	22
71+50.00	0	30
72+00.00	0	44
72+50.00	1	55
73+00.00	1	51
73+50.00	0	38
74+00.00	0	29
74+50.00	1	27
75+00.00	0	31
75+50.00	0	17
76+00.00	0	1
76+50.00	0	1
77+00.00	0	0
77+50.00	0	0
78+00.00	0	0
78+50.00	0	0
79+00.00	0	21
79+50.00	1	40
80+00.00	1	28
80+50.00	2	13
81+00.00	2	8
81+50.00	2	6
82+00.00	1	2
82+50.00	0	0
83+00.00	0	0
83+50.00	0	0
84+50.00	0	0
85+00.00	0	0
85+50.00	0	0
86+00.00	0	0
86+50.00	0	0
87+00.00	0	0
87+50.00	4	2
87+55.00	1	0

SUMMARY NO. 3 (LT)

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+20.00	0	0
16+50.00	4	7
17+00.00	6	31
17+50.00	5	43
18+00.00	2	56
18+50.00	0	74
19+00.00	0	83
19+50.00	0	77

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+00.00	0	33
21+00.00	3	18
21+50.00	5	36
22+00.00	5	38
22+50.00	3	20
23+50.00	0	0
24+00.00	0	0
24+50.00	5	13
25+00.00	12	29
25+50.00	13	32
26+00.00	12	34
26+50.00	7	18
27+00.00	2	0
27+50.00	4	24
28+00.00	5	52
28+50.00	4	53
29+00.00	3	74
29+50.00	3	101
30+00.00	3	94
30+50.00	1	43
31+50.00	1	22
32+00.00	1	44
32+50.00	1	43
33+00.00	1	42
33+50.00	2	41
34+00.00	1	20
34+50.00	2	17
35+00.00	2	17
36+00.00	1	32
36+50.00	3	63
37+00.00	3	51
37+50.00	4	55
38+00.00	4	71
38+50.00	2	36
39+00.00	2	23
39+50.00	2	23
40+00.00	0	0
40+50.00	3	37
41+00.00	4	64
41+50.00	3	78
42+00.00	1	107
42+50.00	0	124
43+00.00	0	67
45+00.00	0	63
45+50.00	0	115
46+00.00	0	51
47+00.00	0	0
47+50.00	0	0
48+00.00	0	0
49+00.00	1	28
49+50.00	2	61
50+00.00	1	71
50+50.00	1	73