

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.05.06.10921.1,etc.	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW	AGGREGATE SHOULDER BORROW (ASB)	SHOULDER GRADING	INCIDENTAL STONE BASE	1 1/2" MILLING	0" TO 1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJUST MANHOLES	ADJUST METER OR VALVE BOX	TEMPORARY SILT FENCE	WATTLE	SEED & MULCHING	INDUCTIVE LOOP SAWCUT		
																												MI	FT
2018CPT.05.06.10921.1	Wake	1	NC 55 - HWY	HARNETT CO TO US 401	1	2	NO	NO	4.82	30-68	436	419	8.73	109	110,926		3,146		10,089	595	110			317	800	3.17	1,632		
TOTAL FOR MAP NO. 1									4.82		436	419	8.73	109	110,926		3,146		10,089	595	110			317	800	3.17	1,632		
TOTAL FOR PROJ NO. 2018CPT.05.06.10921.1									4.82		436	419	8.73	109	110,926		3,146		10,089	595	110			317	800	3.17	1,632		
2018CPT.05.06.20921.1	Wake	2	SR 1004 W GARNER RD	SR 2713 - VANDORA SPRINGS RD TO GROVE CREEK LN	2	2	NO	NO	1.92	24-46	282		2.82	70		2,402	1,757	3,855		231	20	6	6	204	520	2.05	3,131		
TOTAL FOR MAP NO. 2									1.92		282		2.82	70		2,402	1,757	3,855		231	20	6	6	204	520	2.05	3,131		
2018CPT.05.06.20921.1	Wake	3	SR 1399 - JAMES SLAUGHTER RD	NC 55 - N BROAD ST TO SR 1393 - BASS LAKE RD	2	2	NO	NO	1.98	23-40	108	155	2.70	27		2,962	788	2,964		178	100		3	78	200	0.78	391		
TOTAL FOR MAP NO. 3									1.98		108	155	2.70	27		2,962	788	2,964		178	100		3	78	200	0.78	391		
2018CPT.05.06.20921.1	Wake	4	SR 1401 - STEWART RD	SR 1400 - BALLENTINE DAIRY RD TO NORTH ST	2	2	NO	NO	1.55	18-44	99	142	2.47	25		1,472	1,263	2,181		131	60		7	72	180	0.72	602		
TOTAL FOR MAP NO. 4									1.55		99	142	2.47	25		1,472	1,263	2,181		131	60		7	72	180	0.72	602		
2018CPT.05.06.20921.1	Wake	5	SR 1400 - STEWART RD	SR 1399 - JAMES SLAUGHTER RD TO SR 1400 - BALLENTINE DAIRY RD SKIPPING OVER NEW WIDENED SECTION	2	2	NO	NO	0.25	20-21	25	24	0.50	7			330	303		18	40			18	50	0.18			
TOTAL FOR MAP NO. 5									0.25		25	24	0.50	7			330	303		18	40			18	50	0.18			
2018CPT.05.06.20921.1	Wake	6	SR 2541 - WESTON RD	SR 1004 - W GARNER RD TO END OF MAINT (MEADOWBROOK DR)	3	2	NO	NO	0.94	20-26	188		1.88	47	11,029		566	1,029		62	60			137	350	1.37			
TOTAL FOR MAP NO. 6									0.94		188		1.88	47	11,029		566	1,029		62	60			137	350	1.37			
2018CPT.05.06.20921.1	Wake	7	SR 2703 - NEW BETHEL CHURCH RD	DEAD END TO .62 MILES EAST OF NC 50 - BENSON RD SKIPPING NEW WIDENING	2	2	NO	NO	2.52	20-24	274	175	4.56	68		1,123	756	2,758		165	40			199	500	1.99			
TOTAL FOR MAP NO. 7									2.52		274	175	4.56	68		1,123	756	2,758		165	40			199	500	1.99			
2018CPT.05.06.20921.1	Wake	8	SR 2706 - CLIFFORD RD	SR 2703 - NEW BETHEL CHURCH RD TO JT AT .2 MILES WEST OF SR 2547 - HEBRON CHURCH RD	2	2	NO	NO	0.84	20-21	100		1.68	25			200	905		54	40			73	190	0.73			
TOTAL FOR MAP NO. 8									0.84		100		1.68	25			200	905		54	40			73	190	0.73			
2018CPT.05.06.20921.1	Wake	9	SR 2710 - AVERSBORO RD	SR 2794 - TOWN HALL PROJECT PAVEMENT JOINTS TO SR 2812 - TIMBER DR	3	4	NO	NO	1.3	42-62	7		0.07	2	33,080		2,759	3,169		190	60			6	20	0.05	112		
TOTAL FOR MAP NO. 9									1.3		7		0.07	2	33,080		2,759	3,169		190	60			6	20	0.05	112		
2018CPT.05.06.20921.1	Wake	10	SR 2727 - SAULS RD/CROWDER RD	NC 42 TO SR 2728 - RAND RD	2	2	NO	NO	4.77	24-32	954		9.54	239			2,182	6,228		374	120			694	1,740	6.94	396		
TOTAL FOR MAP NO. 10									4.77		954		9.54	239			2,182	6,228		374	120			694	1,740	6.94	396		
2018CPT.05.06.20921.1	Wake	11	SR 2737 - PAGAN RD	SR 2727 - SAULS RD TO SR 2736 - ROCK SERVICE STATION RD	2	2	NO	NO	1.87	20-21	374		3.70	94			1,369	2,083		125	60			272	690	2.72			
TOTAL FOR MAP NO. 11									1.87		374		3.70	94			1,369	2,083		125	60			272	690	2.72			
2018CPT.05.06.20921.1	Wake	12	SR 1402 - BROAD ST	NORTH ST TO 0.08 MI EAST OF COTTON FARM DR	3	2	NO	NO	0.31	20-23	31		0.31	8	4,183		575	420		25	75			23	60	0.22			
TOTAL FOR MAP NO. 12									0.31		31		0.31	8	4,183		575	420		25	75			23	60	0.22			
TOTAL FOR PROJ NO. 2018CPT.05.06.20921.1									18.25		2,442	496	30.23	612	48,292	7,959	12,545	25,895		1,553	675	6	16	1,776	4,500	17.75	4,632		
GRAND TOTAL									23.07		2,878	915	38.96	721	159,218	7,959	15,691	25,895	10,089	2,148	785	6	16	2,093	5,300	20.92	6,264		