PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.05.06.10921.1,etc.	11	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	4" X 90 M WHITE THERMO	4" X 120 M YELLOW THERMO	4" X 120 M WHITE THERMO	8" X 90 M YELLOW THERMO	8" X 90 M WHITE THERMO	8" X 120 M WHITE THERMO	12" X 90 M YELLOW THERMO	12" X 90 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO MSG ONLY 120 M	THERMO MSG SCHOOL 120 M	THERMO LT ARROW 90 M	THERMO RT ARROW 90 M	THERMO STR & RT ARROW 90 M	THERMO STR ARROW 90 M	THERMO STR & LT ARROW 90 M	4" YELLOW COLD APPLIED PLASTIC, TYPE II	4" WHITE COLD APPLIED PLASTIC, TYPE II	4" WHITE PAINT	4" YELLOW PAINT	8" WHITE PAINT	12" YELLOW PAINT	24" WHITE PAINT	PAINT MSG SCHOOL	PAINT MSG ONLY	PAINT LT ARROW	PAINT RT ARROW	PAINT STR & RT ARROW	PAINT STR ARROW	4" LINE REMOVAL	SNOW PLOWABLE MARKERS
							MI	FT	SF	LS	LF	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF	EA
2018CPT.05.06.10921.1	Wake	1	NC 55 - HWY	HARNETT CO TO US 401	1	2	4.82	30-68	534	0.28	51,863	42,995	3,885				1,350		651			159	53	19	29				55,748	42,467		1,336	644			159	52	19	29		728
TOTAL FOR MAP NO. 1							**4.82**		**534**	**0.28**	**51,863**	**42,995**	**3,885**				**1,350**		**651**			**159**	**53**	**19**	**29**				**55,748**	**42,467**		**1,336**	**644**			**159**	**52**	**19**	**29**		**728**
TOTAL FOR PROJ NO. 2018CPT.05.06.10921.1							**4.82**		**534**	**0.28**	**51,863**	**42,995**	**3,885**				**1,350**		**651**			**159**	**53**	**19**	**29**				**55,748**	**42,467**		**1,336**	**644**			**159**	**52**	**19**	**29**		**728**
											46,880						**1,350**					**260**						**98,215**							**259**					
2018CPT.05.06.20921.1	Wake	2	SR 1004 W GARNER RD	SR 2713 - VANDORA SPRINGS RD TO GROVE CREEK LN	2	2	1.92	24-46	126	0.10	19,060	27,553	1,578	175	340		511	65	229	4		24	7	2	7	1															
TOTAL FOR MAP NO. 2							**1.92**		**126**	**0.10**	**19,060**	**27,553**	**1,578**	**175**	**340**		**511**	**65**	**229**	**4**		**24**	**7**	**2**	**7**	**1**															
2018CPT.05.06.20921.1	Wake	3	SR 1399 - JAMES SLAUGHTER RD	NC 55 - N BROAD ST TO SR 1393 - BASS LAKE RD	2	2	1.98	23-40	222	0.08	20,626	20,072	853	333		89	35		60			13	1																		
TOTAL FOR MAP NO. 3							**1.98**		**222**	**0.08**	**20,626**	**20,072**	**853**	**333**		**89**	**35**		**60**			**13**	**1**																		
2018CPT.05.06.20921.1	Wake	4	SR 1401 - STEWART RD	SR 1400 - BALLENTINE DAIRY RD TO NORTH ST	2	2	1.55	18-44	184	0.06	11,656	17,458	325	271					150			10	2	2	1																
TOTAL FOR MAP NO. 4							**1.55**		**184**	**0.06**	**11,656**	**17,458**	**325**	**271**					**150**			**10**	**2**	**2**	**1**																
2018CPT.05.06.20921.1	Wake	5	SR 1400 - STEWART RD	SR 1399 - JAMES SLAUGHTER RD TO SR 1400 - BALLENTINE DAIRY RD SKIPPING OVER NEW WIDENED SECTION	2	2	0.25	20-21	28	0.02	2,690	1,482	30																												
TOTAL FOR MAP NO. 5							**0.25**		**28**	**0.02**	**2,690**	**1,482**	**30**																												
2018CPT.05.06.20921.1	Wake	6	SR 2541 - WESTON RD	SR 1004 - W GARNER RD TO END OF MAINT (MEADOWBROOK DR)	3	2	0.94	20-26	105	0.03	10,114	9,926	18																												
TOTAL FOR MAP NO. 6							**0.94**		**105**	**0.03**	**10,114**	**9,926**	**18**																												
2018CPT.05.06.20921.1	Wake	7	SR 2703 - NEW BETHEL CHURCH RD	DEAD END TO .62 MILES EAST OF NC 50 - BENSON RD SKIPPING NEW WIDENING	2	2	2.52	20-24	283	0.09	27,115	27,115	110														842	842												1,684	
TOTAL FOR MAP NO. 7							**2.52**		**283**	**0.09**	**27,115**	**27,115**	**110**														**842**	**842**												**1,684**	
2018CPT.05.06.20921.1	Wake	8	SR 2706 - CLIFFORD RD	SR 2703 - NEW BETHEL CHURCH RD TO JT AT .2 MILES WEST OF SR 2547 - HEBRON CHURCH RD	2	2	0.84	20-21	94	0.03	8,870	6,750	33						50		6																				
TOTAL FOR MAP NO. 8							**0.84**		**94**	**0.03**	**8,870**	**6,750**	**33**						**50**		**6**																				
2018CPT.05.06.20921.1	Wake	9	SR 2710 - AVERSBORO RD	SR 2794 - TOWN HALL PROJECT PAVEMENT JOINTS TO SR 2812 - TIMBER DR	3	4	1.3	42-62	146	0.08	480	12,158	3,432		270	200			360	12	12	6	4		3				3,432	12,638	470		360	12	12	6	4		3		
TOTAL FOR MAP NO. 9							**1.3**		**146**	**0.08**	**480**	**12,158**	**3,432**		**270**	**200**			**360**	**12**	**12**	**6**	**4**		**3**				**3,432**	**12,638**	**470**		**360**	**12**	**12**	**6**	**4**		**3**		
2018CPT.05.06.20921.1	Wake	10	SR 2727 - SAULS RD/CROWDER RD	NC 42 TO SR 2728 - RAND RD	2	2	4.77	24-32	534	0.17	50,372	44,130	997				102		61			1																			
TOTAL FOR MAP NO. 10							**4.77**		**534**	**0.17**	**50,372**	**44,130**	**997**				**102**		**61**			**1**																			
2018CPT.05.06.20921.1	Wake	11	SR 2737 - PAGAN RD	SR 2727 - SAULS RD TO SR 2736 - ROCK SERVICE STATION RD	2	2	1.87	20-21	210	0.06	19,144	16,235	244																												
TOTAL FOR MAP NO. 11							**1.87**		**210**	**0.06**	**19,144**	**16,235**	**244**																												
2018CPT.05.06.20921.1	Wake	12	SR 1402 - BROAD ST	NORTH ST TO 0.08 MI EAST OF COTTON FARM DR	3	2	0.31	20-23	35	0.01	3,336	3,274																													
TOTAL FOR MAP NO. 12							**0.31**		**35**	**0.01**	**3,336**	**3,274**																													
TOTAL FOR PROJ NO. 2018CPT.05.06.20921.1							**18.25**		**1,967**	**0.73**	**173,463**	**186,153**	**7,620**	**779**	**610**	**289**	**648**	**65**	**910**	**16**	**18**	**54**	**14**	**4**	**11**	**1**	**842**	**842**	**3,432**	**12,638**	**470**		**360**	**12**	**12**	**6**	**4**		**3**	**1,684**	
												193,773		**1,389**			**713**			**34**			**84**				**1,684**		**16,070**					**24**			**13**				
GRAND TOTAL							**23.07**		**2,501**	**1.00**	**225,326**	**229,148**	**11,505**	**779**	**610**	**289**	**1,998**	**65**	**1,561**	**16**	**18**	**213**	**67**	**23**	**40**	**1**	**842**	**842**	**59,180**	**55,105**	**470**	**1,336**	**1,004**	**12**	**12**	**165**	**56**	**19**	**32**	**1,684**	**728**
												240,653		**1,389**			**2,063**			**34**			**344**				**1,684**		**114,285**					**24**			**272**				