PROJ. REFERENCE NO.	SHEET NO.
B-5347	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	
12+16.24	0	0	
12+50.00	2	48	
12+56.50	1	21	
13+00.00	2	305	
13+50.00	0	581	(PHASE 1)
14+00.00	0	663	
14+50.00	0	612	
15+00.00	0	394	
15+50.00	0	228	
16+00.00	3	125	
16+44.03	2	18	

NOTE: Approximate quantities only. Unclassified Excavation, Fine Grading, Clearing and Grubbing, and Removal of Existing Pavement will be paid for at the contract lump sum price for " Grading."

Station L	Uncl. Exc. (cu. yd.)	Undercut Exc. (cu. yd.)	Embt (cu. yd.)	
12+56.50	0		0	
13+00.00	8		6	
13+50.00	15		25	
14+00.00	9	0	319	(PHASE 2)
14+50.00	15	300	314	
15+00.00	12		21	
15+50.00	1		6	

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	
12+16.24	0	0	
12+50.00	60	3	
12+56.50	26	1	
13+00.00	336	2	
13+50.00	619	0	
14+00.00	620	0	(PHASE 3)
14+50.00	517	0	
15+00.00	433	0	
15+50.00	368	1	
16+00.00	202	5	
16+44.03	24	3	