PROJECT REFERENCE NO.	SHEET NO.
W-5704A&B	EC-11/ CONST.4

SEPI ENGINEERING & CONSTRUCTION
1025 Wade Avenue
Raleigh, NC 27605
Tel:919-789-9977
Fax:919-789-9591
License: C-2197

EROSION CONTROL PLAN FOR MEDIAN CONSTRUCTION ONLY

NAD 83/NA 2011

GRAPHIC SCALE
50 25 0 50 100
PLANS

INLET PROTECTION TYPE TO BE DETERMINED BY ENGINEER

-L-
PI Sta. 27+34.76
△ = 18° 58' 02.4" (RT)
D = 1° 00' 00.0"
L = 1,896.73'
T = 957.12'
R = 5,729.58'

REVISIONS
8/17/99

POT Sta. 10+00.00

BEGIN PROJECT W-5704B IMPROVEMENTS
-L- POT STA 16+17.92

MATCHLINE -L- STA. 22+00.00
SEE SHEET 5

PC Sta. 17+77.63

TBM #1
N - 694468
E - 2154424
ELEV = 287.12'
-BL- STA. 11+69.00 117' RT
YELLOW BENCH TIE IN 12" MAPLE

DETAIL 1
FALSE SUMP
(Not to Scale)



Ditch Grade	L	Ditch Grade	L
0.0% To 2.0%	20'	Over 4.0% To 6.0%	40'
Over 2.0% To 4.0%	30'	Over 6.0%	50'

FROM STA. 21+57 TO STA. 21+97 -L- MED

FINAL PHASE
EROSION CONTROL FOR CONSTRUCTION SHEET 4

$$$$USERNAME$$$$ $$$$SYSTIME$$$$