PROJECT REFERENCE NO. U-4751 Sig. 12.4

## ALTERNATE PHASING ACTIVATION DETAIL

TO RUN ALT, PHASING DURING <u>COORDINATION</u> — SELECT ALL PAGE CHANGES (AS SHOWN BELOW) WITHIN COORDINATION PLAN PROGRAMMING.

TO RUN ALT. PHASING DURING FREE RUN — PROGRAM PAGE CHANGES (SHOWN BELOW) IN SEPARATE TIME OF DAY EVENTS. IF PAGE 1 IS USED, NO EVENT PROGRAMMING IS NECESSARY FOR THAT PARTICULAR PAGE.

PHAS I NG	INPUTS PAGE	OVERLAPS PAGE
ACTIVE PAGES REQUIRED TO RUN <u>DEFAULT PHASIN</u> G	1	1
ACTIVE PAGES REQUIRED TO RUN <u>ALTERNATE PHASING</u>	2	2

NOTE: PAGES NOT SHOWN (i.e. sequence, phase control, etc.) SHOULD REMAIN AS '1', OR AS DEFINED BY TIMING ENGINEER.

IMPORTANT: IF ALT. PHASING IS USED DURING FREE RUN AND COORDINATION, DO NOT OPERATE TIME OF DAY PAGE CHANGE EVENTS CONCURRENTLY WITH COORDINATION PLAN EVENTS IN THE EVENT SCHEDULER. (EX, FREE RUN PAGE CHANGE EVENT SHOULD END BEFORE COORDINATION PLAN EVENT STARTS AND VICE-VERSA).

## ALTERNATE PHASING PAGE CHANGE SUMMARY

THE FOLLOWING IS A SUMMARY OF WHAT TAKES PLACE WHEN THESE OVERLAP/INPUT PAGE CHANGES ACTIVATE TO CALL THE "ALTERNATE PHASING":

OVERLAPS PAGE 2: Modifies overlap parent phases

for heads 71 to


run protected turns only.

INPUTS PAGE 2: Reduces delay time for phase 7 call on loop 7A to 0 seconds.

> THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 03-1103 DESIGNED: Aprıl 2017 SEALED: REVISED:

## DOCUMENT NOT CONSIDERED FINAL **UNLESS ALL SIGNATURES COMPLETED**

New Installation - Final Design (Electrical Detail Sheet 4 of 4)



## Northbound SR 1409 (Military Cutoff Road) Lendire Road

Wilmington Division 03 New Hanover County PLAN DATE: April 2017 REVIEWED BY: MB Toth

PREPARED BY: AM Encarnacion REVIEWED BY: REVISIONS INIT. DATE

6/6/2017 Melissa B. Toth

SIG. INVENTORY NO. 03-1103

SEAL

025892

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 160 RALEIGH, NORTH CAROLINA 27609 (919) 876-6888 NCBEES #F-0326