


EDI MODEL 2018ECLIP-NC CONFLICT MONITOR

PROGRAMMING DETAIL

(remove jumpers and set switches as shown)


REMOVE DIODE JUMPERS 1-5, 1-6, 2-5, 2-6, 3-7, 3-8, 3-10, 3-12, 4-7, 4-8, 4-10, 4-12, 7-10, 7-12, 8-10, 8-12, and 10-12.



REMOVE JUMPERS AS SHOWN

NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
- Ensure that Red Enable is active at all times during normal operation.
- Integrate monitor with Ethernet network in cabinet.



■ = DENOTES POSITION OF SWITCH

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Program phases 4 and 8 for Dual Entry.
- Enable Simultaneous Gap-Out for all Phases.
- Program phases 2 and 6 for volume density operation.
- Program controller to start up in phase 2 Green and 6 Green.
- The cabinet and controller are part of the Concord Mills Blvd. CLS.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332 W/AUX
 SOFTWARE.....ECONOLITE ASC/3-2070
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S1,S2,S4,S5,S7,S8,S10,S11,
 AUX S2,AUX S5
 PHASES USED.....1,2,3,4,5,6,7,8
 OVERLAP "A".....NOT USED
 OVERLAP "B".....*
 OVERLAP "C".....NOT USED
 OVERLAP "D".....*
 * See overlap programming detail on sheet 2


SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6	
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18	
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE	
SIGNAL HEAD NO.	11,12	82,83	21,22,23	NU	31*	41,42	NU	51	61,62	NU	71*	81,82,83	NU	NU	31*	NU	NU	71*	NU
RED		128			101			134			107								
YELLOW		129		*	102			135		*	108								
GREEN		130			103			136			109								
RED ARROW	125							131							A124				A101
YELLOW ARROW	126	126						132							A125				A102
FLASHING YELLOW ARROW															A126				A103
GREEN ARROW	127	127			118			133			124								

NU = Not Used
 * Denotes install load resistor. See load resistor installation detail this sheet.
 * See pictorial of head wiring in detail this sheet.

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S
 FS = FLASH SENSE
 ST = STOP TIME


INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND TIME	DELAY TIME	DETECTOR TYPE
1A	TB2-1,2	I1U	56	1	1	YES			S
1B	TB2-3,4	I1L	56	1	1	YES			S
1C	TB2-5,6	I2U	39	2	1	YES		15	S
1D	TB2-7,8	I2L	43	12	1	YES		15	S
2A	TB2-9,10	I3U	63	32	2	YES			S
2B	TB2-11,12	I3L	76	42	2	YES			S
3A ¹	TB4-5,6	I5U	58	3	3	YES		15	S
		J8U	50	28	8	YES			S
4A	TB4-9,10	I6U	41	4	4	YES		10	S
5A	TB3-1,2	J1U	55	5	5	YES			S
6B	TB3-7,8	J2L	44	16	6	YES			S
6C	TB3-9,10	J3U	64	36	6	YES			S
7A ²	TB5-5,6	J5U	57	7	7	YES		15	S
		I8U	49	24	4	YES		3	S
8A	TB5-9,10	J6U	42	8	8	YES			S

¹Add jumper from I5-W to J8-W, on rear of input file.
²Add jumper from J5-W to I8-W, on rear of input file.

Remove jumper from J1-W to I4-W, on rear of input file.

INPUT FILE POSITION LEGEND: J2L




SPECIAL DETECTOR NOTE

Remove all video detection equipment that was installed during the Temporary Design - Phase I construction.

FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)




LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown below)

ACCEPTABLE VALUES

VALUE (ohms)	WATTAGE
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



REMOVE PHASE 1 AND PHASE 5 RESISTORS, AND MOVE RESISTOR FROM RED TERMINAL TO YELLOW TERMINAL FOR PHASE 3 AS SHOWN.

Electrical Detail - Temp Design 2 - Phase II - Sheet 1 of 2

SR 2894 (Concord Mills Blvd.) at Concord Mills Entrance/Bexley Way

Prepared In the Offices of: *Engineering & Construction Services, Inc.*

750 N. Greenfield Pkwy, Garner, NC 27529

Division 10 Cabarrus County Concord

PLAN DATE: September 2017 REVIEWED BY: *S. Armstrong*

PREPARED BY: *S. Armstrong* REVIEWED BY: *S. Armstrong*

REVISIONS: _____ INIT. DATE

DocuSigned by: *Stephen M. Little* 9/26/2017

SIG. INVENTORY NO. 10-1733T2

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED