

COMPUTED BY: SWT DATE: 8/11/17
 CHECKED BY: SSL DATE: 8/11/17

(2-16-16)

PROJECT NO.
R-5703

SHEET NO.
3G-1

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
	CONTINGENCY			SD	3000
				TOTAL LF:	3000

*UD = Underdrain
 *BD = Blind Drain
 *SD = Subsurface Drain

LINE	Station	Station	Aggregate Type* ASU/AST	Aggregate Thickness INCHES	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
Y1	15+25	24+75	ASU		750	1400	800		
Y1	33+25	44+95	ASU		850	1600	950		
Y8	51+25	52+75	ASU		70	50	250		
Y8	53+75	54+25	ASU		70	50	250		
Y8	55+25	55+75	ASU		40	50	250		
Y8	56+75	60+75	ASU		1250	2500	1750		
Y9	10+75	11+25	ASU		70	150	250		
	CONTINGENCY				500	1000	500		500
			TOTAL CY/TONS/SY:		3600	6800	5000**	0	500

*ASU = Aggregate Subgrade

*AST = Aggregate Stabilization

**Total square yards of "Geotextile for Soil Stabilization" is only the estimated quantity for ASU/AST and may only represent a portion of the geotextile quantity shown in the Item Sheets of the Proposal.

SUMMARY OF BRIDGE WAITING PERIODS

Bridge Description	End Bent	MONTHS
No. 208 on -L- over -Y1-	1 and 2	2
No. 209 on -L- over -Y1-	1 and 2	2
No. 210 on -L- over -Y3-	1 and 2	2
No. 211 on -L- over -Y3-	1 and 2	2
No. 212 on -L- over -Y4-	1 and 2	1
No. 213 on -L- over -Y4-	1 and 2	1
No. 214 on -L- over Stonyton Creek	1 and 2	1
No. 215 on -L- over Stonyton Creek	1 and 2	1
No. 216 on -L- over -Y6-	1 and 2	1
No. 217 on -L- over -Y6-	1 and 2	1
No. 218 on -L- over -Y7-	1 and 2	1
No. 219 on -L- over -Y7-	1 and 2	1
No. 220 on -L- over -Y8-	1 and 2	1
No. 221 on -L- over -Y8-	1 and 2	1