



EXISTING SIGNAL AND SIGNAL CABINET TO BE REMOVED

**NOTES:**

\* NOTIFY JIM EVANS OF NCDOT DIVISION 2 AT (252) 439-2800 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY JIM EVANS AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS UP AND OPERATIONAL.

\* CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

 <b>Michael Baker INTERNATIONAL</b> 8000 Regency Parkway, Suite 600 Cary, North Carolina 27518 Phone: 919-463-5488 NC License No.: F-1084 MBAKERINTL.COM	Prepared in the Offices of:  Kelly M. Cory 750 N. Greenfield Pkwy., Garner, NC 27529	<b>COMMUNICATIONS CABLE SPLICE DETAILS</b>		 Kelly M. Cory 8/17/2017
		Division 2    Lenoir County    Kinston	PLAN DATE: August 2017    REVIEWED BY: W M Ruhsam	
NOT TO SCALE		CADD Filename:		