

SEE SHEET 3 FOR PLAN SHEET LAYOUT
AT TIME OF INVESTIGATION

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	R-5703	1	59

CONTENTS

SHEET	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	PLAN SHEET
4 - 11	PROFILES
12 - 31	BORING LOGS
32 - 59	LABORATORY TEST RESULTS

**STRUCTURE
SUBSURFACE INVESTIGATION**

COUNTY LENOIR

PROJECT DESCRIPTION C.F. HARVEY PARKWAY AND NC 58 TO
INTERSECTION OF NC 11 AND GRANGER STATION ROAD
GRADING, PAVING, DRAINAGE, STRUCTURES AND SIGNALS

SITE DESCRIPTION BRIDGE NO. 214 AND NO. 215 ON -L-
(FELIX HARVEY PARKWAY) OVER STONYTON CREEK

INVENTORY

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF PREPARING THE SCOPE OF WORK TO BE INCLUDED IN THE REQUEST FOR PROPOSAL. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

SOIL AND ROCK BOUNDARIES WITHIN A BOREHOLE ARE BASED ON GEOTECHNICAL INTERPRETATION UNLESS ENCOUNTERED IN A SAMPLE. INTERPRETED BOUNDARIES MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN SAMPLED STRATA AND BOREHOLE INFORMATION MAY NOT NECESSARILY REFLECT ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTES:

1. THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
2. BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

S. LANEY

K. HILL

S. MITCHELL

S. TIERNAN

C. CHANDLER

F. WRIGHT

E. BLONSHINE

J. PEELE

M. RAWLS

INVESTIGATED BY S&ME, INC.

DRAWN BY C. CHANDLER

CHECKED BY S. MITCHELL

SUBMITTED BY S&ME, INC.

DATE MAY 2017

REFERENCE: R-5703

PROJECT: 46375



[Handwritten Signature]

9-15-17

SIGNATURE


DATE

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**


SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOGGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (ROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SRC) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
<table border="1"> <tr> <th colspan="2">GENERAL CLASS.</th> <th colspan="3">GRANULAR MATERIALS (≤ 35% PASSING #200)</th> <th colspan="3">SILT-CLAY MATERIALS (> 35% PASSING #200)</th> <th colspan="2">ORGANIC MATERIALS</th> </tr> <tr> <td>A-1</td> <td>A-2</td> <td>A-3</td> <td>A-4</td> <td>A-5</td> <td>A-6</td> <td>A-7</td> <td>A-1, A-2</td> <td>A-4, A-5</td> <td></td> </tr> <tr> <td>A-1-a</td> <td>A-1-b</td> <td>A-2-4</td> <td>A-2-5</td> <td>A-2-6</td> <td>A-2-7</td> <td>A-3</td> <td>A-3</td> <td>A-6, A-7</td> <td></td> </tr> <tr> <td>SYMBOL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>% PASSING #10 #40 #200</td> <td>50 MX 30 MX 15 MX</td> <td>50 MX 25 MX 10 MX</td> <td>51 MN 35 MX 35 MX</td> <td>35 MX 35 MX 35 MX</td> <td>36 MN 36 MN 36 MN</td> <td>36 MN 36 MN 36 MN</td> <td>GRANULAR SOILS</td> <td>SILT-CLAY SOILS</td> <td>MUCK, PEAT</td> </tr> <tr> <td>MATERIAL PASSING #40 LL PI</td> <td>- 6 MX</td> <td>- NP</td> <td>40 MX 41 MN 10 MX 11 MN</td> <td>40 MX 41 MN 10 MX 11 MN</td> <td>40 MX 41 MN 10 MX 11 MN</td> <td>40 MX 41 MN 10 MX 11 MN</td> <td>SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER</td> <td>HIGHLY ORGANIC SOILS</td> <td></td> </tr> <tr> <td>GROUP INDEX</td> <td>0</td> <td>0</td> <td>0</td> <td>4 MX</td> <td>8 MX</td> <td>12 MX</td> <td>16 MX</td> <td>NO MX</td> <td></td> </tr> <tr> <td>USUAL TYPES OF MAJOR MATERIALS</td> <td>STONE FRAGS. GRAVEL, AND SAND</td> <td>FINE SAND</td> <td>SILTY OR CLAYEY GRAVEL AND SAND</td> <td>SILTY SOILS</td> <td>CLAYEY SOILS</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>GEN. RATING AS SUBGRADE</td> <td colspan="3">EXCELLENT TO GOOD</td> <td colspan="2">FAIR TO POOR</td> <td>FAIR TO POOR</td> <td>POOR</td> <td>UNSATURABLE</td> <td></td> </tr> <tr> <td colspan="10">PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30</td> </tr> </table>										GENERAL CLASS.		GRANULAR MATERIALS (≤ 35% PASSING #200)			SILT-CLAY MATERIALS (> 35% PASSING #200)			ORGANIC MATERIALS		A-1	A-2	A-3	A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5		A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-3	A-3	A-6, A-7		SYMBOL										% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX 10 MX	51 MN 35 MX 35 MX	35 MX 35 MX 35 MX	36 MN 36 MN 36 MN	36 MN 36 MN 36 MN	GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT	MATERIAL PASSING #40 LL PI	- 6 MX	- NP	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER	HIGHLY ORGANIC SOILS		GROUP INDEX	0	0	0	4 MX	8 MX	12 MX	16 MX	NO MX		USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS					GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD			FAIR TO POOR		FAIR TO POOR	POOR	UNSATURABLE		PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30										<table border="1"> <tr> <th colspan="2">MINERALOGICAL COMPOSITION</th> </tr> <tr> <td colspan="2">MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.</td> </tr> <tr> <th colspan="2">COMPRESSIBILITY</th> </tr> <tr> <td>SLIGHTLY COMPRESSIBLE</td> <td>LL < 31</td> </tr> <tr> <td>MODERATELY COMPRESSIBLE</td> <td>LL = 31 - 50</td> </tr> <tr> <td>HIGHLY COMPRESSIBLE</td> <td>LL > 50</td> </tr> <tr> <th colspan="2">PERCENTAGE OF MATERIAL</th> </tr> <tr> <td>ORGANIC MATERIAL</td> <td>GRANULAR SOILS</td> <td>SILT - CLAY SOILS</td> <td>OTHER MATERIAL</td> </tr> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE 1 - 10%</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE 10 - 20%</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME 20 - 35%</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>> 10%</td> <td>> 20%</td> <td>HIGHLY 35% AND ABOVE</td> </tr> <tr> <th colspan="4">GROUND WATER</th> </tr> <tr> <td></td> <td colspan="3">WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING</td> </tr> <tr> <td></td> <td colspan="3">STATIC WATER LEVEL AFTER _____ HOURS</td> </tr> <tr> <td></td> <td colspan="3">PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA</td> </tr> <tr> <td></td> <td colspan="3">SPRING OR SEEP</td> </tr> <tr> <th colspan="4">MISCELLANEOUS SYMBOLS</th> </tr> <tr> <td></td> <td colspan="3">ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</td> </tr> <tr> <td></td> <td colspan="3">SOIL SYMBOL</td> </tr> <tr> <td></td> <td colspan="3">ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</td> </tr> <tr> <td></td> <td colspan="3">INFERRED SOIL BOUNDARY</td> </tr> <tr> <td></td> <td colspan="3">INFERRED ROCK LINE</td> </tr> <tr> <td></td> <td colspan="3">ALLUVIAL SOIL BOUNDARY</td> </tr> <tr> <td></td> <td colspan="3">DIP & DIP DIRECTION OF ROCK STRUCTURES</td> </tr> <tr> <td></td> <td colspan="3">TEST BORING</td> </tr> <tr> <td></td> <td colspan="3">AUGER BORING</td> </tr> <tr> <td></td> <td colspan="3">CORE BORING</td> </tr> <tr> <td></td> <td colspan="3">MONITORING WELL</td> </tr> <tr> <td></td> <td colspan="3">PIEZOMETER INSTALLATION</td> </tr> <tr> <td></td> <td colspan="3">SLOPE INDICATOR INSTALLATION</td> </tr> <tr> <td></td> <td colspan="3">CONE PENETROMETER TEST</td> </tr> <tr> <td></td> <td colspan="3">SOUNDING ROD</td> </tr> <tr> <td></td> <td colspan="3">TEST BORING WITH CORE</td> </tr> <tr> <td></td> <td colspan="3">SPT N-VALUE</td> </tr> <tr> <th colspan="4">RECOMMENDATION SYMBOLS</th> </tr> <tr> <td></td> <td colspan="3">UNDERCUT</td> </tr> <tr> <td></td> <td colspan="3">UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE</td> </tr> <tr> <td></td> <td colspan="3">UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK</td> </tr> <tr> <td></td> <td colspan="3">SHALLOW UNDERCUT</td> </tr> <tr> <th colspan="4">ABBREVIATIONS</th> </tr> <tr> <td>AR - AUGER REFUSAL</td> <td>BT - BORING TERMINATED</td> <td>CL - CLAY</td> <td>CPT - CONE PENETRATION TEST</td> </tr> <tr> <td>CSE - COARSE</td> <td>DMT - DILATOMETER TEST</td> <td>DPT - DYNAMIC PENETRATION TEST</td> <td>e - VOID RATIO</td> </tr> <tr> <td>F - FINE</td> <td>FOSS. - FOSSILIFEROUS</td> <td>FRAC. - FRACTURED, FRACTURES</td> <td>FRAGS. - FRAGMENTS</td> </tr> <tr> <td>HL - HIGHLY</td> <td>MED. - MEDIUM</td> <td>MICA - MICA</td> <td>MOD. - MODERATELY</td> </tr> <tr> <td>NP - NON PLASTIC</td> <td>ORG. - ORGANIC</td> <td>PMT - PRESSUREMETER TEST</td> <td>SAP. - SAPROLITIC</td> </tr> <tr> <td>SD. - SAND, SANDY</td> <td>SL. - SILTY, SILTY</td> <td>SLI. - SLIGHTLY</td> <td>TCR - TRICONE REFUSAL</td> </tr> <tr> <td>w - MOISTURE CONTENT</td> <td>v - VERY</td> <td>VST - VANE SHEAR TEST</td> <td>WEA. - WEATHERED</td> </tr> <tr> <td></td> <td></td> <td>WU - UNIT WEIGHT</td> <td>Wg - DRY UNIT WEIGHT</td> </tr> <tr> <td></td> <td></td> <td>S - BULK</td> <td>SS - SPLIT SPOON</td> </tr> <tr> <td></td> <td></td> <td>ST - SHELBY TUBE</td> <td>RS - ROCK</td> </tr> <tr> <td></td> <td></td> <td>RT - RECOMPACTED TRIAXIAL RATIO</td> <td>CBR - CALIFORNIA BEARING RATIO</td> </tr> <tr> <th colspan="4">EQUIPMENT USED ON SUBJECT PROJECT</th> </tr> <tr> <td>DRILL UNITS:</td> <td>ADVANCING TOOLS:</td> <td colspan="2">HAMMER TYPE:</td> </tr> <tr> <td><input type="checkbox"/> CME-45C</td> <td><input type="checkbox"/> CLAY BITS</td> <td colspan="2"><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> CME-55</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td colspan="2">CORE SIZE:</td> </tr> <tr> <td><input type="checkbox"/> CME-550</td> <td><input type="checkbox"/> 8" HOLLOW AUGERS</td> <td colspan="2"><input type="checkbox"/> -B <input type="checkbox"/> -H</td> </tr> <tr> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td colspan="2"><input type="checkbox"/> -N</td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td> <td colspan="2">HAND TOOLS:</td> </tr> <tr> <td><input checked="" type="checkbox"/> BK-51</td> <td><input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td> <td colspan="2"><input type="checkbox"/> POST HOLE DIGGER</td> </tr> <tr> <td><input checked="" type="checkbox"/> D-25</td> <td><input checked="" type="checkbox"/> TRICONE 2 15/16" STEEL TEETH</td> <td colspan="2"><input type="checkbox"/> HAND AUGER</td> </tr> <tr> <td></td> <td><input type="checkbox"/> TRICONE _____ TUNG-CARB.</td> <td colspan="2"><input type="checkbox"/> SOUNDING ROD</td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td colspan="2"><input type="checkbox"/> VANE SHEAR TEST</td> </tr> <tr> <td></td> <td><input type="checkbox"/></td> <td colspan="2"></td> </tr> <tr> <td></td> <td><input type="checkbox"/></td> <td colspan="2"></td> </tr> <tr> <th colspan="4">TEXTURE OR GRAIN SIZE</th> </tr> <tr> <td>U.S. STD. SIEVE SIZE</td> <td>4</td> <td>10</td> <td>40</td> <td>60</td> <td>200</td> <td>270</td> </tr> <tr> <td>OPENING (MM)</td> <td>4.76</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> <tr> <td>BOULDER (BLDR.)</td> <td>COBBLE (COB.)</td> <td>GRAVEL (GR.)</td> <td>COARSE SAND (CSE. SD.)</td> <td>FINE SAND (F SD.)</td> <td>SILT (SL.)</td> <td>CLAY (CL.)</td> </tr> <tr> <td>GRAIN SIZE</td> <td>MM 305 12</td> <td>75 3</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> </tr> <tr> <th colspan="7">SOIL MOISTURE - CORRELATION OF TERMS</th> </tr> <tr> <td colspan="2">SOIL MOISTURE SCALE (ATTERBERG LIMITS)</td> <td colspan="2">FIELD MOISTURE DESCRIPTION</td> <td colspan="3">GUIDE FOR FIELD MOISTURE DESCRIPTION</td> </tr> <tr> <td rowspan="3">LL PLASTIC RANGE (PI) PL</td> <td>LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> <td colspan="3"></td> </tr> <tr> <td>PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> <td colspan="3"></td> </tr> <tr> <td>OPTIMUM MOISTURE SHRINKAGE LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> <td colspan="3"></td> </tr> <tr> <td></td> <td></td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> <td colspan="3"></td> </tr> <tr> <th colspan="7">PLASTICITY</th> </tr> <tr> <td colspan="3">NON PLASTIC</td> <td colspan="4">DRY STRENGTH</td> </tr> <tr> <td colspan="3">SLIGHTLY PLASTIC</td> <td colspan="4">VERY LOW</td> </tr> <tr> <td colspan="3">MODERATELY PLASTIC</td> <td colspan="4">SLIGHT</td> </tr> <tr> <td colspan="3">HIGHLY PLASTIC</td> <td colspan="4">MEDIUM</td> </tr> <tr> <td colspan="3"></td> <td colspan="4">HIGH</td> </tr> <tr> <th colspan="7">COLOR</th> </tr> <tr> <td colspan="7">DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</td> </tr> <tr> <th colspan="4">FRACTURE SPACING</th> <th colspan="3">BEDDING</th> </tr> <tr> <td>TERM</td> <td>SPACING</td> <td>TERM</td> <td>THICKNESS</td> <td colspan="3"></td> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 10 FEET</td> <td>VERY THICKLY BEDDED</td> <td>4 FEET</td> <td colspan="3"></td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> <td colspan="3"></td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> <td colspan="3"></td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FOOT</td> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> <td colspan="3"></td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> <td colspan="3"></td> </tr> <tr> <td></td> <td></td> <td>THINLY LAMINATED</td> <td>< 0.008 FEET</td> <td colspan="3"></td> </tr> <tr> <th colspan="7">INDURATION</th> </tr> <tr> <td colspan="7">FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</td> </tr> <tr> <td colspan="7">FRIABLE</td> </tr> <tr> <td colspan="7">RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</td> </tr> <tr> <td colspan="7">MODERATELY INDURATED</td> </tr> <tr> <td colspan="7">GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</td> </tr> <tr> <td colspan="7">INDURATED</td> </tr> <tr> <td colspan="7">GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</td> </tr> <tr> <td colspan="7">EXTREMELY INDURATED</td> </tr> <tr> <td colspan="7">SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</td> </tr> <tr> <td colspan="7">BENCH MARK: BM4 : 340.30 FEET RIGHT -L- 224+52 RR SPIKE IN BASE OF 12" PINE</td> </tr> <tr> <td colspan="7">N 579,95.2330 E 2,436,020.6560 ELEVATION: 64.40 FEET</td> </tr> <tr> <td colspan="7">NOTES: FIAD - FILLED IMMEDIATELY AFTER DRILLING</td> </tr> </table>										MINERALOGICAL COMPOSITION		MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.		COMPRESSIBILITY		SLIGHTLY COMPRESSIBLE	LL < 31	MODERATELY COMPRESSIBLE	LL = 31 - 50	HIGHLY COMPRESSIBLE	LL > 50	PERCENTAGE OF MATERIAL		ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%	HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE	GROUND WATER					WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING				STATIC WATER LEVEL AFTER _____ HOURS				PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA				SPRING OR SEEP			MISCELLANEOUS SYMBOLS					ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION				SOIL SYMBOL				ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT				INFERRED SOIL BOUNDARY				INFERRED ROCK LINE				ALLUVIAL SOIL BOUNDARY				DIP & DIP DIRECTION OF ROCK STRUCTURES				TEST BORING				AUGER BORING				CORE BORING				MONITORING WELL				PIEZOMETER INSTALLATION				SLOPE INDICATOR INSTALLATION				CONE PENETROMETER TEST				SOUNDING ROD				TEST BORING WITH CORE				SPT N-VALUE			RECOMMENDATION SYMBOLS					UNDERCUT				UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE				UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK				SHALLOW UNDERCUT			ABBREVIATIONS				AR - AUGER REFUSAL	BT - BORING TERMINATED	CL - CLAY	CPT - CONE PENETRATION TEST	CSE - COARSE	DMT - DILATOMETER TEST	DPT - DYNAMIC PENETRATION TEST	e - VOID RATIO	F - FINE	FOSS. - FOSSILIFEROUS	FRAC. - FRACTURED, FRACTURES	FRAGS. - FRAGMENTS	HL - HIGHLY	MED. - MEDIUM	MICA - MICA	MOD. - MODERATELY	NP - NON PLASTIC	ORG. - ORGANIC	PMT - PRESSUREMETER TEST	SAP. - SAPROLITIC	SD. - SAND, SANDY	SL. - SILTY, SILTY	SLI. - SLIGHTLY	TCR - TRICONE REFUSAL	w - MOISTURE CONTENT	v - VERY	VST - VANE SHEAR TEST	WEA. - WEATHERED			WU - UNIT WEIGHT	Wg - DRY UNIT WEIGHT			S - BULK	SS - SPLIT SPOON			ST - SHELBY TUBE	RS - ROCK			RT - RECOMPACTED TRIAXIAL RATIO	CBR - CALIFORNIA BEARING RATIO	EQUIPMENT USED ON SUBJECT PROJECT				DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:		<input type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL		<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:		<input type="checkbox"/> CME-550	<input type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B <input type="checkbox"/> -H		<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N		<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	HAND TOOLS:		<input checked="" type="checkbox"/> BK-51	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> POST HOLE DIGGER		<input checked="" type="checkbox"/> D-25	<input checked="" type="checkbox"/> TRICONE 2 15/16" STEEL TEETH	<input type="checkbox"/> HAND AUGER			<input type="checkbox"/> TRICONE _____ TUNG-CARB.	<input type="checkbox"/> SOUNDING ROD			<input type="checkbox"/> CORE BIT	<input type="checkbox"/> VANE SHEAR TEST			<input type="checkbox"/>				<input type="checkbox"/>			TEXTURE OR GRAIN SIZE				U.S. STD. SIEVE SIZE	4	10	40	60	200	270	OPENING (MM)	4.76	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)	GRAIN SIZE	MM 305 12	75 3	2.0	0.25	0.05	0.005	SOIL MOISTURE - CORRELATION OF TERMS							SOIL MOISTURE SCALE (ATTERBERG LIMITS)		FIELD MOISTURE DESCRIPTION		GUIDE FOR FIELD MOISTURE DESCRIPTION			LL PLASTIC RANGE (PI) PL	LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE				PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE				OPTIMUM MOISTURE SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE						- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE				PLASTICITY							NON PLASTIC			DRY STRENGTH				SLIGHTLY PLASTIC			VERY LOW				MODERATELY PLASTIC			SLIGHT				HIGHLY PLASTIC			MEDIUM							HIGH				COLOR							DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.							FRACTURE SPACING				BEDDING			TERM	SPACING	TERM	THICKNESS				VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET				WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET				MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET				CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET				VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET						THINLY LAMINATED	< 0.008 FEET				INDURATION							FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.							FRIABLE							RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.							MODERATELY INDURATED							GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.							INDURATED							GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.							EXTREMELY INDURATED							SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.							BENCH MARK: BM4 : 340.30 FEET RIGHT -L- 224+52 RR SPIKE IN BASE OF 12" PINE							N 579,95.2330 E 2,436,020.6560 ELEVATION: 64.40 FEET							NOTES: FIAD - FILLED IMMEDIATELY AFTER DRILLING						
GENERAL CLASS.		GRANULAR MATERIALS (≤ 35% PASSING #200)			SILT-CLAY MATERIALS (> 35% PASSING #200)			ORGANIC MATERIALS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
A-1	A-2	A-3	A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7	A-3	A-3	A-6, A-7																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
SYMBOL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
% PASSING #10 #40 #200	50 MX 30 MX 15 MX	50 MX 25 MX 10 MX	51 MN 35 MX 35 MX	35 MX 35 MX 35 MX	36 MN 36 MN 36 MN	36 MN 36 MN 36 MN	GRANULAR SOILS	SILT-CLAY SOILS	MUCK, PEAT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
MATERIAL PASSING #40 LL PI	- 6 MX	- NP	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	40 MX 41 MN 10 MX 11 MN	SOILS WITH LITTLE OR MODERATE AMOUNTS OF ORGANIC MATTER	HIGHLY ORGANIC SOILS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
GROUP INDEX	0	0	0	4 MX	8 MX	12 MX	16 MX	NO MX																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS. GRAVEL, AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
GEN. RATING AS SUBGRADE	EXCELLENT TO GOOD			FAIR TO POOR		FAIR TO POOR	POOR	UNSATURABLE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
MINERALOGICAL COMPOSITION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
COMPRESSIBILITY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
SLIGHTLY COMPRESSIBLE	LL < 31																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
MODERATELY COMPRESSIBLE	LL = 31 - 50																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
HIGHLY COMPRESSIBLE	LL > 50																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
PERCENTAGE OF MATERIAL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE 1 - 10%																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE 10 - 20%																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME 20 - 35%																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
HIGHLY ORGANIC	> 10%	> 20%	HIGHLY 35% AND ABOVE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
GROUND WATER																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
	WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	STATIC WATER LEVEL AFTER _____ HOURS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SPRING OR SEEP																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
MISCELLANEOUS SYMBOLS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
	ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SOIL SYMBOL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	INFERRED SOIL BOUNDARY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	INFERRED ROCK LINE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	ALLUVIAL SOIL BOUNDARY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	DIP & DIP DIRECTION OF ROCK STRUCTURES																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	TEST BORING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	AUGER BORING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	CORE BORING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	MONITORING WELL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	PIEZOMETER INSTALLATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SLOPE INDICATOR INSTALLATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	CONE PENETROMETER TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SOUNDING ROD																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	TEST BORING WITH CORE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SPT N-VALUE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
RECOMMENDATION SYMBOLS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
	UNDERCUT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	SHALLOW UNDERCUT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
ABBREVIATIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
AR - AUGER REFUSAL	BT - BORING TERMINATED	CL - CLAY	CPT - CONE PENETRATION TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
CSE - COARSE	DMT - DILATOMETER TEST	DPT - DYNAMIC PENETRATION TEST	e - VOID RATIO																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
F - FINE	FOSS. - FOSSILIFEROUS	FRAC. - FRACTURED, FRACTURES	FRAGS. - FRAGMENTS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
HL - HIGHLY	MED. - MEDIUM	MICA - MICA	MOD. - MODERATELY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
NP - NON PLASTIC	ORG. - ORGANIC	PMT - PRESSUREMETER TEST	SAP. - SAPROLITIC																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
SD. - SAND, SANDY	SL. - SILTY, SILTY	SLI. - SLIGHTLY	TCR - TRICONE REFUSAL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
w - MOISTURE CONTENT	v - VERY	VST - VANE SHEAR TEST	WEA. - WEATHERED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		WU - UNIT WEIGHT	Wg - DRY UNIT WEIGHT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		S - BULK	SS - SPLIT SPOON																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		ST - SHELBY TUBE	RS - ROCK																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		RT - RECOMPACTED TRIAXIAL RATIO	CBR - CALIFORNIA BEARING RATIO																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
EQUIPMENT USED ON SUBJECT PROJECT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input type="checkbox"/> CME-45C	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input type="checkbox"/> CME-55	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input type="checkbox"/> CME-550	<input type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> -B <input type="checkbox"/> -H																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -N																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	HAND TOOLS:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input checked="" type="checkbox"/> BK-51	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> POST HOLE DIGGER																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
<input checked="" type="checkbox"/> D-25	<input checked="" type="checkbox"/> TRICONE 2 15/16" STEEL TEETH	<input type="checkbox"/> HAND AUGER																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
	<input type="checkbox"/> TRICONE _____ TUNG-CARB.	<input type="checkbox"/> SOUNDING ROD																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
	<input type="checkbox"/> CORE BIT	<input type="checkbox"/> VANE SHEAR TEST																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
	<input type="checkbox"/>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
	<input type="checkbox"/>																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
TEXTURE OR GRAIN SIZE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
U.S. STD. SIEVE SIZE	4	10	40	60	200	270																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
OPENING (MM)	4.76	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
GRAIN SIZE	MM 305 12	75 3	2.0	0.25	0.05	0.005																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
SOIL MOISTURE - CORRELATION OF TERMS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
SOIL MOISTURE SCALE (ATTERBERG LIMITS)		FIELD MOISTURE DESCRIPTION		GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
LL PLASTIC RANGE (PI) PL	LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
	OPTIMUM MOISTURE SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
PLASTICITY																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
NON PLASTIC			DRY STRENGTH																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
SLIGHTLY PLASTIC			VERY LOW																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
MODERATELY PLASTIC			SLIGHT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
HIGHLY PLASTIC			MEDIUM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
			HIGH																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
COLOR																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
FRACTURE SPACING				BEDDING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
TERM	SPACING	TERM	THICKNESS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	4 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
CLOSE	0.16 TO 1 FOOT	VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
		THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
INDURATION																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
FRIABLE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
MODERATELY INDURATED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
INDURATED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
EXTREMELY INDURATED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
BENCH MARK: BM4 : 340.30 FEET RIGHT -L- 224+52 RR SPIKE IN BASE OF 12" PINE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
N 579,95.2330 E 2,436,020.6560 ELEVATION: 64.40 FEET																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
NOTES: FIAD - FILLED IMMEDIATELY AFTER DRILLING																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																

SKEW 0°
 SITE 4



5/14/99

PROJECT REFERENCE NO. R-5703	SHEET NO. 4
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	



5/14/99

5/14/99


SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)				% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	60	200		
SS-36	35' LT	217+00	3.5 - 5.0	A-4 (0)	15	NP	11	42	22	25	100	98	89	50.8	17.0	ND
SS-37	35' LT	217+00	48.2 - 49.1	A-2-6 (0)	31	14	30	41	10	18	99	80	69	31.6	22.4	ND

PROJECT REFERENCE NO. R-5703	SHEET NO. 5
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
100	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

PROFILE THROUGH BORINGS PROJECTED ALONG LEFT LANE CONTROL LINE

VE 1:1



217+00

+50

218+00

+50

219+00

5/14/99


SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)				% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	60	200		
SS-38	35' LT	220+00	2.2 - 3.8	A-7-6 (8)	47	18	11	36	29	24	100	95	89	56.4	87.6	ND
SS-39	35' LT	220+00	48.6 - 50.1	A-6 (3)	28	12	15	32	29	19	95	92	80	52.7	24.0	ND
SS-40	35' LT	221+00	8.2 - 9.7	A-2-6 (1)	38	22	48	21	9	21	98	69	50	31.9	20.9	ND
SS-41	35' LT	221+00	13.1 - 14.6	A-4 (0)	18	NP	44	19	28	7	98	71	54	37.6	20.7	ND
SS-42	35' LT	222+00	2.5 - 4.0	A-2-4 (0)	27	3	18	57	15	10	100	98	82	28.0	79.9	ND
SS-43	35' LT	222+00	8.5 - 10.0	A-3 (0)	19	NP	29	65	3	3	100	91	71	8.4	26.4	ND

PROJECT REFERENCE NO. R-5703	SHEET NO. 6
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

PROFILE THROUGH BORINGS PROJECTED ALONG LEFT LANE CONTROL LINE

VE 1:1



NOTE : GROUNDLINE ALONG LEFT LANE CONTROL LINE 23 FEET LEFT OF -L- FROM PRELIMINARY GENERAL DRAWING FOR BRIDGE ON C.F. HARVEY PARKWAY OVER STONYTON CREEK BETWEEN SR 1732 AND SR 1735

NOTE : INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE PROFILE


5/14/99

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	60		
SS-44	35' LT	223+00	4.2 - 5.7	A-2-4 (0)	29	NP	6	78	6	10	100	99	94	20.0	37.8
SS-45	35' LT	223+00	43.4 - 44.9	A-6 (2)	33	14	22	44	14	20	100	94	78	42.4	25.2
ST-6	38' LT	223+00	9.7 - 11.7	A-2-6 (2)	47	22	48	21	6	24	99	71	51	33.3	18.9

PROJECT REFERENCE NO. R-5703	SHEET NO. 7
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

PROFILE THROUGH BORINGS PROJECTED ALONG LEFT LANE CONTROL LINE




5/14/99

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)				% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	60	200		
SS-46	35' RT	218+00	1.0 - 2.5	A-2-4 (0)	20	3	21	51	13	15	100	92	79	32.0	16.5	1.5
SS-47	35' RT	218+00	58.1 - 59.6	A-2-4 (0)	20	NP	38	51	5	6	100	90	62	13.2	27.1	0.7

PROJECT REFERENCE NO. R-5703	SHEET NO. 9
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

PROFILE THROUGH BORINGS PROJECTED ALONG RIGHT LANE CONTROL LINE



NOTE : GROUNDLINE ALONG RIGHT LANE CONTROL LINE 23 FEET RIGHT OF -L- FROM PRELIMINARY GENERAL DRAWING FOR BRIDGE ON C.F. HARVEY PARKWAY OVER STONYTON CREEK BETWEEN SR 1732 AND SR 1735

NOTE : INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE PROFILE


5/14/99
 \$\$\$\$\$\$SYTIME\$\$\$\$\$\$
 \$\$\$\$\$\$DGN\$\$\$\$\$\$
 \$\$\$\$\$\$DATE\$\$\$\$\$\$

SOIL TEST RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)				% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	60	200		
SS-48	35' RT	220+00	4.2 - 5.7	A-2-4 (0)	22	9	32	39	16	13	100	84	68	31.1	24.4	ND
SS-49	35' RT	220+00	48.5 - 50.0	A-6 (3)	28	12	15	32	29	19	95	92	80	52.7	24.0	ND
SS-50	35' RT	221+00	0.3 - 1.8	A-6 (8)	40	11	10	20	35	35	100	97	90	74.2	70.2	ND

PROJECT REFERENCE NO. R-5703	SHEET NO. 10
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	


PROFILE THROUGH BORINGS PROJECTED ALONG RIGHT LANE CONTROL LINE



5/14/99
\$SYTIME\$\$\$\$
\$\$\$\$\$CDGN\$\$\$\$\$
\$\$\$\$\$\$\$\$\$\$

PROJECT REFERENCE NO. R-5703	SHEET NO. 11
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER
INCOMPLETE PLANS DO NOT USE FOR R/W ACQUISITION	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

PROFILE THROUGH BORINGS PROJECTED ALONG RIGHT LANE CONTROL LINE



+ 50

223 + 00

+ 50

224 + 00

+ 50





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB1-A LT LN	STATION 214+45	OFFSET 30 ft LT	ALIGNMENT -L-
COLLAR ELEV. 42.8 ft	TOTAL DEPTH 100.2 ft	NORTHING 579,003	EASTING 2,434,991
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 08/22/16	COMP. DATE 08/22/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB1-A LT LN	STATION 214+45	OFFSET 30 ft LT	ALIGNMENT -L-
COLLAR ELEV. 42.8 ft	TOTAL DEPTH 100.2 ft	NORTHING 579,003	EASTING 2,434,991
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 08/22/16	COMP. DATE 08/22/16	SURFACE WATER DEPTH N/A




NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17



NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B1-A LT LN	STATION 216+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 42.4 ft	TOTAL DEPTH 51.7 ft	NORTHING 578,986	EASTING 2,435,140
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/02/16	COMP. DATE 08/02/16	SURFACE WATER DEPTH 1.5ft



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B2-A LT LN	STATION 217+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 42.3 ft	TOTAL DEPTH 98.8 ft	NORTHING 578,975	EASTING 2,435,240
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/03/16	COMP. DATE 08/03/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B2-A LT LN	STATION 217+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 42.3 ft	TOTAL DEPTH 98.8 ft	NORTHING 578,975	EASTING 2,435,240
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/03/16	COMP. DATE 08/03/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B3-A LT LN	STATION 218+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 41.8 ft	TOTAL DEPTH 41.6 ft	NORTHING 578,964	EASTING 2,435,339
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/05/16	COMP. DATE 08/05/16	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)		
45																
														41.8	GROUND SURFACE	0.0
40	40.8	1.0	WOH	1	1								W			
	38.3	3.5	1	WOH	WOH								Sat.			
35	35.8	6.0	WOH	WOH	3								Sat.			
	33.3	8.5	10	5	6								W			
30																
	28.3	13.5	3	4	6								W			
25																
	23.3	18.5	11	24	25								W			
20																
	18.3	23.5	14	20	24								W			
15																
	13.3	28.5	16	20	23								W			
10																
	8.3	33.5	20	34	38								W			
5																
	3.3	38.5	30	34	44								W			
	0.2	41.6	60/0.0										W			
														0.2	Boring Terminated with Standard Penetration Test Refusal at Elevation 0.2 ft in Very Dense Gray Fine to Medium SAND with Cemented Layers	41.6



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17



NCDOT GEOTECHNICAL ENGINEERING UNIT
BORELOG REPORT

WBS 46375.1.1		TIP R-5703		COUNTY LENOIR		GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek							GROUND WTR (ft)
BORING NO. B4-A LT LN		STATION 219+00		OFFSET 35 ft LT		ALIGNMENT -L-	
COLLAR ELEV. 41.4 ft		TOTAL DEPTH 99.7 ft		NORTHING 578,953		EASTING 2,435,438	
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER Coogan, M.		START DATE 08/09/16		COMP. DATE 08/10/16		SURFACE WATER DEPTH 1.2ft	

WBS 46375.1.1		TIP R-5703		COUNTY LENOIR		GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek							GROUND WTR (ft)
BORING NO. B4-A LT LN		STATION 219+00		OFFSET 35 ft LT		ALIGNMENT -L-	
COLLAR ELEV. 41.4 ft		TOTAL DEPTH 99.7 ft		NORTHING 578,953		EASTING 2,435,438	
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER Coogan, M.		START DATE 08/09/16		COMP. DATE 08/10/16		SURFACE WATER DEPTH 1.2ft	




NCDOT BORE DOUBLE SITE #4.GPJ NC_DOT_GDT 5/2/17




NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B5-A LT LN	STATION 220+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 41.6 ft	TOTAL DEPTH 100.1 ft	NORTHING 578,942	EASTING 2,435,538
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/24/16	COMP. DATE 08/25/16	SURFACE WATER DEPTH 0.3ft



WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B5-A LT LN	STATION 220+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 41.6 ft	TOTAL DEPTH 100.1 ft	NORTHING 578,942	EASTING 2,435,538
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/24/16	COMP. DATE 08/25/16	SURFACE WATER DEPTH 0.3ft



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B6-A LT LN	STATION 221+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 39.8 ft	TOTAL DEPTH 99.6 ft	NORTHING 578,931	EASTING 2,435,537
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/23/16	COMP. DATE 08/24/16	SURFACE WATER DEPTH 0.5ft

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B6-A LT LN	STATION 221+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 39.8 ft	TOTAL DEPTH 99.6 ft	NORTHING 578,931	EASTING 2,435,537
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/23/16	COMP. DATE 08/24/16	SURFACE WATER DEPTH 0.5ft



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B7-A LT LN	STATION 222+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 39.7 ft	TOTAL DEPTH 98.5 ft	NORTHING 578,920	EASTING 2,435,737
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/22/16	COMP. DATE 08/23/16	SURFACE WATER DEPTH 0.2ft

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B7-A LT LN	STATION 222+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 39.7 ft	TOTAL DEPTH 98.5 ft	NORTHING 578,920	EASTING 2,435,737
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/22/16	COMP. DATE 08/23/16	SURFACE WATER DEPTH 0.2ft



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B8-A LT LN	STATION 223+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 40.8 ft	TOTAL DEPTH 99.1 ft	NORTHING 578,909	EASTING 2,435,836
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/19/16	COMP. DATE 08/19/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B8-A LT LN	STATION 223+00	OFFSET 35 ft LT	ALIGNMENT -L-
COLLAR ELEV. 40.8 ft	TOTAL DEPTH 99.1 ft	NORTHING 578,909	EASTING 2,435,836
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/19/16	COMP. DATE 08/19/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB2-A LT LN	STATION 224+07	OFFSET 34 ft LT	ALIGNMENT -L-
COLLAR ELEV. 50.5 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,898	EASTING 2,435,935
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 09/09/16	COMP. DATE 09/09/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 214 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB2-A LT LN	STATION 224+07	OFFSET 34 ft LT	ALIGNMENT -L-
COLLAR ELEV. 50.5 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,898	EASTING 2,435,935
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 09/09/16	COMP. DATE 09/09/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB1-B RT LN	STATION 214+45	OFFSET 47 ft RT	ALIGNMENT -L-
COLLAR ELEV. 44.3 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,933	EASTING 2,434,983
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 08/22/16	COMP. DATE 08/23/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB1-B RT LN	STATION 214+45	OFFSET 47 ft RT	ALIGNMENT -L-
COLLAR ELEV. 44.3 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,933	EASTING 2,434,983
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 08/22/16	COMP. DATE 08/23/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B1-B RT LN	STATION 215+98	OFFSET 40 ft RT	ALIGNMENT -L-
COLLAR ELEV. 42.5 ft	TOTAL DEPTH 99.5 ft	NORTHING 578,917	EASTING 2,435,132
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/03/16	COMP. DATE 08/03/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B1-B RT LN	STATION 215+98	OFFSET 40 ft RT	ALIGNMENT -L-
COLLAR ELEV. 42.5 ft	TOTAL DEPTH 99.5 ft	NORTHING 578,917	EASTING 2,435,132
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Wiggins, M.	START DATE 08/03/16	COMP. DATE 08/03/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17



NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Peele, J.E.	
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek				GROUND WTR (ft)
BORING NO. B4-B RT LN	STATION 218+00	OFFSET 35 ft RT	ALIGNMENT -L-	0 HR. 0.0
COLLAR ELEV. 41.6 ft	TOTAL DEPTH 73.1 ft	NORTHING 578,895	EASTING 2,435,331	24 HR. 0.0
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic	
DRILLER Wiggins, M.	START DATE 08/04/16	COMP. DATE 08/04/16	SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	L O G	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
45																
40	40.6	1.0	WOH	2	3									41.6	GROUND SURFACE	0.0
	38.1	3.5		3	5	7							SS-46	17%	ALLUVIAL Brown/Tan Fine SAND with Silt	3.0
	35.6	6.0		5	5	8							W		UNDIVIDED COASTAL PLAIN Tan Fine to Medium Clayey SAND	
	33.1	8.5		3	4	4							W			
	28.1	13.5		3	3	4							W		COASTAL PLAIN Dark Gray Fine Clayey SAND with shell fragments and Cemented Layers [Peedee Formation]	8.0
	23.1	18.5		14	29	38							W			
	18.1	23.5		32	47	60/0.4							W			
	13.1	28.5		27	47	53							W			
	8.1	33.5		22	27	40							W			
	3.1	38.5		7	8	13							W			
	-1.1	42.7											W			
	-1.5	43.1	60/0.0	6	7								W			
	-6.5	48.1		5	5	8							W			
	-11.5	53.1	100/0.2										W			
	-16.5	58.1		9	34	31							SS-47	27%		
	-21.5	63.1		7	10	14							W			
	-26.5	68.1		6	94/0.3								W			
	-31.5	73.1	60/0.0										W			
Boring Terminated with Standard Penetration Test Refusal at Elevation -31.5 ft in Very Dense Dark Gray to Black SAND																

NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B5-B RT LN	STATION 219+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 41.2 ft	TOTAL DEPTH 98.9 ft	NORTHING 578,884	EASTING 2,435,431
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/08/16	COMP. DATE 08/09/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B5-B RT LN	STATION 219+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 41.2 ft	TOTAL DEPTH 98.9 ft	NORTHING 578,884	EASTING 2,435,431
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/08/16	COMP. DATE 08/09/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B6-B RT LN	STATION 220+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 39.6 ft	TOTAL DEPTH 99.1 ft	NORTHING 578,872	EASTING 2,435,530
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/11/16	COMP. DATE 08/12/16	SURFACE WATER DEPTH 0.7ft


WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B6-B RT LN	STATION 220+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 39.6 ft	TOTAL DEPTH 99.1 ft	NORTHING 578,872	EASTING 2,435,530
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/11/16	COMP. DATE 08/12/16	SURFACE WATER DEPTH 0.7ft




NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17

NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)	
BORING NO. B7-B RT LN	STATION 221+00	OFFSET 35 ft RT	ALIGNMENT -L-	
COLLAR ELEV. 39.4 ft	TOTAL DEPTH 99.6 ft	NORTHING 578,861	EASTING 2,435,629	
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016			DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.		START DATE 08/15/16	COMP. DATE 08/16/16	SURFACE WATER DEPTH 0.5ft



WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)	
BORING NO. B7-B RT LN	STATION 221+00	OFFSET 35 ft RT	ALIGNMENT -L-	
COLLAR ELEV. 39.4 ft	TOTAL DEPTH 99.6 ft	NORTHING 578,861	EASTING 2,435,629	
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016			DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.		START DATE 08/15/16	COMP. DATE 08/16/16	SURFACE WATER DEPTH 0.5ft



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek				GROUND WTR (ft)
BORING NO. B8-B RT LN	STATION 222+00	OFFSET 35 ft RT	ALIGNMENT -L-	0 HR. 0.0
COLLAR ELEV. 39.9 ft	TOTAL DEPTH 99.2 ft	NORTHING 578,850	EASTING 2,435,729	24 HR. 0.0
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic	
DRILLER Coogan, M.	START DATE 08/16/16	COMP. DATE 08/17/16	SURFACE WATER DEPTH 0.0ft	

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.	
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek				GROUND WTR (ft)
BORING NO. B8-B RT LN	STATION 222+00	OFFSET 35 ft RT	ALIGNMENT -L-	0 HR. 0.0
COLLAR ELEV. 39.9 ft	TOTAL DEPTH 99.2 ft	NORTHING 578,850	EASTING 2,435,729	24 HR. 0.0
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic	
DRILLER Coogan, M.	START DATE 08/16/16	COMP. DATE 08/17/16	SURFACE WATER DEPTH 0.0ft	




NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT 5/2/17




NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B9-B RT LN	STATION 223+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 40.9 ft	TOTAL DEPTH 98.7 ft	NORTHING 578,839	EASTING 2,435,828
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/18/16	COMP. DATE 08/18/16	SURFACE WATER DEPTH N/A



WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. B9-B RT LN	STATION 223+00	OFFSET 35 ft RT	ALIGNMENT -L-
COLLAR ELEV. 40.9 ft	TOTAL DEPTH 98.7 ft	NORTHING 578,839	EASTING 2,435,828
DRILL RIG/HAMMER EFF./DATE MID0314 D-25 86% 08/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Coogan, M.	START DATE 08/18/16	COMP. DATE 08/18/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17





NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB2-B RT LN	STATION 224+12	OFFSET 33 ft RT	ALIGNMENT -L-
COLLAR ELEV. 50.4 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,828	EASTING 2,435,928
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 09/08/16	COMP. DATE 09/09/16	SURFACE WATER DEPTH N/A

WBS 46375.1.1	TIP R-5703	COUNTY LENOIR	GEOLOGIST Wright, F.K.
SITE DESCRIPTION Bridge No. 215 on -L- (Felix Harvey Pkwy) over Stonyton Creek			GROUND WTR (ft)
BORING NO. EB2-B RT LN	STATION 224+12	OFFSET 33 ft RT	ALIGNMENT -L-
COLLAR ELEV. 50.4 ft	TOTAL DEPTH 100.2 ft	NORTHING 578,828	EASTING 2,435,928
DRILL RIG/HAMMER EFF./DATE BRI9103 BK-51 89% 05/04/2016		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Eister, G.	START DATE 09/08/16	COMP. DATE 09/09/16	SURFACE WATER DEPTH N/A



NCDOT BORE DOUBLE SITE 4.GPJ NC_DOT_GDT_5/2/17

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/8/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/1-8/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B2-A LT LN	Sample #:	SS-36
		Sample Date:	8/3/16
Location:	217+00	Offset:	35' LT
		Depth (ft):	3.5-5.0'
Sample Description:	Gray sandy SILT A-4 (0)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm		
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#10	Coarse Sand	11%	Silt	22%
Gravel	0%	Fine Sand	42%	Clay	25%
Apparent Relative Density	2.650	Moisture Content	17.0%	% Passing #200	50.8%
Liquid Limit	15	Plastic Limit	0	Plastic Index	N.P.
Soil Mortar (-#10 Sieve)					
Coarse Sand	11%	Fine Sand	42%	Silt	22%
				Clay	25%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Karen Warner 118-06-0305 Laboratory Technician 11/8/2016
Technician Name Certification No. Position Date

Stewart Laney, P.E _____ Senior Engineer _____
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/8/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/1-8/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B2-A LT LN	Sample #:	SS-37
		Sample Date:	8/3/16
Location:	217+00	Offset:	35' LT
		Depth (ft):	48.2-49.1'
Sample Description:	Brown Clayey Sand A-2-6 (0)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm		
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	30%	Silt	10%
Gravel	1%	Fine Sand	41%	Clay	18%
Apparent Relative Density	2.650	Moisture Content	22.4%	% Passing #200	31.6%
Liquid Limit	31	Plastic Limit	17	Plastic Index	14
Soil Mortar (-#10 Sieve)					
Coarse Sand	30%	Fine Sand	42%	Silt	10%
				Clay	18%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Karen Warner 118-06-0305 Laboratory Technician 11/8/2016
Technician Name Certification No. Position Date

Stewart Laney, P.E _____ Senior Engineer _____
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B5-A LT LN	Sample #:	SS-38
		Sample Date:	8/24/16
Location:	220+00	Offset:	35' LT
		Depth (ft):	2.3 - 3.8
Sample Description:	Dark Gray Coarse to Fine Sandy Silty CLAY A-7-6 (8)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm
Maximum Particle Size	#4	Coarse Sand	11%
		Fine Sand	36%
		Silt	29%
		Clay	24%
Gravel	0%	Moisture Content	87.6%
Apparent Relative Density	ND	% Passing #200	56.4%
Liquid Limit	47	Plastic Limit	29
		Plastic Index	18
Soil Mortar (-#10 Sieve)			
Coarse Sand	11%	Fine Sand	36%
		Silt	29%
		Clay	24%
Description of Sand & Gravel Particles:	Rounded <input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>
		Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET 104-01-0703 Laboratory Manager 9/12/2016
Technician Name Certification No. Position Date

Mal Krajan, ET [Signature] Laboratory Manager 9/26/2016
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/8/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/1-8/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B5-A LL	Sample #:	SS-39
		Sample Date:	8/24/16
Location:	220+00	Offset:	35' LT
		Depth (ft):	48.6-50.1
Sample Description:	Brown Gray Fine Sandy CLAY A-6 (3)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm
Maximum Particle Size	1/2"	Coarse Sand	15%
		Fine Sand	32%
		Silt	29%
		Clay	19%
Gravel	5%	Moisture Content	24.0%
Apparent Relative Density	2.650	% Passing #200	52.7%
Liquid Limit	28	Plastic Limit	16
		Plastic Index	12
Soil Mortar (-#10 Sieve)			
Coarse Sand	16%	Fine Sand	34%
		Silt	30%
		Clay	20%
Description of Sand & Gravel Particles:	Rounded <input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>
		Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Karen Warner 118-06-0305 Laboratory Technician 11/8/2016
Technician Name Certification No. Position Date

Stewart Laney, P.E. [Signature] Senior Engineer [Date]
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B6-A LT LN	Sample #:	SS-40
		Sample Date:	8/23/16
Location:	221+00	Offset:	35' LT
		Depth (ft):	8.2 - 9.7
Sample Description:	Dark Gray Silty Clayey Fine to Coarse SAND A-2-6 (1)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm		
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	48%	Silt	9%
Gravel	2%	Fine Sand	21%	Clay	21%
Apparent Relative Density	ND	Moisture Content	20.9%	% Passing #200	31.9%
Liquid Limit	38	Plastic Limit	16	Plastic Index	22
Soil Mortar (-#10 Sieve)					
Coarse Sand	49%	Fine Sand	21%	Silt	9%
				Clay	21%
Description of Sand & Gravel Particles:		Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>	Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET <i>Technician Name</i>	104-01-0703 <i>Certification No.</i>	Laboratory Manager <i>Position</i>	9/12/2016 <i>Date</i>
Mal Krajan, ET <i>Technical Responsibility</i>	 <i>Signature</i>	Laboratory Manager <i>Position</i>	9/26/2016 <i>Date</i>

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance


S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B6-A LT LN	Sample #:	SS-41
		Sample Date:	8/23/16
Location:	221+00	Offset:	35' LT
		Depth (ft):	13.1 - 14.6
Sample Description:	Dark Gray Silty Clayey Fine to Coarse SAND A-4 (0)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm		
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	44%	Silt	28%
Gravel	2%	Fine Sand	19%	Clay	7%
Apparent Relative Density	ND	Moisture Content	20.7%	% Passing #200	37.6%
Liquid Limit	18	Plastic Limit	0	Plastic Index	N.P.
Soil Mortar (-#10 Sieve)					
Coarse Sand	45%	Fine Sand	19%	Silt	29%
				Clay	7%
Description of Sand & Gravel Particles:		Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>	Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET <i>Technician Name</i>	104-01-0703 <i>Certification No.</i>	Laboratory Manager <i>Position</i>	9/12/2016 <i>Date</i>
Mal Krajan, ET <i>Technical Responsibility</i>	 <i>Signature</i>	Laboratory Manager <i>Position</i>	9/26/2016 <i>Date</i>

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B7-A LT LN	Sample #:	SS-42
		Sample Date:	8/22/16
Location:	222+00	Offset:	35' LT
		Depth (ft):	2.5 - 4.0
Sample Description:	Dark Brown Silty Clayey Coarse to Fine SAND A-2-4 (0)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	18%	Silt	15%
Gravel	0%	Fine Sand	57%	Clay	10%
Apparent Relative Density	ND	Moisture Content	79.9%	% Passing #200	28.0%
Liquid Limit	27	Plastic Limit	24	Plastic Index	3
Soil Mortar (-#10 Sieve)					
Coarse Sand	18%	Fine Sand	57%	Silt	15%
				Clay	10%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>	Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

<u>Mal Krajan, ET</u> Technician Name	<u>104-01-0703</u> Certification No.	<u>Laboratory Manager</u> Position	<u>9/12/2016</u> Date
<u>Mal Krajan, ET</u> Technical Responsibility	 Signature	<u>Laboratory Manager</u> Position	<u>9/26/2016</u> Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance


S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B7-A LT LN	Sample #:	SS-43
		Sample Date:	8/22/16
Location:	222+00	Offset:	35' LT
		Depth (ft):	8.5 - 10
Sample Description:	Gray Silty Clayey Coarse to Fine SAND A-3 (0)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	29%	Silt	3%
Gravel	0%	Fine Sand	65%	Clay	3%
Apparent Relative Density	ND	Moisture Content	26.4%	% Passing #200	8.4%
Liquid Limit	19	Plastic Limit	0	Plastic Index	N.P.
Soil Mortar (-#10 Sieve)					
Coarse Sand	29%	Fine Sand	65%	Silt	3%
				Clay	3%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>	Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

<u>Mal Krajan, ET</u> Technician Name	<u>104-01-0703</u> Certification No.	<u>Laboratory Manager</u> Position	<u>9/12/2016</u> Date
<u>Mal Krajan, ET</u> Technical Responsibility	 Signature	<u>Laboratory Manager</u> Position	<u>9/26/2016</u> Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils

AASHTO T88 as Modified by NCDOT



Quality Assurance


Moisture, Ash, and Organic Matter



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/14/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/7 - 11/14/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B8-A LT LN	Sample #:	SS-44
		Sample Date:	8/19/16
Location:	223+00	Offset:	35' LT
		Depth (ft):	4.2 - 5.7
Sample Description:	Gray Silty Clayey Coarse to Fine SAND A-2-4 (0)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#10	Coarse Sand	6%	Silt	6%
Gravel	0%	Fine Sand	78%	Clay	10%
Apparent Relative Density	ND	Moisture Content	37.8%	% Passing #200	20.0%
Liquid Limit	29	Plastic Limit	0	Plastic Index	N.P.
Soil Mortar (-#10 Sieve)					
Coarse Sand	6%	Fine Sand	78%	Silt	6%
				Clay	10%
Description of Sand & Gravel Particles:		Rounded	<input type="checkbox"/>	Angular	<input type="checkbox"/>
Hard & Durable		<input type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable
			<input type="checkbox"/>		<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET 104-01-0703 Laboratory Manager 10/7/2016
 Technician Name Certification No. Position Date

Mal Krajan, ET [Signature] Laboratory Manager 11/14/2016
 Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

S&ME, Inc. Raleigh, 3201 Spring Forest Raod, Raleigh, North Carolina 27616			
Project #:	6235-16-010	Report Date:	10/21/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/18 - 10/21/16
Client Name:	Michael Baker Engineering		
Client Address:	Raleigh, NC		
Boring #:	B8-A LT LN	Sample #:	SS-44
		Sample Date:	8/19/16
Location:	223+00	Offset:	35' LT
		Depth (ft):	4.2 - 5.7
Sample Description:	Gray Silty Clayey Coarse to Fine SAND (A-2-4) (A)		

Equipment: Balance: 0.01 g. Readability, 500g. Minimum Capacity
 Balance: S&ME ID #: 1024 Cal. Date: 11/06/16 Due: 11/06/17

Method A: Moisture Content Determination Required Oven Temperature: 105 ± 5 °C

Oven Temperature: 105 °C		Tare #	1
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	46.08
a	Mass of As-Received Specimen + Tare Wt.	grams	91.85
b	Mass of Oven Dry Specimen + Tare Wt.	grams	79.30
w	Water Weight	(a-b)	12.55
A	Mass of As-Received Specimen	(a-t)	45.77
B	Mass of Oven Dry Specimen	(b-t)	33.22
% Moisture Content as a % of As Received or Total Mass		(w/A)*100	27.4%
% Moisture Content as a % of Oven-dried Mass		(w/B)*100	37.8%

Oven S&ME ID #: 1454 Cal. Date: 10/7/16 Due: 10/7/17

Method C (440° C) or D (750° C): Ash Content and Organic Matter Determination

Muffle Furnace: 455 °C		Tare #	44
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	50.03
b	Mass of Oven Dry Specimen + Tare Wt.	grams	83.23
c	Ash Weight + Tare Wt.	grams	82.14
C	Ash Weight	c-t	32.11
B	Mass of Oven Dry Specimen	(b-t)	33.20
D	% Ash Content	(C/B)*100	96.7%
% Organic Matter		100-D	3.3%

Muffle Furnace: S&ME ID #: 00261

Notes / Deviations / References:

Mal Krajan, ET [Signature] Laboratory Manager 11/14/2016
 Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

pH of Soil

AASHTO T289



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616				
Project #:	6235-16-010	Report Date:	11/7/16	
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/5 - 11/7/16	
Client Name:	Michael Baker Engineering			
Client Address:	Raleigh, NC			
Boring #:	B8-A LT LN	Sample #:	SS-44	Sample Date:
Location:	223+00	Offset:	35' LT	Depth (ft):
				4.2 - 5.7
Sample Description:	Gray Silty Clayey Coarse to Fine SAND (A-2-4) (0)			
Equipment:				
Balance	S&ME ID#	1024	Cal. Date:	11/6/16
			Due:	11/6/17
Sieve: #10	S&ME ID#	13223	Cal. Date:	6/11/16
			Due:	6/11/17
pH Meter:	S&ME ID#	1365	Cal. Date:	11/7/16
			Due:	NA

pH Meter Calibration

Buffer Solution	Results
pH buffer 7.0	7.02
pH buffer 4.01	4.01
pH buffer 10.0	10.03
Buffer Temperature °C	22.4

Measuring pH of Soil

Measurements	
Weight of Air Dry Soil (g)	30.01
Distilled Water (g)	30.02
Temperature °C	22.7
pH Readings	5.88

Notes / Deviations / References: AASHTO T-289: Determining pH of Soil for Use in Corrosion Testing

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.


Particle Size Analysis of Soils

AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616			
S&ME Project #:	6235-16-010	Report Date:	11/14/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/7 - 11/14/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B8-A LT LN	Sample #:	SS-45
		Sample Date:	8/19/16
Location:	223+00	Offset:	35' LT
		Depth (ft):	43.4 - 44.9
Sample Description:	Dark Gray Coarse to Fine Sandy Silty CLAY A-6 (2)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#10	Coarse Sand	22%	Silt	14%
Gravel	0%	Fine Sand	44%	Clay	20%
Apparent Relative Density	ND	Moisture Content	25.2%	% Passing #200	42.4%
Liquid Limit	33	Plastic Limit	19	Plastic Index	14
Soil Mortar (-#10 Sieve)					
Coarse Sand	22%	Fine Sand	44%	Silt	14%
				Clay	20%
Description of Sand & Gravel Particles:		Rounded	<input type="checkbox"/>	Angular	<input type="checkbox"/>
Hard & Durable		<input type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable
					<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET
 Technician Name

104-01-0703
 Certification No.

Laboratory Manager
 Position

11/14/2016
 Date

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Form No: TR-T267
 Revision No. 0
 Revision Date: 07/10/08

Moisture, Ash, and Organic Matter



AASHTO T-267

Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616			
Project #:	6235-16-010	Report Date:	10/21/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/18 - 10/21/16
Client Name:	Michael Baker Engineering		
Client Address:	Raleigh, NC		
Boring #:	B8-A LT LN	Sample #:	SS-45
Location:	223+00	Sample Date:	8/19/16
	Offset:	35' LT	Depth (ft): 43.4 - 44.9
Sample Description: Dark Gray Coarse to Fine Sandy Silty CLAY (A-6) (2)			
Equipment: Balance: 0.01 g. Readability, 500g. Minimum Capacity			
Balance:	S&ME ID #: 1024	Cal. Date: 11/06/16	Due: 11/06/17

Method A: Moisture Content Determination Required Oven Temperature: 105 ± 5 °C

Oven Temperature: 105 °C		Tare #	2
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	47.05
a	Mass of As-Received Specimen + Tare Wt.	grams	100.89
b	Mass of Oven Dry Specimen + Tare Wt.	grams	90.07
w	Water Weight	(a-b)	10.82
A	Mass of As-Received Specimen	(a-t)	53.84
B	Mass of Oven Dry Specimen	(b-t)	43.02
% Moisture Content as a % of As Received or Total Mass		(w/A)*100	20.1%
% Moisture Content as a % of Oven-dried Mass		(w/B)*100	25.2%

Oven S&ME ID #: 1454 Cal. Date: 10/7/16 Due: 10/7/17

Method C (440 °C) or D (750 °C): Ash Content and Organic Matter Determination

Muffle Furnace: 455 °C		Tare #	2
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	13.61
b	Mass of Oven Dry Specimen + Tare Wt.	grams	38.57
c	Ash Weight + Tare Wt.	grams	38.08
C	Ash Weight	c-t	24.47
B	Mass of Oven Dry Specimen	(b-t)	24.96
D	% Ash Content	(C/B)*100	98.0%
	% Organic Matter	100-D	2.0%

Muffle Furnace: S&ME ID #: 00261

Notes / Deviations / References:

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Form No: TR-T289-1
 Revision No. 0
 Revision Date: 07/10/08

pH of Soil



AASHTO T289

Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616				
Project #:	6235-16-010	Report Date:	11/7/16	
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/5 - 11/7/16	
Client Name:	Michael Baker Engineering			
Client Address:	Raleigh, NC			
Boring #:	B8-A LT LN	Sample #:	SS-45	Sample Date:
Location:	223+00	Sample Date:	8/19/16	
	Offset:	35' LT	Depth (ft):	43.4 - 44.9
Sample Description: Dark Gray Coarse to Fine Sandy Silty CLAY (A-6) (2)				
Equipment:				
Balance	S&ME ID#	1024	Cal. Date:	11/6/16
			Due:	11/6/17
Sieve:	#10	S&ME ID#	13223	Cal. Date:
				6/11/16
			Due:	6/11/17
pH Meter:	S&ME ID#	1365	Cal. Date:	11/7/16
			Due:	NA

pH Meter Calibration

Buffer Solution	Results
pH buffer 7.0	7.02
pH buffer 4.01	4.01
pH buffer 10.0	10.03
Buffer Temperature °C	22.4

Measuring pH of Soil

Measurements	
Weight of Air Dry Soil (g)	30.03
Distilled Water (g)	30.03
Temperature °C	22.4
pH Readings	5.61

Notes / Deviations / References: AASHTO T-289: Determining pH of Soil for Use in Corrosion Testing

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	12/27/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	12/24 - 12/27/16
State Project #:	46375.1.1	F.A. Project No:	N/A
Client Name:	Michael Baker Engineering	TIP NO:	R-5703
Address:	Raleigh, NC		
Boring #:	B8-A LT LN	Sample #:	ST-6
Location:	223+00	Sample Date:	8/19/16
		Offset:	38' LT
		Depth (ft):	9.7 - 11.7 ft.
Sample Description:	Dark Gray Silty Clayey Fine to Coare SAND A-2-6 (2)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	48%	Silt	6%
Gravel	1%	Fine Sand	21%	Clay	24%
Apparent Relative Density	ND	Moisture Content	18.9%	% Passing #200	33.3%
Liquid Limit	37	Plastic Limit	15	Plastic Index	22
Soil Mortar (-#10 Sieve)					
Coarse Sand	48%	Fine Sand	22%	Silt	6%
				Clay	24%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

<u>Mal Krajan, ET</u> Technician Name	<u>104-01-0703</u> Certification No.	<u>Laboratory Manager</u> Position	<u>12/27/2016</u> Date
<u>Mal Krajan, ET</u> Technical Responsibility	 Signature	<u>Laboratory Manager</u> Position	<u>9/26/2016</u> Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Oedometer Settlement Tests

Sample details

Sketch showing specimen location in original Sample



Depth: 9.7 - 11.7 ft.
 Description: Dark Gray Silty Clayey Fine to Coarse SAND (A-2-6) (0)

Type: Undisturbed
 Height H₀ (in): 0.997
 Diameter D₀ (in): 2.501
 Weight W₀ (gr): 165.58
 Bulk Density ρ (PCF): 128.79
 Particle Density ρ_s: 2.667 (measured)

Initial Conditions

Settlement Channel: 1942
 Moisture Content w₀%: 19.1
 Dry Density ρ_d (PCF): 108.17
 Voids Ratio e₀: 0.5385
 Deg of Saturation S₀%: 94.4
 Swelling Pressure S_s (TSF): 0.000

Final Conditions


Moisture Content w_f%: 22.4
 Dry Density ρ_d (PCF): 110.46
 Voids Ratio e_f: 0.5066
 Deg of Saturation S_f%: 100.00
 Settlement (in): 0.021
 Compression Index C_c: 0.060

Notes: Test specimen taken from the middle portion of UD tube.




ASTM D2435-96	Test name: Consolidation
Site Reference: C.F. Harvey	Date of Test: 12-6-16
Jobfile: E:\16010.JOB	Sample: ST-6
Operator: <u>mk</u>	Borehole: B8-A LT LN
Checked: <u>mk</u>	Approved:

Oedometer Settlement Tests




Oedometer Settlement Tests




	ASTM D2435-96		Test name: Consolidation
	Site Reference: C.F. Harvey		Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6	Borehole: B8-A LT LN
	Operator: <i>MLL</i>	Checked: <i>MLL</i>	Approved:

	ASTM D2435-96		Test name: Consolidation
	Site Reference: C.F. Harvey		Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6	Borehole: B8-A LT LN
	Operator: <i>MLL</i>	Checked: <i>MLL</i>	Approved:

Oedometer Settlement Tests




Oedometer Settlement Tests



	ASTM D2435-96		Test name: Consolidation
			Date of Test: 12-6-16
	Site Reference: C.F. Harvey	Sample: ST-6	
	Jobfile: E:\16010.JOB	Borehole: B8-A LT LN	
Operator: <i>mk</i>	Checked: <i>mk</i>	Approved:	

	ASTM D2435-96		Test name: Consolidation
			Date of Test: 12-6-16
	Site Reference: C.F. Harvey	Sample: ST-6	
	Jobfile: E:\16010.JOB	Borehole: B8-A LT LN	
Operator: <i>mk</i>	Checked: <i>mk</i>	Approved:	

Oedometer Settlement Tests



Oedometer Settlement Tests

Stress (TSF)	Initial Temp. oC	Settlement Total (in)	Cal Corr. (in)	Final Temp. oC	Void Ratio e_f	t_{90} (mins)	Secondary Compr C_{sec}	c_v (ft2/day)	m_v (ft2/ton)
0.050	21.6	0.0032	0.0	21.6	0.5336	4.974	0.00	0.422	0.064
0.250	21.6	0.0048	0.0	21.6	0.5311	2.926	0.00	0.714	0.008
0.500	21.6	0.0080	0.0	21.6	0.5262	4.808	0.00	0.433	0.013
1.000	21.6	0.0132	0.0	21.6	0.5181	1.528	0.00	1.350	0.011
2.000	21.6	0.0221	0.0	21.6	0.5044	3.021	0.00	0.673	0.009
4.000	21.6	0.0328	0.0	21.6	0.4879	2.111	0.00	0.944	0.006
2.000	21.6	0.0312	0.0	21.6	0.4904				0.001
0.500	21.6	0.0264	0.0	21.6	0.4978				0.003
0.050	21.6	0.0207	0.0	21.6	0.5066				0.013

	ASTM D2435-96	Test name: Consolidation
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mlc</i>	Borehole: B8-A LT LN
	Checked: <i>mlc</i>	Approved:

	ASTM D2435-96	Test name: Consolidation
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mlc</i>	Borehole: B8-A LT LN
	Checked: <i>mlc</i>	Approved:


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	0	0.0000	0.0000
2	0.017	5	0.0005	0.0005
3	0.167	8	0.0008	0.0008
4	0.417	13	0.0013	0.0013
5	0.917	16	0.0016	0.0016
6	1.917	21	0.0021	0.0021
7	3.917	26	0.0026	0.0026
8	7.917	29	0.0029	0.0029
9	14.917	31	0.0031	0.0031
10	29.917	32	0.0032	0.0032
11	38.567	32	0.0032	0.0032

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	0.050
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0032
Void Ratio e	0.5336
Final Temp oC	0.0
t ₉₀ (mins)	4.97
c _v (ft ² /day)	0.422
m _v (ft ² /ton)	0.064
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 0.050 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>MLC</i>	Borehole:	B8-A LT LN
	Checked: <i>MLC</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>MLC</i>	Borehole:	B8-A LT LN
	Checked: <i>MLC</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	32	0.0032	0.0032
2	0.017	36	0.0036	0.0036
3	0.167	40	0.0040	0.0040
4	0.417	41	0.0041	0.0041
5	0.917	43	0.0043	0.0043
6	1.917	45	0.0045	0.0045
7	3.917	46	0.0046	0.0046
8	7.917	46	0.0046	0.0046
9	14.917	47	0.0047	0.0047
10	29.917	48	0.0048	0.0048
11	42.383	48	0.0048	0.0048

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	0.250
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0016
Void Ratio e	0.5311
Final Temp oC	0.0
t ₉₀ (mins)	2.93
c _v (ft ² /day)	0.714
m _v (ft ² /ton)	0.008
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 0.250 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mk</i>	Borehole:	B8-A LT LN
	Checked: <i>mk</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mk</i>	Borehole:	B8-A LT LN
	Checked: <i>mk</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	48	0.0048	0.0048
2	0.017	52	0.0052	0.0052
3	0.167	69	0.0069	0.0069
4	0.417	71	0.0071	0.0071
5	0.917	72	0.0072	0.0072
6	1.917	73	0.0073	0.0073
7	3.917	74	0.0074	0.0074
8	7.917	75	0.0075	0.0075
9	14.917	76	0.0076	0.0076
10	29.917	76	0.0076	0.0076
11	59.917	77	0.0077	0.0077
12	119.917	78	0.0078	0.0078
13	149.917	79	0.0079	0.0079
14	179.917	79	0.0079	0.0079
15	209.917	80	0.0080	0.0080
16	239.917	80	0.0080	0.0080

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	0.500
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0032
Voids Ratio e	0.5262
Final Temp oC	0.0
t ₉₀ (mins)	4.81
c _v (ft ² /day)	0.433
m _v (ft ² /ton)	0.013
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 0.500 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mlc</i>	Borehole:	B8-A LT LN
	Checked: <i>mlc</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mlc</i>	Borehole:	B8-A LT LN
	Checked: <i>mlc</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	80	0.0080	0.0080
2	0.017	88	0.0088	0.0088
3	0.167	112	0.0112	0.0112
4	0.417	117	0.0117	0.0117
5	0.917	120	0.0120	0.0120
6	1.917	122	0.0122	0.0122
7	3.917	125	0.0125	0.0125
8	7.917	127	0.0127	0.0127
9	14.917	127	0.0127	0.0127
10	29.917	129	0.0129	0.0129
11	59.917	130	0.0130	0.0130
12	111.567	132	0.0132	0.0132

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	1.000
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0052
Voids Ratio e	0.5181
Final Temp oC	0.0
t ₉₀ (mins)	1.53
c _v (ft ² /day)	1.35
m _v (ft ² /ton)	0.011
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 1.000 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>MK</i>	Borehole:	B8-A LT LN
	Checked: <i>MK</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>MK</i>	Borehole:	B8-A LT LN
	Checked: <i>MK</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	132	0.0132	0.0132
2	0.017	136	0.0136	0.0136
3	0.167	184	0.0184	0.0184
4	0.417	192	0.0192	0.0192
5	0.917	199	0.0199	0.0199
6	1.917	204	0.0204	0.0204
7	3.917	207	0.0207	0.0207
8	7.917	208	0.0208	0.0208
9	14.917	212	0.0212	0.0212
10	29.917	214	0.0214	0.0214
11	59.917	215	0.0215	0.0215
12	119.917	216	0.0216	0.0216
13	149.917	216	0.0216	0.0216
14	179.917	217	0.0217	0.0217
15	209.917	218	0.0218	0.0218
16	239.917	219	0.0219	0.0219
17	269.917	220	0.0220	0.0220
18	299.917	221	0.0221	0.0221

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	2.000
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0089
Voids Ratio e	0.5044
Final Temp oC	0.0
t ₉₀ (mins)	3.02
c _v (ft ² /day)	0.673
m _v (ft ² /ton)	0.009
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 2.000 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
Operator: <i>mk</i>	Checked: <i>mk</i>	Borehole:	B8-A LT LN
		Approved:	


	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
Operator: <i>mk</i>	Checked: <i>mk</i>	Borehole:	B8-A LT LN
		Approved:	

Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	221	0.0221	0.0221
2	0.017	224	0.0224	0.0224
3	0.167	288	0.0288	0.0288
4	0.417	296	0.0296	0.0296
5	0.917	304	0.0304	0.0304
6	1.917	312	0.0312	0.0312
7	3.917	316	0.0316	0.0316
8	7.917	319	0.0319	0.0319
9	14.917	320	0.0320	0.0320
10	29.917	324	0.0324	0.0324
11	59.917	326	0.0326	0.0326
12	119.917	328	0.0328	0.0328
13	130.600	328	0.0328	0.0328

Oedometer Settlement Tests

Settlement Stage Results	
Vertical Stress (TSF)	4.000
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0107
Voids Ratio e	0.4879
Final Temp oC	0.0
t ₉₀ (mins)	2.11
c _v (ft ² /day)	0.944
m _v (ft ² /ton)	0.006
Sec Compression C _{sec}	0.00



	ASTM D2435-96	Test name	Consolidation Load: 4.000 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
Operator: <i>mk</i>	Checked: <i>mk</i>	Borehole:	B8-A LT LN
		Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
Operator: <i>mk</i>	Checked: <i>mk</i>	Borehole:	B8-A LT LN
		Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	328	0.0328	0.0328
2	0.017	319	0.0319	0.0319
3	0.167	316	0.0316	0.0316
4	0.417	312	0.0312	0.0312
5	0.917	312	0.0312	0.0312
6	1.917	312	0.0312	0.0312
7	3.917	312	0.0312	0.0312
8	7.917	312	0.0312	0.0312
9	14.917	312	0.0312	0.0312
10	29.917	312	0.0312	0.0312
11	59.917	312	0.0312	0.0312
12	119.917	312	0.0312	0.0312
13	149.917	312	0.0312	0.0312
14	155.283	312	0.0312	0.0312

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	2.000
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0016
Voids Ratio e	0.4904
Final Temp oC	
t ₉₀ (mins)	
c _v (ft ² /day)	
m _v (ft ² /ton)	
Sec Compression C _{sec}	



	ASTM D2435-96	Test name	Consolidation Load: 2.000 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mk</i>	Borehole:	B8-A LT LN
	Checked: <i>mk</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mk</i>	Borehole:	B8-A LT LN
	Checked: <i>mk</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	312	0.0312	0.0312
2	0.017	304	0.0304	0.0304
3	0.167	286	0.0286	0.0286
4	0.417	280	0.0280	0.0280
5	0.917	277	0.0277	0.0277
6	1.917	272	0.0272	0.0272
7	3.917	269	0.0269	0.0269
8	7.917	265	0.0265	0.0265
9	14.917	264	0.0264	0.0264
10	29.917	264	0.0264	0.0264
11	59.917	264	0.0264	0.0264
12	111.867	264	0.0264	0.0264

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	0.500
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0048
Voids Ratio e	0.4978
Final Temp oC	
t ₉₀ (mins)	
c _v (ft ² /day)	
m _v (ft ² /ton)	
Sec Compression C _{sec}	



	ASTM D2435-96	Test name	Consolidation Load: 0.500 (TSF)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mlk</i>	Borehole:	B8-A LT LN
	Checked: <i>mlk</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: <i>mlk</i>	Borehole:	B8-A LT LN
	Checked: <i>mlk</i>	Approved:	


Oedometer Settlement Tests

No.	Time (mins)	Displacement (divs)	Displacement (in)	Settlement (in)
1	0.000	264	0.0264	0.0264
2	0.017	256	0.0256	0.0256
3	0.167	245	0.0245	0.0245
4	0.417	239	0.0239	0.0239
5	0.917	235	0.0235	0.0235
6	1.917	229	0.0229	0.0229
7	3.917	222	0.0222	0.0222
8	7.917	217	0.0217	0.0217
9	14.917	212	0.0212	0.0212
10	29.917	208	0.0208	0.0208
11	36.117	207	0.0207	0.0207

Oedometer Settlement Tests

Settlement Stage Results

Vertical Stress (TSF)	0.050
Initial Temp oC	21.6
Correction (in)	0.0
Settlement (in)	0.0057
Void Ratio e	0.5066
Final Temp oC	
t ₉₀ (mins)	
c _v (ft ² /day)	
m _v (ft ² /ton)	
Sec Compression C _{sec}	



	ASTM D2435-96	Test name	Consolidation Load: 0.050 (TSF)
		Date of Test:	12-6-16
	Site Reference: C.F. Harvey	Sample:	ST-6
	Jobfile: E:\16010.JOB	Borehole:	B8-A LT LN
Operator: <i>mk</i>	Checked: <i>mk</i>	Approved:	

	ASTM D2435-96	Test name	Consolidation
		Date of Test:	12-6-16
	Site Reference: C.F. Harvey	Sample:	ST-6
	Jobfile: E:\16010.JOB	Borehole:	B8-A LT LN
Operator: <i>mk</i>	Checked: <i>mk</i>	Approved:	

Effective Stress Triaxial Compression

Consolidated Undrained

Sample details

Sketch showing specimen location in original Sample



Depth: 9.7 - 11.7 ft.
Description: Dark Gray Silty Clayey Fine to Coarse SAND (A-2-6) (0)

	Specimen 1	Specimen 2	Specimen 3
Type	Undisturbed	Undisturbed	Undisturbed
Height H_0 (in)	5.992	5.879	6.037
Diameter D_0 (in)	2.865	2.868	2.863
Weight W_0 (gr)	1309	1307.7	1332.7
Bulk Density ρ (PCF)	129.09	131.17	130.63
Particle Density ρ_s	2.667	2.667	2.667
	(measured)	(measured)	(measured)

Initial Conditions

	Specimen 1	Specimen 2	Specimen 3
Cell Pressure σ_3 (lb/in ²)	4.0	10.0	16.0
Pore Pressure u (lb/in ²)	0.0	0.0	0.0
Machine Speed d_r (in/min)	0.0067	0.0195	0.0068
No. of Membranes	1	1	1
Total Thickness (in)	0.012	0.012	0.012
Strain Channel	1798	1798	1798
Load Channel	1776	1776	1776
Pore P. Channel	1779	1779	1779
Volume Channel	Volume Chang	Volume Chang	Volume Chang
Moisture Content w_0 %	19.8	18.6	18.4
Dry Density ρ_{d0} (PCF)	107.80	110.62	110.32
Voids Ratio e_0	0.54	0.50	0.51
Deg of Saturation S_0 %	96.88	98.21	96.57
Final B Value	0.95	0.97	0.96

Final Conditions

	Specimen 1	Specimen 2	Specimen 3
Moisture Content w_f %	20.5	19.2	19.3
Dry Density ρ_d (PCF)	108.97	113.19	113.59
Voids Ratio e_f	0.53	0.47	0.47
Deg of Saturation S_f %	100.00	100.00	100.00
Failure Criteria	Mx Stress Ratio	Mx Stress Ratio	Mx Stress Ratio
Axial Strain ϵ_f %	3.0	4.0	6.0
Corr Dev Stress $(\sigma_1 - \sigma_3)_f$ (lb/in ²)	25.9	34.2	47.2
Minor Stress σ_{3f} (lb/in ²)	1.2	3.9	7.7
Major Stress σ_{1f} (lb/in ²)	27.1	38.1	54.9
Stress Ratio $(\sigma_1/\sigma_3)_f$	22.6	9.8	7.1

Notes:




Failure Sketch



Surface Inclination

Effective Stress Triaxial Compression

Consolidated Undrained





	Test Method: ASTM D4767-95	Test name: CU Triaxial (SS, MS)
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mlc</i>	Borehole: B8-A LT LN
	Checked: <i>mlc</i>	Approved:

	Test Method: ASTM D4767-95	Test name: CU Triaxial (SS, MS)
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mlc</i>	Borehole: B8-A LT LN
	Checked: <i>mlc</i>	Approved:


Effective Stress Triaxial Compression

Consolidated Undrained



Effective Stress Triaxial Compression

Consolidated Undrained



	Test Method: ASTM D4767-95	Test name: CU Triaxial (SS, MS)
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mk</i>	Borehole: B8-A LT LN
	Checked: <i>mk</i>	Approved:

	Test Method: ASTM D4767-95	Test name: CU Triaxial (SS, MS)
	Site Reference: C.F. Harvey	Date of Test: 12-6-16
	Jobfile: E:\16010.JOB	Sample: ST-6
	Operator: <i>mk</i>	Borehole: B8-A LT LN
	Checked: <i>mk</i>	Approved:

Effective Stress Triaxial Compression

Consolidated Undrained Shear (Specimen 1)

No.	Strain (divs)	Strain ε%	Load (divs)	Load (lbs)	Pore Prs (divs)	Pore Prs (lbf/in2)	D. Stress (σ ₁ - σ ₃) _m (lbf/in2)	D. Stress (σ ₁ - σ ₃) _c (lbf/in2)	Minor Str σ ₃ ' (lbf/in2)	Major Str σ ₁ ' (lbf/in2)	Ratio σ ₁ '/σ ₃ '
1	321	0.00	569	0.0	0	0.0	0.0	0.0	4.00	4.00	1.00
2	376	0.09	733	16.4	5	0.5	2.6	2.6	3.50	6.06	1.73
3	427	0.18	800	23.1	7	0.7	3.6	3.6	3.30	6.90	2.09
4	485	0.27	936	36.7	9	0.9	5.7	5.7	3.10	8.82	2.84
5	538	0.36	1002	43.3	11	1.1	6.7	6.7	2.90	9.64	3.32
6	593	0.46	1103	53.4	12	1.2	8.3	8.3	2.80	11.10	3.97
7	650	0.55	1228	65.9	14	1.4	10.2	10.1	2.60	12.68	4.88
8	705	0.64	1286	71.7	16	1.6	11.1	11.0	2.40	13.37	5.57
9	759	0.73	1359	79.0	17	1.7	12.3	12.1	2.30	14.39	6.26
10	816	0.83	1447	87.8	19	1.9	13.6	13.4	2.10	15.54	7.40
11	870	0.92	1542	97.3	20	2.0	15.1	14.9	2.00	16.90	8.45
12	922	1.01	1601	103.2	21	2.1	16.0	15.8	1.90	17.70	9.32
13	982	1.11	1708	113.9	23	2.3	17.6	17.4	1.70	19.14	11.26
14	1535	2.03	2074	150.5	28	2.8	23.0	22.8	1.20	23.96	19.96
15	2088	2.96	2299	173.0	28	2.8	26.2	25.9	1.20	27.07	22.56
16	2702	3.99	2495	192.6	22	2.2	28.9	28.4	1.80	30.21	16.79
17	3316	5.02	2666	209.7	12	1.2	31.1	30.6	2.80	33.36	11.92
18	3929	6.04	2807	223.8	1	0.1	32.9	32.2	3.90	36.12	9.26
19	4493	6.99	2976	240.7	-10	-1.0	35.0	34.3	5.00	39.26	7.85
20	5106	8.01	3115	254.6	-22	-2.2	36.6	35.8	6.20	41.99	6.77
21	5672	8.96	3210	264.1	-32	-3.2	37.6	36.7	7.20	43.89	6.10
22	6288	9.99	3296	272.7	-41	-4.1	38.3	37.4	8.10	45.49	5.62
23	6908	11.03	3379	281.0	-50	-5.0	39.1	38.0	9.00	47.02	5.22
24	7470	11.97	3454	288.5	-57	-5.7	39.7	38.6	9.70	48.26	4.98
25	8089	13.01	3524	295.5	-65	-6.5	40.2	39.0	10.50	49.48	4.71
26	8670	13.98	3554	298.5	-69	-6.9	40.1	38.9	10.90	49.76	4.56
27	9258	14.97	3594	302.5	-72	-7.2	40.2	38.9	11.20	50.07	4.47
28	9851	15.96	3606	303.7	-74	-7.4	39.9	38.5	11.40	49.90	4.38
29	10450	16.96	3640	307.1	-75	-7.5	39.8	38.4	11.50	49.89	4.34
30	11053	17.97	3681	311.2	-78	-7.8	39.9	38.4	11.80	50.17	4.25
31	11659	18.99	3691	312.2	-80	-8.0	39.5	38.0	12.00	49.96	4.16
32	12265	20.00	3702	313.3	-81	-8.1	39.2	37.6	12.10	49.66	4.10

Effective Stress Triaxial Compression

Consolidated Undrained Shear (Specimen 2)

No.	Strain (divs)	Strain ε%	Load (divs)	Load (lbs)	Pore Prs (divs)	Pore Prs (lbf/in2)	D. Stress (σ ₁ - σ ₃) _m (lbf/in2)	D. Stress (σ ₁ - σ ₃) _c (lbf/in2)	Minor Str σ ₃ ' (lbf/in2)	Major Str σ ₁ ' (lbf/in2)	Ratio σ ₁ '/σ ₃ '
1	127	0.00	603	0.0	0	0.0	0.0	0.0	10.00	10.00	1.00
2	183	0.10	789	18.6	5	0.5	2.9	2.9	9.50	12.42	1.31
3	236	0.19	947	34.4	10	1.0	5.4	5.4	9.00	14.40	1.60
4	289	0.28	1009	40.6	14	1.4	6.4	6.4	8.60	14.96	1.74
5	347	0.38	1139	53.6	18	1.8	8.4	8.4	8.20	16.59	2.02
6	401	0.47	1188	58.5	21	2.1	9.2	9.2	7.90	17.05	2.16
7	455	0.56	1293	69.0	24	2.4	10.8	10.6	7.60	18.23	2.40
8	513	0.66	1377	77.4	28	2.8	12.1	11.9	7.20	19.13	2.66
9	567	0.75	1478	87.5	31	3.1	13.7	13.5	6.90	20.39	2.96
10	621	0.85	1574	97.1	34	3.4	15.1	15.0	6.60	21.58	3.27
11	680	0.95	1658	105.5	37	3.7	16.4	16.3	6.30	22.57	3.58
12	733	1.04	1762	115.9	39	3.9	18.0	17.9	6.10	23.97	3.93
13	786	1.13	1828	122.5	42	4.2	19.0	18.9	5.80	24.68	4.26
14	1285	1.98	2297	169.4	53	5.3	26.1	25.8	4.70	30.52	6.49
15	1897	3.03	2703	210.0	58	5.8	32.0	31.7	4.20	35.85	8.54
16	2456	3.99	2899	229.6	61	6.1	34.7	34.2	3.90	38.08	9.76
17	3018	4.96	3088	248.5	58	5.8	37.1	36.6	4.20	40.77	9.71
18	3633	6.01	3274	267.1	51	5.1	39.5	38.8	4.90	43.73	8.92
19	4198	6.98	3491	288.8	40	4.0	42.2	41.5	6.00	47.52	7.92
20	4816	8.04	3663	306.0	25	2.5	44.2	43.4	7.50	50.94	6.79
21	5382	9.01	3781	317.8	9	0.9	45.5	44.6	9.10	53.68	5.90
22	5945	9.97	3933	333.0	-5	-0.5	47.1	46.2	10.50	56.67	5.40
23	6568	11.04	4077	347.4	-19	-1.9	48.6	47.5	11.90	59.45	5.00
24	7135	12.01	4183	358.0	-31	-3.1	49.5	48.4	13.10	61.50	4.70
25	7701	12.98	4281	367.8	-40	-4.0	50.3	49.1	14.00	63.14	4.51
26	8273	13.96	4341	373.8	-50	-5.0	50.6	49.3	15.00	64.30	4.29
27	8894	15.03	4451	384.8	-60	-6.0	51.4	50.1	16.00	66.09	4.13
28	9465	16.01	4501	389.8	-68	-6.8	51.5	50.1	16.80	66.89	3.98
29	10030	16.97	4588	398.5	-77	-7.7	52.0	50.6	17.70	68.26	3.86
30	10598	17.95	4691	408.8	-83	-8.3	52.7	51.2	18.30	69.52	3.80
31	11194	18.97	4774	417.1	-86	-8.6	53.1	51.6	18.60	70.18	3.77
32	11800	20.01	4862	425.9	-89	-8.9	53.6	52.0	18.90	70.87	3.75

	Test Method: ASTM D4767-95		Test name: CU Triaxial (SS, MS) Shear (Specimen 1)	
	Date of Test: 12-6-16		Date of Test: 12-6-16	
	Site Reference: C.F. Harvey	Sample: ST-6	Borehole: B8-A LT LN	
	Jobfile: E:\16010.JOB	Operator: <i>mk</i> Checked: <i>mk</i> Approved:		

	Test Method: ASTM D4767-95		Test name: CU Triaxial (SS, MS) Shear (Specimen 2)	
	Date of Test: 12-6-16		Date of Test: 12-6-16	
	Site Reference: C.F. Harvey	Sample: ST-6	Borehole: B8-A LT LN	
	Jobfile: E:\16010.JOB	Operator: <i>mk</i> Checked: <i>mk</i> Approved:		

Effective Stress Triaxial Compression


Consolidated Undrained Shear (Specimen 3)

No.	Strain (divs)	Strain ε%	Load (divs)	Load (lbs)	Pore Prs (divs)	Pore Prs (lbf/in2)	D. Stress (σ ₁ - σ ₃) _m (lbf/in2)	D. Stress (σ ₁ - σ ₃) _c (lbf/in2)	Minor Str σ ₃ ' (lbf/in2)	Major Str σ ₁ ' (lbf/in2)	Ratio σ ₁ '/σ ₃ '
1	289	0.00	703	0.0	0	0.0	0.0	0.0	16.00	16.00	1.00
2	343	0.09	850	14.7	6	0.6	2.3	2.3	15.40	17.73	1.15
3	394	0.18	950	24.7	10	1.0	3.9	3.9	15.00	18.91	1.26
4	453	0.27	1117	41.4	14	1.4	6.5	6.5	14.60	21.14	1.45
5	505	0.36	1270	56.7	17	1.7	8.9	8.9	14.30	23.25	1.63
6	560	0.45	1425	72.2	21	2.1	11.4	11.4	13.90	25.29	1.82
7	618	0.55	1564	86.1	24	2.4	13.6	13.4	13.60	27.01	1.99
8	673	0.64	1648	94.5	27	2.7	14.9	14.7	13.30	28.02	2.11
9	728	0.73	1745	104.2	31	3.1	16.4	16.2	12.90	29.13	2.26
10	785	0.83	1825	112.2	35	3.5	17.6	17.5	12.50	29.97	2.40
11	841	0.92	1887	118.4	38	3.8	18.6	18.4	12.20	30.62	2.51
12	895	1.01	1963	126.0	42	4.2	19.8	19.6	11.80	31.40	2.66
13	953	1.11	2045	134.2	46	4.6	21.0	20.9	11.40	32.26	2.83
14	1456	1.95	2503	180.0	70	7.0	28.0	27.7	9.00	36.68	4.08
15	2071	2.98	3003	230.0	81	8.1	35.4	35.0	7.90	42.89	5.43
16	2691	4.02	3418	271.5	86	8.6	41.3	40.8	7.40	48.20	6.51
17	3256	4.96	3688	298.5	84	8.4	44.9	44.4	7.60	51.98	6.84
18	3880	6.01	3913	321.0	83	8.3	47.8	47.2	7.70	54.86	7.12
19	4447	6.96	4082	337.9	78	7.8	49.8	49.1	8.20	57.29	6.99
20	5073	8.00	4227	352.4	70	7.0	51.4	50.6	9.00	59.56	6.62
21	5641	8.95	4413	371.0	65	6.5	53.5	52.6	9.50	62.14	6.54
22	6270	10.00	4572	386.9	62	6.2	55.2	54.2	9.80	64.00	6.53
23	6839	10.96	4691	398.8	58	5.8	56.3	55.2	10.20	65.42	6.41
24	7467	12.01	4797	409.4	52	5.2	57.1	56.0	10.80	66.75	6.18
25	8040	12.97	4883	418.0	45	4.5	57.6	56.5	11.50	67.95	5.91
26	8668	14.02	4969	426.6	40	4.0	58.1	56.9	12.00	68.85	5.74
27	9239	14.97	5025	432.2	32	3.2	58.2	56.9	12.80	69.70	5.45
28	9868	16.02	5077	437.4	25	2.5	58.2	56.8	13.50	70.31	5.21
29	10438	16.98	5122	441.9	20	2.0	58.1	56.7	14.00	70.67	5.05
30	11068	18.03	5188	448.5	16	1.6	58.2	56.7	14.40	71.13	4.94
31	11615	18.95	5268	456.5	10	1.0	58.6	57.1	15.00	72.06	4.80
32	12221	19.96	5298	459.5	5	0.5	58.3	56.7	15.50	72.17	4.66



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616			
S&ME Project #:	6235-16-010	Report Date:	11/14/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/7 - 11/14/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B4-B RT LN	Sample #:	SS-46
		Sample Date:	8/4/16
Location:	218+00	Offset:	35' RT
		Depth (ft):	1.0 - 2.5
Sample Description:	Tan Silty Clayey Coarse to Fine SAND A-2-4 (0)		



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm

Maximum Particle Size	#4	Coarse Sand	21%	Silt	13%
Gravel	0%	Fine Sand	51%	Clay	15%
Apparent Relative Density	ND	Moisture Content	16.5%	% Passing #200	32.0%
Liquid Limit	20	Plastic Limit	17	Plastic Index	3

Soil Mortar (-#10 Sieve)					
Coarse Sand	21%	Fine Sand	51%	Silt	13%
				Clay	15%

Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input type="checkbox"/>	
Hard & Durable	<input type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET
Technician Name

104-01-0703
Certification No.

Laboratory Manager
Position

11/14/2016
Date

Mal Krajan, ET
Technical Responsibility

Signature

Laboratory Manager
Position

11/14/2016
Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

	Test Method: ASTM D4767-95	Test name	CU Triaxial (SS, MS) Shear (Specimen 3)
	Site Reference: C.F. Harvey	Date of Test:	12-6-16
	Jobfile: E:\16010.JOB	Sample:	ST-6
	Operator: mke	Borehole:	B8-A LT LN
	Checked: mke	Approved:	

Form No: TR-T267
 Revision No. 0
 Revision Date: 07/10/08

Moisture, Ash, and Organic Matter



AASHTO T-267

Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616			
Project #:	6235-16-010	Report Date:	10/21/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/18 - 10/21/16
Client Name:	Michael Baker Engineering		
Client Address:	Raleigh, NC		
Boring #:	B4-B RT LN	Sample #:	SS-46
		Sample Date:	8/4/16
Location:	218+00	Offset:	35' RT
		Depth (ft):	1.0 - 2.5
Sample Description:	Tan Silty Clayey Coarse to Fine SAND (A-2-4) (0)		
Equipment:	Balance: 0.01 g. Readability, 500g. Minimum Capacity		
Balance:	S&ME ID #: 1024	Cal. Date:	11/06/16
		Due:	11/06/17

Method A: Moisture Content Determination Required Oven Temperature: 105 ± 5 °C

Oven Temperature: 105 °C		Tare #	am
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	48.40
a	Mass of As-Received Specimen + Tare Wt.	grams	93.53
b	Mass of Oven Dry Specimen + Tare Wt.	grams	87.24
w	Water Weight	(a-b)	6.29
A	Mass of As-Received Specimen	(a-t)	45.13
B	Mass of Oven Dry Specimen	(b-t)	38.84
% Moisture Content as a % of As Received or Total Mass		(w/A)*100	13.9%
% Moisture Content as a % of Oven-dried Mass		(w/B)*100	16.2%

Oven S&ME ID #: 1454 Cal. Date: 10/7/16 Due: 10/7/17

Method C (440 °C) or D (750 °C): Ash Content and Organic Matter Determination

Muffle Furnace: 455 °C		Tare #	85
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	49.03
b	Mass of Oven Dry Specimen + Tare Wt.	grams	87.97
c	Ash Weight + Tare Wt.	grams	87.39
C	Ash Weight	c-t	38.36
B	Mass of Oven Dry Specimen	(b-t)	38.94
D	% Ash Content	(C/B)*100	98.5%
	% Organic Matter	100-D	1.5%

Muffle Furnace: S&ME ID #: 00261

Notes / Deviations / References:

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Form No: TR-T289-1
 Revision No. 0
 Revision Date: 07/10/08

pH of Soil



AASHTO T289

Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616				
Project #:	6235-16-010	Report Date:	11/7/16	
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/5 - 11/7/16	
Client Name:	Michael Baker Engineering			
Client Address:	Raleigh, NC			
Boring #:	B4-B RT LN	Sample #:	SS-46	Sample Date:
				8/4/16
Location:	218+00	Offset:	35' RT	Depth (ft):
				1.0 - 2.5
Sample Description:	Tan Silty Clayey Coarse to Fine SAND (A-2-4) (0)			
Equipment:	Balance			
Balance:	S&ME ID# 1024	Cal. Date:	11/6/16	Due:
				11/6/17
Sieve:	#10	S&ME ID# 13223	Cal. Date:	6/11/16
				Due: 6/11/17
pH Meter:	S&ME ID# 1365	Cal. Date:	11/7/16	Due:
				NA

pH Meter Calibration

Buffer Solution	Results
pH buffer 7.0	7.02
pH buffer 4.01	4.01
pH buffer 10.0	10.03
Buffer Temperature °C	22.4

Measuring pH of Soil

Measurements	
Weight of Air Dry Soil (g)	30.02
Distilled Water (g)	30.02
Temperature °C	22.1
pH Readings	5.88

Notes / Deviations / References: AASHTO T-289: Determining pH of Soil for Use in Corrosion Testing

Mal Krajan, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils

AASHTO T88 as Modified by NCDOT



Quality Assurance


Moisture, Ash, and Organic Matter



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/14/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/7 - 11/14/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B4-B RT LN	Sample #:	SS-47
		Sample Date:	8/4/16
Location:	218+00	Offset:	35' RT
		Depth (ft):	58.1 - 59.6
Sample Description:	Dark Gray Silty Clayey Coarse to Fine SAND A-2-4 (0)		



As Defined by NCDOT		Fine Sand	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm

Maximum Particle Size	#4	Coarse Sand	38%	Silt	5%
Gravel	0%	Fine Sand	51%	Clay	6%
Apparent Relative Density	ND	Moisture Content	27.1%	% Passing #200	13.2%
Liquid Limit	20	Plastic Limit	0	Plastic Index	N.P.

Soil Mortar (-#10 Sieve)							
Coarse Sand	38%	Fine Sand	51%	Silt	5%	Clay	6%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input type="checkbox"/>			
Hard & Durable	<input type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>		

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET 104-01-0703 Laboratory Manager 11/14/2016
 Technician Name Certification No. Position Date

Mal Krajan, ET [Signature] Laboratory Manager 11/14/2016
 Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

AASHTO T-267

S&ME, Inc. Raleigh, 3201 Spring Forest Raod, Raleigh, North Carolina 27616

Project #:	6235-16-010	Report Date:	10/21/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	10/18 - 10/21/16
Client Name:	Michael Baker Engineering		
Client Address:	Raleigh, NC		
Boring #:	B4-B RT LN	Sample #:	SS-47
		Sample Date:	8/4/16
Location:	218+00	Offset:	35' RT
		Depth (ft):	58.1 - 59.6
Sample Description:	Dark Gray Silty Clayey Coarse to Fine SAND (A-2-4) (0)		

Equipment: Balance: 0.01 g. Readability, 500g. Minimum Capaccity
 Balance: S&ME ID #: 1024 Cal. Date: 11/06/16 Due: 11/06/17

Method A: Moisture Content Determination Required Oven Temperature: 105 ± 5° C

Oven Temperature: 105 °C		Tare #	m
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	48.80
a	Mass of As-Received Specimen + Tare Wt.	grams	92.58
b	Mass of Oven Dry Specimen + Tare Wt.	grams	83.24
w	Water Weight	(a-b)	9.34
A	Mass of As-Received Specimen	(a-t)	43.78
B	Mass of Oven Dry Specimen	(b-t)	34.44
% Moisture Content as a % of As Received or Total Mass		(w/A)*100	21.3%
% Moisture Content as a % of Oven-dried Mass		(w/B)*100	27.1%

Oven S&ME ID #: 1454 Cal. Date: 10/7/16 Due: 10/7/17

Method C (440° C) or D (750° C): Ash Content and Organic Matter Determination

Muffle Furnace: 455 °C		Tare #	49
t	Tare Weight (Dish plus Aluminum Foil Cover)	grams	49.46
b	Mass of Oven Dry Specimen + Tare Wt.	grams	83.89
c	Ash Weight + Tare Wt.	grams	83.65
C	Ash Weight	c-t	34.19
B	Mass of Oven Dry Specimen	(b-t)	34.43
D	% Ash Content	(C/B)*100	99.3%
% Organic Matter		100-D	0.7%

Muffle Furnace: S&ME ID #: 00261

Notes / Deviations / References:

Mal Krajan, ET [Signature] Laboratory Manager 11/14/2016
 Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Form No: TR-T289-1
 Revision No. 0
 Revision Date: 07/10/08

pH of Soil



AASHTO T289

Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616				
Project #:	6235-16-010	Report Date:	11/7/16	
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/5 - 11/7/16	
Client Name:	Michael Baker Engineering			
Client Address:	Raleigh, NC			
Boring #:	B4-B RT LN	Sample #:	SS-47	Sample Date: 8/4/16
Location:	218+00	Offset:	35' RT	Depth (ft): 58.1 - 59.6
Sample Description:	Dark Gray Silty Clayey Coarse to Fine SAND (A-2-4) (0)			
Equipment:				
Balance	S&ME ID#	1024	Cal. Date:	11/6/16 Due: 11/6/17
Sieve: #10	S&ME ID#	13223	Cal. Date:	6/11/16 Due: 6/11/17
pH Meter:	S&ME ID#	1365	Cal. Date:	11/7/16 Due: NA

pH Meter Calibration

Buffer Solution	Results
pH buffer 7.0	7.02
pH buffer 4.01	4.01
pH buffer 10.0	10.03
Buffer Temperature °C	22.4

Measuring pH of Soil

Measurements	
Weight of Air Dry Soil (g)	20.00
Distilled Water (g)	20.01
Temperature °C	21.8
pH Readings	6.01

Notes / Deviations / References: AASHTO T-289: Determining pH of Soil for Use in Corrosion Testing

Mal Krajani, ET
 Technical Responsibility

Signature

Laboratory Manager
 Position

11/14/2016
 Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Form No. TR-T88
 Revision No. 0
 Revision Date: 12/20/09


Particle Size Analysis of Soils

AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616				
S&ME Project #:	6235-16-010	Report Date:	11/8/16	
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/1-8/16	
State Project #:	46375.1.1	F.A. Project No:	N/A	TIP NO: R-5703
Client Name:	Michael Baker Engineering			
Address:	Raleigh, NC			
Boring #:	B6-B RT LN	Sample #:	SS-48	Sample Date: 8/11/16
Location:	220+00	Offset:	35' RT	Depth (ft): 4.2-5.7'
Sample Description:	Gray Silty SAND A-2-4 (0)			



As Defined by NCDOT		Fine Sand	< 0.25 mm and > 0.05 mm				
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm				
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm				
Maximum Particle Size	#20	Coarse Sand	32%	Silt	16%		
Gravel	0%	Fine Sand	39%	Clay	13%		
Apparent Relative Density	2.650	Moisture Content	24.5%	% Passing #200	31.1%		
Liquid Limit	22	Plastic Limit	13	Plastic Index	9		
Soil Mortar (-#10 Sieve)							
Coarse Sand	32%	Fine Sand	39%	Silt	16%	Clay	13%
Description of Sand & Gravel Particles:		Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>		
Hard & Durable		<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>	

References / Comments / Deviations: ND=Not Determined.

Karen Warner
 Technician Name

118-06-0305
 Certification No.

Laboratory Technician
 Position

11/8/2016
 Date

Stewart Laney, P.E
 Technical Responsibility

Signature

Senior Engineer
 Position

Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	11/8/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	11/1-8/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B6-B RT LN	Sample #:	SS-49
		Sample Date:	8/11/16
Location:	220+00	Offset:	35' RT
		Depth (ft):	48.5-50.0
Sample Description:	Gray Silty CLAY A-6 (3)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	1/2"	Coarse Sand	15%	Silt	29%
Gravel	5%	Fine Sand	32%	Clay	19%
Apparent Relative Density	2.650	Moisture Content	24.0%	% Passing #200	52.7%
Liquid Limit	28	Plastic Limit	16	Plastic Index	12
Soil Mortar (-#10 Sieve)					
Coarse Sand	16%	Fine Sand	34%	Silt	30%
				Clay	20%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input type="checkbox"/>	Weathered & Friable	<input type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Karen Warner 118-06-0305 Laboratory Technician 11/8/2016
Technician Name Certification No. Position Date

Stewart Laney, P.E _____ Senior Engineer _____
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.

Particle Size Analysis of Soils


AASHTO T88 as Modified by NCDOT



Quality Assurance

S&ME, Inc. Raleigh, 3201 Spring Forest Road, Raleigh, North Carolina 27616

S&ME Project #:	6235-16-010	Report Date:	9/20/16
Project Name:	C.F. Harvey Parkway Extension R-5703	Test Date(s):	9/12 - 9/20/16
State Project #:	46375.1.1	F.A. Project No:	N/A
		TIP NO:	R-5703
Client Name:	Michael Baker Engineering		
Address:	Raleigh, NC		
Boring #:	B7-B RT LN	Sample #:	SS-50
		Sample Date:	8/15/16
Location:	221+00	Offset:	35' RT
		Depth (ft):	0.3 - 1.8
Sample Description:	Dark Brown Coarse to Fine Sandy Silty CLAY A-6 (8)		



As Defined by NCDOT		Fine Sand		< 0.25 mm and > 0.05 mm	
Gravel	< 75 mm and > 2.00 mm	Silt	< 0.05 and > 0.005 mm		
Coarse Sand	< 2.00 mm and > 0.25 mm	Clay	< 0.005 mm		
Maximum Particle Size	#4	Coarse Sand	10%	Silt	35%
Gravel	0%	Fine Sand	20%	Clay	35%
Apparent Relative Density	ND	Moisture Content	70.2%	% Passing #200	74.2%
Liquid Limit	40	Plastic Limit	29	Plastic Index	11
Soil Mortar (-#10 Sieve)					
Coarse Sand	10%	Fine Sand	20%	Silt	35%
				Clay	35%
Description of Sand & Gravel Particles:	Rounded	<input type="checkbox"/>	Angular	<input checked="" type="checkbox"/>	
Hard & Durable	<input checked="" type="checkbox"/>	Soft	<input checked="" type="checkbox"/>	Weathered & Friable	<input checked="" type="checkbox"/>

References / Comments / Deviations: ND=Not Determined.

Mal Krajan, ET 104-01-0703 Laboratory Manager 9/12/2016
Technician Name Certification No. Position Date

Mal Krajan, ET _____ Laboratory Manager 9/26/2016
Technical Responsibility Signature Position Date

This report shall not be reproduced, except in full, without the written approval of S&ME, Inc.