TOTAL BILL OF MATERIAL										
STRUCTURE I.D.	STATION	LOCATION	*	SUPPORTS,	GENERIC SIGNING ITEM -	** GENERIC SIGNING ITEM -				
			OVERHEAD	OVERHEAD SIGN	CLASS A CONCRETE	REINFORCING STEEL				
			FOOTING	STRUCTURE (TRUSS) (AESTHETIC COLUMNS ONLY) (A		(AESTHETIC COLUMNS ONLY)				
			CUBIC YARDS	LUMP SUM CUBIC YARDS		POUNDS				
Α	475+00.00	-NC540-	10.6	LUMP SUM	27.5	4,730				
В	527+50.00	-NC540-	7.6	LUMP SUM	12.0	2,050				
С	550+00.00	-NC540-	11.0	LUMP SUM	27.8	4,776				
D	590+21.00	-NC540-	15.2	LUMP SUM	29.5	4,971				
E	655+00.00	-NC540-	5.1	LUMP SUM	11.1	1,955				
F	691+50.00	-NC540-	15.1	LUMP SUM	28.9	4,897				
T15 IN	21+16.00	-LPD-	11.4	LUMP SUM	28.5	4,846				
T15 OUT	20+66.00	-LPD-	11.4	LUMP SUM	28.4	4,850				
T16 IN	20+14.00	-RPB-	9.0	LUMP SUM	28.6	4,884				
T16 OUT	20+64.00	-RPB-	9.0	LUMP SUM	28.8	4,900				
	TOTAL		105.4	LUMP SUM	251.1	42,859				

^{*} OVERHEAD FOOTING QUANTITY INCLUDES FOUNDATION CONCRETE FOR DRILLED PIERS AND TRANSITION FOOTINGS. THE CONTRACT UNIT PRICE FOR OVERHEAD FOOTINGS WILL BE FULL COMPENSATION FOR PROVIDING REINFORCING STEEL TO CONSTRUCT DRILLED PIERS AND TRANSITION FOOTINGS.

PROJECT NO. <u>U-5315 A & B</u> COUNTY STATION:_

DEPARTMENT OF TRANSPORTATION
RALEIGH OVERHEAD STRUCTURES TOTAL BILL OF MATERIAL

PATH CARO

RUMMEL, KLEPPER & KAHL, LLP 900 RIDGEFIELD DRIVE SUITE 350 RALEIGH, NC 27609–3960 (919) 878–9560	29360 29360 11/14/2017		ТС			
NC LICENSE NUMBER: F-0112		NO.	BY:			
DOCUMENT NOT CONSID	ERED FINAL	1				
UNLESS ALL SIGNATURES COMPLETED						

LEPPER & KAHL, LLP	DE EISH							
LD DRIVE SUITE 350 09–3960 (919) 878–9560	11/14/2017	REVISIONS					SHEET NO	
SE NUMBER: F-0112		NO.	BY:	DATE:	NO.	BY:	DATE:	SIGN-2
SUMENT NOT CONSIDERED FINAL					3			TOTAL SHEETS
SS ALL SIGNATURES COMPLETED					4			12

DRAWN BY: B.A.HAAG

CHECKED BY: R.D.FISHER

DATE: AUG 2017

DESIGN ENGINEER OF RECORD: R.D.FISHER

DATE: AUG 2017 DRAWN BY : B.A.HAAG CHECKED BY : R.D.FISHER

^{**} QUANTITY INCLUDES #9 V1 BARS.