

FRAMING PLAN


ANTICIPATED BEAM REPAIR LOCATIONS							
SPAN	BEAM	LOCATION	REPAIR TYPE	DIM "A"	DIM "B"	DIM "C"	DIM "D"
A	1	END BENT 1	PW	2'-10"	1'-0"	-	-
B	6	BENT 1	PF	5"	5"	-	-
B	1	BENT 2	PW	6"	6'-0"	-	-
C	1	BENT 2	PW	4"	1'-0"	-	-
C	2	BENT 2	PW	4"	1'-6"	-	-
C	3	BENT 2	PW	4"	1'-6"	-	-

BEAM REPAIR QUANTITY TABLE		
	ESTIMATED	ACTUAL
PLATING REPAIR	129.7 LBS.	

- ① - BEAM NUMBER
- Ⓜ - PLATING WEB REPAIR
- Ⓟ - PLATING FLANGE REPAIR
- Ⓩ - ZONE PAINTING

NOTES:

SEE SHEET NO. S-6 FOR BEAM PLATING REPAIR DETAILS.
 THE LOCATIONS AND DIMENSIONS OF THE AREAS FOR REPAIR ARE BASED ON THE BEST INFORMATION AVAILABLE. THE CONTRACTOR, IN CONJUNCTION WITH THE ENGINEER, SHALL VERIFY THE LOCATION AND EXTENT OF REPAIR AREAS PRIOR TO PERFORMING REPAIRS.
 CONTRACTOR SHALL ENSURE THAT EXISTING UTILITIES ADJACENT TO THE BRIDGE ARE NOT DAMAGED DURING THE REPAIR OPERATIONS.



LIMITS OF ZONE PAINTING

PROJECT NO. I-5889A
BUNCOMBE COUNTY
 BRIDGE NO. 334



DocuSigned by:
Eric B. Nelson
 11/16/2017

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
BEAM REPAIR LOCATIONS					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					S-5
					TOTAL SHEETS 208

DRAWN BY : M.A.LEE DATE : 10/2017
 CHECKED BY : R.NELSON DATE : 10/2017

PLANS PREPARED BY:
Gannett Fleming
 Excellence Delivered *As Promised*
 2610 Wycliff Road
 Suite 102
 Raleigh, NC 27607-3073
 (919) 420-7660
 NC Lic. No. F-0270

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED