

M.A.LEE

R.NELSON

DRAWN BY : ____

CHECKED BY : .

_ DATE : <u>9/2017</u>

_ DATE : <u>10/2017</u>

SUMMARY OF QUANTITIES FOR WEST APPROACH ESTIMATE ACTUAL SCARIFYING BRIDGE DECK 131.3 SY 131.3 SY HYDRO-DEMOLITION OF BRIDGE DECK CLASS II SURFACE PREPARATION GROOVING BRIDGE DECK 1168.4 SF SUMMARY OF QUANTITIES FOR EAST APPROACH ESTIMATE ACTUAL SCARIFYING BRIDGE DECK 131.3 SY HYDRO-DEMOLITION OF BRIDGE DECK 131.3 SY CLASS II SURFACE PREPARATION GROOVING BRIDGE DECK 1168.4 SF

THE EXISTING BRIDGE DECK HAS AN ASPHALT WEARING SURFACE. IT IS POSSIBLE THAT CLASS II SURFACE PREPARATION MIGHT BE NECESSARY, BUT CANNOT BE ESTIMATED WITH THE AWS PRESENT. THE QUANTITY INDICATED IS FOR BIDDING PURPOSES ONLY, THE ACTUAL QUANTITY SHALL BE CONFIRMED AFTER SCARIFICATION OF BRIDGE DECK.

PAYMENT FOR CLASS II SURFACE PREPARATION. IS BASED UPON SQUARE FEET OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING SCARIFICATION OF BRIDGE DECK. SEE "OVERLAY SURFACE PREPARATION" SPECIAL PROVISION.

SCARIFYING AND HYDRO-DEMOLITION OF BRIDGE DECK

APPROX.AREA CLASS II

- APPROX. AREA CLASS II SURFACE PREPARATION


- BRIDGE JOINT DEMOLITION

- TEST LOCATIONS

NO DEFICIENCIES NOTED DURING FIELD SCOPING INSPECTION.
THE CONTRACTOR AND ENGINEER SHALL INSPECT THE DECK
SURFACE AFTER SCARFICATION FOR POTENTIAL CLASS II
REPAIRS.

PROJECT NO. I-5889A BUNCOMBE COUNTY 358

BRIDGE NO._



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SURFACE PREPARATION APPROACH ROADWAY SLABS

2610 Wycliff Road Gannett Fleming (919) 420-7660 Excellence Delivered As Promised NC Lic. No. F-0270

OCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SHEET NO REVISIONS NO. BY: S-92 DATE: TOTAL SHEETS