

SUMMARY OF QUANTITIES FOR WEST APPROACH ESTIMATE ACTUAL SCARIFYING BRIDGE DECK 95.0 SY HYDRO-DEMOLITION OF BRIDGE DECK 95.0 SY CLASS II SURFACE PREPARATION GROOVING BRIDGE DECK 786.7 SUMMARY OF QUANTITIES FOR EAST APPROACH ESTIMATE ACTUAL SCARIFYING BRIDGE DECK 95.0 SY HYDRO-DEMOLITION OF BRIDGE DECK 95.0 SY CLASS II SURFACE PREPARATION 786.7 GROOVING BRIDGE DECK

NOTES:

THE EXISTING BRIDGE DECK HAS AN ASPHALT WEARING SURFACE, IT IS POSSIBLE THAT CLASS II SURFACE PREPARATION MIGHT BE NECESSARY, BUT CANNOT BE ESTIMATED WITH THE AWS PRESENT. THE QUANTITY INDICATED IS FOR BIDDING PURPOSES ONLY, THE ACTUAL QUANTITY SHALL BE CONFIRMED AFTER SCARIFICATION OF BRIDGE DECK.

PAYMENT FOR CLASS II SURFACE PREPARATION. IS BASED UPON SQUARE FEET OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING SCARIFICATION OF BRIDGE DECK. SEE "OVERLAY SURFACE PREPARATION" SPECIAL PROVISION.

> SCARIFYING AND HYDRO-DEMOLITION OF BRIDGE DECK

APPROX. AREA CLASS II SURFACE PREPARATION

- BRIDGE JOINT DEMOLITION

- TEST LOCATIONS

NO DEFICIENCIES NOTED DURING FIELD SCOPING INSPECTION.
THE CONTRACTOR AND ENGINEER SHALL INSPECT THE DECK
SURFACE AFTER SCARFICATION FOR POTENTIAL CLASS II
REPAIRS.

PROJECT NO. I-5889A

BUNCOMBE

378

_ COUNTY

BRIDGE NO. _

020208 Eir BML J 11/20/2017
BA9F91762D7044A...

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SURFACE PREPARATION APPROACH ROADWAY SLABS

SHEET NO. REVISIONS NO. BY: S-190 DATE: TOTAL SHEETS

PLAN OF EAST APPROACH SLAB

(SEE SHEET NO. S-170 FOR SECTIONS A-A AND D-D)

(SEE SHEET NO.S-170 FOR SECTIONS A-A AND D-D)

PLAN OF WEST APPROACH SLAB

2610 Wycliff Road

OOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED Gannett Fleming Raleigh NC 27607-3073 (919) 420-7660 Excellence Delivered As Promised NC Lic. No. F-0270

M.A.LEE _ DATE : <u>10/2017</u> DRAWN BY : ____ _ DATE : <u>10/2017</u> R.NELSON CHECKED BY : .