PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.05.13.10921.1, etc.	9	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	4457000000-N TEMPORARY TRAFFIC CONTROL	4510000000-N LAW ENFORCEMENT	4685000000-E 4" X 90 M YELLOW THERMO	4685000000-E 4" X 90 M WHITE THERMO	4686000000-E 4" X 120 M YELLOW THERMO	4686000000-E 4" X 120 M WHITE THERMO	4688000000-E 6" X 90 M YELLOW THERMO	4688000000-E 6" X 90 M WHITE THERMO	4690000000-E 6" X 120 M WHITE THERMO	4695000000-E 8" X 90 M WHITE THERMO	4695000000-E 8" X 90 M YELLOW THERMO	4697000000-E 8" X 120 M WHITE THERMO	4700000000-E 12" X 90 M YELLOW THERMO	4700000000-E 12" X 90 M WHITE THERMO	4702000000-E 12" X 120 M WHITE THERMO	4705000000-E 16" X 120 M WHITE THERMO
							MI	FT	SF	LS	HR	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF
2018CPT.05.13.10921.1	Wake	1	US 1 NORTH BOUND - CAPITAL BLVD	.1 MI N OF US 1A TO NC 98 - DURHAM RD (INCLUDE EXIT RAMPS)	4	3	2.19	32-80	484	0.07	120	256				14,858	14,899	6,399				12	3,568		
		2	US 1 SOUTH BOUND - CAPITAL BLVD	NC 98 - DURHAM RD TO .1 MI N OF US 1A (INCLUDE EXIT RAMPS)	4	3	2.19	32-80	488	0.07	40					15,183	15,321	5,988					3,639		
TOTAL FOR PROJ NO. 2018CPT.05.13.10921.1							**4.38**		**972**	**0.14**	**160**	**256**				**30,041**	**30,220**	**12,387**				**12**	**7,207**		
												256				**60,261**						**7,219**			
2018CPT.05.13.20921.1	Wake	3	SR 1900 - BOYCE BRIDGE RD	START OF MAINTENANCE TO DEAD END	3	2	1.56	18	175	0.05			16,786	16,474											
		4	SR 1901 - OLD WEAVER TRL	SR 1907 - NEW LIGHT RD TO NC 50	3	2	4	24	447	0.13			43,040	39,971	83										
		5	SR 1903 - OLIVE GROVE CHURCH RD/BOYCE RD	SR 1901 - OLD WEAVER TRL TO DEAD END	3	2	2.33	20	260	0.07			25,071	24,482											
		6	SR 1906 - BEAVER DAM RD	GRANVILLE CO TO SR 1901 - OLD WEAVER TRL	3	2	1.88	20	211	0.06			20,229	19,900	63										
		7	SR 1967 - OLD NC 98	480' WEST OF SR 2000 - FALLS OF NEUSE RD TO DEAD END	3	2	1.1	20	123	0.03			11,836	8,178	101										
		8	SR 1975 - OLIVE GROVE CHURCH RD	SR 1903 - BOYCE RD TO END MAINT	3	2	0.4	18	44	0.01			4,304	4,222											
		9	SR 2005 - HONEYCUTT RD	SR 2000 - FALLS OF NEUSE RD TO SR 2007 - BRASSFIELD RD (SKIP SR - 2006 DURANT RD INTERSECTION)	3	2	2.73	20-44	305	0.09	40		29,375	31,699	1,328							312			
		10	SR 2006 - DURANT RD	US 1 -CAPITAL BLVD TO SR 2000 - FALLS OF NEUSE RD (SKIP CAMP DURANT RD INTERSECTION)	5	5	2.49	62-96	279	0.08	240			27,456	9,527				574		1,825		36	1,532	450
		11	SR 2036 - NEW HOPE RD	.11 MI S OF WILLOW OAK RD. TO US 401 - LOUISBURG RD	5	5	2.74	60-72	375	0.10	240			15,750	12,437						1,700	84			
		12	SR 2206 - MARSH CREEK RD	SR 2205 - TRAWICK RD TO SR 2036 - NEW HOPE RD	3	2	0.68	24-48	76	0.02			7,317	9,390	861				159	96					
		13	SR 2108 - NEW HOPE RD	0.1 MI N OF US 401 - LOUISBURD RD TO US 1 - CAPITAL BLVD	5	5	0.62	64-70	69	0.01	80			8,185	1,637						132	72		132	
		14	SR 2212 - JAMES RD	US 401 - LOUISBURG RD ST TO SR 2036 - NEW HOPE RD	2	2	0.3	22	41	0.01															
		15	SR 2213 - KYLE DR/VALLEY STREAM DR	US 401 - LOUISBURG RD TO US 401 - LOUISBURG RD	2	2	1.35	20-36	151	0.03			14,526	14,260	404										
		16	SR 2215 - BUFFALOE RD	.04 MI E OF SR 2214 - SOUTHALL RD TO US 1 - CAPITAL BLVD	5	5	1.71	60-72	192	0.05	160			16,149	6,054				259	129	479				
		17	SR 2255 - WOODLAWN DR	SR 2036 - NEW HOPE RD TO CUL-DE-SAC	2	2	0.29	24	38	0.01															
		18	SR 2264 - JANE LN	SR 2036 - NEW HOPE RD TO DEAD END	1	2	0.3	18-34	38	0.01			3,658												
		19	SR 2291 - WEDGEWOOD DR	SR 2036 - NEW HOPE RD TO END MAINT	2	2	0.31	23-27	35	0.01															
		20	SR 2294 - STONEWALL DR	SR 2291 - WEDGEWOOD DR TO END MAINT	2	2	0.16	23	16	0.01															
		21	SR 2295 - REBEL CIR	SR 2294 - STONEWALL DR TO CUL-DE-SAC	2	2	0.05	23	6	0.01															
		22	SR 2517 - N ROGERS LN	SR 5275 - N ROGERS LN TO BRIDGE	2	2	1.14	52-70	128	0.02			1,425	11,063	2,517				402		919	288	125	769	
		23	SR 2517 - ANDERSON POINT DR	SR 2625 - ROBBINS DRIVE TO GILMAN LN	2	2	0.23	23	26	0.01			2,475	1,518											
		24	SR 2917 - VALLEY STREAM DR	SR 2919 - STILLMEADOW RD TO END MAINT	2	2	0.23	23	26	0.01															
		25	SR 2918 - FALLBROOK CIR	SR 2917 - VALLEY STREAM DR TO CUL-DE-SAC	2	2	0.1	23	11	0.01															
		26	SR 2919 - STILLMEADOW RD	SR 2214 - SOUTHALL RD TO END MAINT	2	2	0.18	23	24	0.01															
		27	SR 5275 - N ROGERS LN	US 64 - NEW BERN AVE TO SR 2517 - N ROGERS LN	2	2	0.33	63-72	37	0.01	40			2,755	1,479				585		166		64	1,246	
TOTAL FOR PROJ NO. 2018CPT.05.13.20921.1							**27.21**		**3,133**	**0.86**	**800**		**180,042**	**251,452**	**36,491**				**1,979**	**225**	**5,221**	**756**	**225**	**3,679**	**450**
												180,042		**287,943**					**2,204**			**981**			
GRAND TOTAL							**31.59**		**4,105**	**1.00**	**960**	**256**	**180,042**	**251,452**	**36,491**	**30,041**	**30,220**	**12,387**	**1,979**	**225**	**5,221**	**768**	**7,432**	**3,679**	**450**
												180,298		**287,943**		**60,261**			**2,204**			**8,200**			