PROJ. REFERENCE NO.	SHEET NO.
B-5373	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00000	0	0
11+75.00000	6	3
12+00.00000	13	1
12+25.00000	19	2
12+50.00000	21	4
12+75.00000	24	9
13+00.00000	19	19
13+25.00000	4	33

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+25.00000	0	0
14+50.00000	9	16
14+75.00000	17	13
15+00.00000	11	9
15+25.00000	3	4
15+50.00000	1	2
15+75.00000	1	3
16+05.00000	1	2