PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.12.07.10231, 2018CPT.12.07.20231	14	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	AGGRE-GATE SHOULDER BORROW	INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	1½" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, S9.5C	LEVELING COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #6M STONE	EMULSION FOR ASPHALT SURFACE TREATMENT	RETROFIT EXISTING CURB RAMP	CONC CURB RAMPS	ADJ. OF DROP INLETS	ADJ. OF MAN-HOLES	ADJ. OF COMMUNI CATIONS MANHOLES	ADJ. OF METER OR VALVE BOXES	JUNCTION BOX (STANDARD SIZE)	INDUCTIVE LOOP SAW-CUT	LEAD-IN CABLE (14-2)
									MI	FT	TON	TONS	SMI	SY	SY	TONS	TONS	TON	TONS	TONS	TONS	TONS	SY	GAL	EA	EA	EA	EA	EA	EA	EA	LF	LF
		1	NC 150 (GAFFNEY HWY)	SC STATELINE TO SR 1146	12	2	NO	NO	3.41	VAR. 21-33	1,194	70	6.82		650				4,903	1,110	366	1,370	58,004	23,202									
		2	NC 180 (S POST RD)	NC 226 (CLEV AVE) TO PROJECT LIMITS FOR W-5712A (325' S. OF NC 226 EARL RD)	2	2	NO	NO	1.57	VAR. 22-36	550	95	3.14		240				2,338	110	147	374								1		200	120
		3	NC 182 (STAGECOACH TR)	SR 1004 TO NC 18	5 12 3	2 2 2	NO	NO	0.89 2.53 0.03	VAR. 33-37 VAR. 24-25 VAR. 35-37	886	45	5.09	20,448	120				5,140	300	328	1,350	41,177	16,470	10	1		1	1			175	105
2018CPT.12.07.10231	Cleveland	4	NC 216 (BATTLEGROUND RD)	SC STATELINE TO US 29	12	2	NO	NO	1.22	VAR. 22-24	427	50	2.44		1,400				1,483	170	100	475	17,545	7,018									
		5	NC 216 (S BATTLEGROUND AVE)	US 29 TO LACKEY ST	2 4 5 6 1 7	2 2 2 2 4 4	NO	NO	3.97 0.76 0.50 0.07 0.10 0.20	VAR. 23-58 VAR. 23-49 VAR. 32-61 32 50 VAR. 59-69	1,523	135	8.70	38,708	2,000				9,099	676	590	2,436			15	5	3	11		15	2	2,000	1,200
TOTAL FOR PROJ NO. 2018CPT.12.07.10231									**15.25**		**4,580**	**395**	**26.19**	**59,156**	**4,410**				**22,963**	**2,366**	**1,531**	**6,005**	**116,726**	**46,690**	**25**	**6**	**3**	**12**	**1**	**16**	**2**	**2,375**	**1,425**
		6	SR 1004 (CASAR-LAWNDALE RD)	NC 10 TO NC 182	12 5	2 2	NO	NO	7.87 0.06	VAR. 20-21 VAR. 33-36	2,755		15.74	1,300	1,700				8,866	1,761	646	2,900	103,571	41,428					1				
		7	SR 1100 (SULFUR SPRINGS RD)	NC 226 TO NC 180	1 12	2 2	NO	NO	0.04 3.02	VAR. 18-23 VAR. 18-19	1,057		6.04	600	972				3,189	159	202	462	37,211	14,885								200	100
		8	SR 1106 (S MORGAN ST)	SR 1105 TO NC 18	2 5 1	2 2 2	NO	NO	1.75 0.23 0.04	VAR. 18-35 VAR. 21-22 VAR. 36-37	613	50	3.50	4,208	950				2,275	113	144	364			2					3			
		9	SR 1112 (SEATLE ST)	NC 18 TO NC 150	2	2	NO	NO	0.25	VAR. 18-42	88	14	0.50		75				322	16	20	33											
		10	SR 1161 (WESTLEE ST)	448 FT N OF SR 1319 TO SR 1323	2	2	NO	NO	1.25	VAR. 18-19	438	70	2.50		512				1,296	293	97	285											
		11	SR 1237 (WEASE DR)	NC 18 TO DEAD END	8	2	NO	NO	0.12	VAR. 17-18		10					78				5	14											
		12	SR 1313 (WASHBURN SWITCH/HUGH HARRILL)	SR 1323 TO SR 1337	12	2	NO	NO	2.11	VAR. 19-21	739	59	4.22		120				2,079	100	131	333	24,596	9,839									
		13	SR 1337 (E. ZION CH RD)	NC 226 TO NC 18	1 2 9 1 10	3 2 2 1 2	NO	NO	0.02 1.46 0.19 0.13 2.27	VAR. 35-39 VAR. 25-35 VAR. 25-26 VAR. 19-21 VAR. 24-25	1,306	162	7.46	1,520	670	2,330			5,511	803	488	1,115											
		14	SR 1351 (NEW HOUSE RD)	RUTHERFORD CL TO SR 1323	1 2	2 2	NO	NO	0.71 6.59	VAR. 24-25 VAR. 22-25	2,307	146	13.18	11,111	200				9,557	3,125	777	950			4								
		15	SR 1605 (KAY RD)	NC 18 TO SR 1606	2	2	NO	NO	0.39	19	137	50	0.78		120				415	20	26	42											
		16	SR 1683 (DEER MEADOW)	NC 18 TO CULDESAC	8	2	NO	NO	0.26	20							189	19			13	18											
		17	SR 1684 (MEADOWVIEW)	SR 1683 TO SR 1685	8	2	NO	NO	0.09	20							65				4	6											
		18	SR 1685 (BUCK HAVEN)	SR 1684 TO CULDESAC	8	2	NO	NO	0.21	20							152	15			10	8											
		19	SR 1686 (STONEBROOK)	SR 1683 TO CULDESAC	8	2	NO	NO	0.05	20							36				2	3											
		20	SR 1687 (SNOW HILL)	SR 1683 TO CULDESAC	8	2	NO	NO	0.1	20							73				4	8											
		21	SR 1848 (FREDERICK ST)	NC 18 TO END C&G	1	2	NO	NO	0.6	VAR. 28-33				10,932					924	55	59	167			10	2		6		10	1	200	90
		22	SR 2021 (LINWOOD RD)	2ND ST TO NC 216	1 5 2	4 2 2	NO	NO	0.11 0.08 0.16	VAR. 32-49 VAR. 31-32 VAR. 32-36	56		0.32	5,105	50				737	35	46	155				1	4	3		1	1	275	150
		23	SR 2039 (WRIGHT RD)	SR 2034 TO SR 2038	2	2	NO	NO	0.39	VAR. 18-19	140	84	0.78		60				402	20	25	40											
		24	SR 2047 (BORDERS RD)	SR 2033 TO SR 2052	2	2	NO	NO	0.98	VAR. 18-24	343	45	1.96		30				1,133	58	72	114											
		25	SR 2052 (ELIZABETH AVE)	US 74 BUS TO NC 180	1 2	2 2	NO	NO	0.06 0.59	VAR. 22-37 VAR. 20-22	207	20	1.18	1,162	1,200				727	30	46	100							1			450	200
2018CPT.12.07.20231	Cleveland	26	SR 2063 (KEMPER RD)	US 74 BUS TO DEAD END	2 3 11	2 2 2	NO	NO	0.36 0.07 0.06	24 VAR. 30-45 VAR. 30-40		25	0.85	4,505	220				754	38	48	91										150	95
		27	SR 2076 (CHARCOAL RD)	SR 2075 TO CULDESAC	8	2	NO	NO	0.38	VAR. 18-19		110					252	12			16	25											
		28	SR 2180 (DUNES DR)	SR 1001 TO CULDESAC	8	2	NO	NO	0.55	20							399	20			25	8											
		29	SR 2181 (QUAIL HOLLOW DR)	SR 2180 TO CULDESAC	8	2	NO	NO	0.6	20							435	21			28	43											
		30	SR 2182 (CANTERBURY DR)	SR 2180 TO CULDESAC	8	2	NO	NO	0.24	20							174	8			11	17											
		31	SR 2184 (HIGHLAND CIR)	SR 2052 TO SR 2190	8	2	NO	NO	0.28	VAR. 19-20							198	10			13	19											
		32	SR 2190 (NEW CREST LN)	SR 2184 TO SR 2184	8	2	NO	NO	0.33	VAR. 19-20							234	11			15	22											
		33	SR 2236 (HICKS RD)	US 29 TO DEAD END	2	2	NO	NO	0.14	20	49		0.28						153	23	11	40											
		34	SR 2256 (PHIFER RD)	US 74 BUSINESS TO SR 2487	3 2 1 4	2 2 3 3	NO	NO	0.02 1.14 0.22 0.27	25 VAR. 24-36 VAR. 36-37 VAR. 36-48	450		2.57	12,156	120				2,790	167	178	447			4	5		4		3	1	400	250
		35	SR 2317 (SERVICE RD)	US 74 TO US 74	2	2	NO	NO	0.32	VAR. 22-23	112		0.64		120				392	19	25	39										190	100
		36	SR 2339 (DELMAR RD)	SR 1100 TO SR 2505	8	2	NO	NO	0.28	20							203	10			13	20											
		37	SR 2416 (CEDARWOOD)	GREEN OAK DR TO COTTONWOOD DR	8	2	NO	NO	0.12	VAR. 19-20							85				5	8											
		38	SR 2459 (APPLE HILL DR)	SR 2200 TO CULDESAC	8	2	NO	NO	0.24	18							157	8			10	15											
		39	SR 2460 (CIDER DR)	CULDESAC TO CULDESAC	8	2	NO	NO	0.34	18							222	11			14	22											
		40	SR 2462 (GOLDMINE SCH RD)	SR 2292 TO DEAD END	8	2	NO	NO	0.14	VAR. 13-18							86				5	8											
		41	SR 2463 (PENNANT DR)	SR 2283 TO CULDESAC	8	2	NO	NO	0.08	VAR. 18-19		25					54				3	6											
		42	SR 2464 (KINGSVIEW AVE)	SR 2459 TO CULDESAC	8	2	NO	NO	0.12	18							78				5	7											
		43	SR 2504 (KIMBERLEE DR)	SR 2339 TO SR 2505	8	2	NO	NO	0.12	20							87				5	8											
		44	SR 2505 (STONE ST)	SR 1100 TO SR 2339	8	2	NO	NO	0.19	20							138	7			9	13											
		45	SR 2542 (KEN DAVES RD)	SR 1158 TO DEAD END	8	2	NO	NO	0.34	20							247	12			16	24											
		46	SR 2564 (DIXIE DR)	NC 18 TO END MAINT	8	2	NO	NO	0.31	VAR. 20-21							235	15			15	42											
		47	SR 2608 (MUIRFIELD DR)	SR 2180 TO CULDESAC	8	2	NO	NO	0.42	20							305	15			19	29											
		48	SR 2656 (MAGGIE DR)	SR 2008 TO CULDESAC	8	2	NO	NO	0.09	18							59				4	5											
		49	SR 2665 (PINE LAKE DR)	SR 2181 TO CULDESAC	8	2	NO	NO	0.15	20							109	5			7	10											
		50	SR 2666 (CASTLE CT)	NC 216 TO CULDESAC	2	2	NO	NO	0.66	20	231	190	1.32		25				720	87	49	209											
		51	SR 2689 (POINTE COVE DR)	SR 2627 TO CULDESAC	8	2	NO	NO	0.08	18							52				3	5											
		52	SR 2690 (LAKE FIELD CT)	SR 2627 TO CULDESAC	8	2	NO	NO	0.07	18							46				3	8											
		53	SR 2691 (RIDGECREST DR)	SR 2694 TO SR 2627	8	2	NO	NO	0.35	18							229	12			15	22											
		54	SR 2692 (LAUREL COVE)	SR 2694 TO CULDESAC	8	2	NO	NO	0.06	18							39				2	8											
		55	SR 2693 (RIDGE CT)	SR 2694 TO CULDESAC	8	2	NO	NO	0.09	18							59				4	5											
		56	SR 2694 (LAUREL RIDGE DR)	SR 2627 TO SR 2691	8	2	NO	NO	0.31	18							203	10			13	20											
TOTAL FOR PROJ NO. 2018CPT.12.07.20231									**41.72**		**11,028**	**1,060**	**63.82**	**52,599**	**7,144**	**2,330**	**4,978**	**221**	**42,242**	**6,922**	**3,406**	**8,362**	**165,378**	**66,152**	**20**	**8**	**4**	**13**	**2**	**17**	**3**	**1,865**	**985**
GRAND TOTAL									**56.97**		**15,608**	**1,455**	**90.01**	**111,755**	**11,554**	**2,330**	**4,978**	**221**	**65,205**	**9,288**	**4,937**	**14,367**	**282,104**	**112,842**	**45**	**14**	**7**	**25**	**3**	**33**	**5**	**4,240**	**2,410**