


**EDI MODEL 2018ECL-NC CONFLICT MONITOR
PROGRAMMING DETAIL**

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Program phases 4 and 8 for Dual Entry.
3. Enable Simultaneous Gap-Out for all Phases.
4. Program phases 2 and 6 for Variable Initial and Gap Reduction.
5. Program phases 2 and 6 for Startup In Green.
6. Program phases 2 and 6 for Yellow Flash, and overlap 1 as Wag Overlaps.
7. The cabinet and controller are part of the NC 59 Closed Loop System.

EQUIPMENT INFORMATION

CONTROLLER.....2070
 CABINET.....332 W/ AUX
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...18 WITH AUX. OUTPUT FILE
 LOAD SWITCHES USED.....S1,S2,S5,S7,S8,S11,AUX S1,AUX S4
 PHASES USED.....1,2,4,5,6,8
 OVERLAP "A".....1+2
 OVERLAP "B".....NOT USED
 OVERLAP "C".....5+6
 OVERLAP "D".....NOT USED

SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	11	21,22	NU	NU	41,42	NU	42	51	61,62	NU	NU	81,82	NU	11	NU	NU	51	NU
RED		128			101			*	134			107						
YELLOW	*	129			102				135			108						
GREEN		130			103				136			109						
RED ARROW													A121			A114		
YELLOW ARROW							132						A122			A115		
FLASHING YELLOW ARROW													A123			A116		
GREEN ARROW	127						133	133										

NU = Not Used

* Denotes install load resistor. See load resistor installation detail this sheet.

★ See pictorial of head wiring in detail this sheet.

INPUT FILE POSITION LAYOUT

(front view)

FILE "I"	1	2	3	4	5	6	7	8	9	10	11	12	13	14
U	∅ 1A	NOT USED	∅ 1S	∅ 1S	∅ 1S	∅ 4A	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	FS
L	NOT USED	∅ 2/SYS	∅ 1S	∅ 1S	∅ 1S	NOT USED	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	DC ISOLATOR
U	∅ 5A	∅ 5B	NOT USED	∅ 1S	∅ 1S	∅ 8A	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	DC ISOLATOR
L	NOT USED	NOT USED	∅ 6/SYS	∅ 1S	∅ 1S	∅ 8B	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	∅ 1S	DC ISOLATOR

EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
 ST = STOP TIME

⊗ Wired Input - Do not populate slot with detector card


INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
1A ¹	TB2-1,2	I1U	56	18	1	1	Y	Y			15
	-	J4U	48	10	26	6	Y	Y	Y		3
2B/S02	TB2-7,8	I2L	43	5	12	2/SYS	Y	Y			
4A	TB4-9,10	I6U	41	3	4	4	Y	Y			3
5A ²	TB3-1,2	J1U	55	17	5	5	Y	Y			15
	-	I4U	47	9	22	2	Y	Y	Y		3
5B	TB3-5,6	J2U	40	2	6	5	Y	Y			15
6B/S15	TB3-11,12	J3L	77	39	46	6/SYS	Y	Y			
8A	TB5-9,10	J6U	42	4	8	8	Y	Y			3
8B	TB5-11,12	J6L	46	8	18	8	Y	Y			15

¹Add jumper from I1-W to J4-W, on rear of input file.


²Add jumper from J1-W to I4-W, on rear of input file.

INPUT FILE POSITION LEGEND: J2L



FYA SIGNAL WIRING DETAIL

(wire signal heads as shown)



NOTE


The sequence display for signal heads 11 and 51 requires special logic programming. See sheet 2 for programming instructions.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 06-0946T4
 DESIGNED: September 2017
 SEALED: 11-28-17
 REVISED: N/A

LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown below)

VALUE (ohms)	WATTAGE
1.5K - 1.9K	25W (min)
2.0K - 3.0K	10W (min)



Electrical Detail - Sheet 1 of 2 - Temp,4 (Phase III)

Electrical and Programming Details for: **NC 59 (South Main Street) at I-95 Bus./US 301 SB Ramp / SR 2285 (Shipman Road)**

Prepared In the Offices of: **James Peterson**

Division 6 Cumberland County Hope Mills

PLAN DATE: November 2017 REVIEWED BY:

PREPARED BY: James Peterson REVIEWED BY:

REVISIONS: _____ INIT. DATE

DocuSigned by: **Keith M. Mins** 12/1/2017

750 N. Greenfield Pkwy, Garner, NC 27529

SEAL: **KEITH M. MINS** ENGINEER 036880

SIG. INVENTORY NO. 06-0946T4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED