PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.09.01.10291, 2018CPT.09.02.20291	15	
2018CPT.08.06.20761,		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXCAVATION	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E MILLING ASPHALT PAVEMENT, 1 1/2"DEPTH	1308000000-E MILLING ASPHALT PAVEMENT, 0"TO 1 1/2" DEPTH	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2815000000-N ADJ. OF DROP INLET	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	5255000000-N PORTABLE LIGHTING	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE
										MI	FT	CY	TONS	SMI	SY	SY	SY	TONS	TONS	TONS	TONS	EA	EA	EA	LS	LF	LF
2018CPT.09.01.10291	Davidson	1	NC 8	FROM PAVEMENT JT AT NC 47 TO BRIDGE NO.92 OVER I-85	1,2	5	2WU	NO	NO	1.52	varies 60-76	25	50	0.20	60,557				5,861	352	20		20	14		82	8
TOTAL FOR MAP NO. 1										**1.52**		**25**	**50**	**0.20**	**60,557**				**5,861**	**352**	**20**		**20**	**14**		**82**	**8**
2018CPT.09.01.10291	Davidson	2	NC 8 / TALBERT BLVD.	FROM NC 8 / COTTON GROVE RD. TO W. M.L.K JR. BLVD. / RALEIGH RD. SR 2205	1,2	2	M2	NO	NO	1.702	varies 24-56	30		0.25	44,164				4,278	257	20		19	12		101	10
TOTAL FOR MAP NO. 2										**1.702**		**30**		**0.25**	**44,164**				**4,278**	**257**	**20**		**19**	**12**		**101**	**10**
2018CPT.09.01.10291	Davidson	3	NC 8 / W. M.L.K. JR. BLVD.	NC 8 / TALBERT BLVD. TO N. MAIN ST. SR 3346	2	2	M2	NO	NO	0.769	varies 22-48				17,552				1,701	102	20		26	16	*		
TOTAL FOR MAP NO. 3										**0.769**					**17,552**				**1,701**	**102**	**20**		**26**	**16**			
2018CPT.09.01.10291	Davidson	4	NC 8 / E. 5TH ST SOUTH BOUND	N. MAIN ST. SR 3346 TO END OF CONC MEDIAN NOSE AT BEGIN 48 FT. WIDTH	2	2	MU	NO	NO	0.288	varies 32-33				5,811				563	34	20		2				
TOTAL FOR MAP NO. 4										**0.288**					**5,811**				**563**	**34**	**20**		**2**				
2018CPT.09.01.10291	Davidson	5	NC 47/SALISBURY ST.	NC 109/GLENN ST. TO APPROX. 95 FT. W. OF N. JONES ST. INTERSECTION (MILL LOOPS)	2	2	2WU	NO	NO	0.431	varies 43-44				10,873				1,053	63	20	16	7	8			
TOTAL FOR MAP NO. 5										**0.431**					**10,873**				**1,053**	**63**	**20**	**16**	**7**	**8**			
2018CPT.09.01.10291	Davidson	6	NC 109	FROM PVMT. JT SOUTH OF NC 49 TO RANDOLPH CO. LINE	1	2	2WU	NO	NO	3.41	varies 24-26	409	246	6.82	48,013				4,751	285	413					1,364	136
TOTAL FOR MAP NO. 6										**3.41**		**409**	**246**	**6.82**	**48,013**				**4,751**	**285**	**413**					**1,364**	**136**
2018CPT.09.01.10291	Davidson	7	NC109/NC47	FROM PVMT JT. SOUTH OF KLOPMAN MILL RD. SR 2559 TO PVMT. JT. SOUTH OF TOMS CREEK CHURCH RD. SR 2338	1,2	2	2WU	NO	NO	1.894	varies 25-54	76	24	1.27	42,668				4,135	248	20		11	8		253	25
TOTAL FOR MAP NO. 7										**1.894**		**76**	**24**	**1.27**	**42,668**				**4,135**	**248**	**20**		**11**	**8**		**253**	**25**
2018CPT.09.01.10291	Davidson	8	NC 150	FROM PVMT JT. NORTH OF OLD SALISBURY RD. SR 1147 TO PVMT JT AT SWICEGOOD RD SR 1155	3	2	2WU	NO	NO	0.804	22	96	111	1.61	11,310				1,467	88	20			2		321	32
TOTAL FOR MAP NO. 8										**0.804**		**96**	**111**	**1.61**	**11,310**				**1,467**	**88**	**20**			**2**		**321**	**32**
TOTAL FOR PROJ NO. 2018CPT.09.01.10291										**10.818**		**636**	**431**	**10.15**	**240,948**				**23,809**	**1,429**	**553**	**16**	**85**	**60**		**2,121**	**211**
2018CPT.09.02.20291	Davidson	9	HILLTOP DR. SR 1290	E.O.P. AT TRADING FORD WAY SR 1138 TO END OF MAINTENANCE	4	2	2WU	NO	NO	0.209	19	25	33	0.42				316		21						84	8
TOTAL FOR MAP NO. 9										**0.209**		**25**	**33**	**0.42**				**316**		**21**						**84**	**8**
2018CPT.09.02.20291	Davidson	10	TRADING FORD WAY SR 1138	FROM SOWERS RD. SR 1139 SOUTH TO YORK HILL RIVER BOAT ACCESS	4	2	2WU	NO	NO	0.65	19	78	189	1.30				692		47						260	26
TOTAL FOR MAP NO. 10										**0.65**		**78**	**189**	**1.30**				**692**		**47**						**260**	**26**
2018CPT.09.02.20291	Davidson	11	TRADING FORD WAY SR 1138	SOWERS RD. SR 1139 NORTH TO END OF MAINTENANCE	4	2	2WU	NO	NO	0.371	20	45	72	0.74				431		30						148	15
TOTAL FOR MAP NO. 11										**0.371**		**45**	**72**	**0.74**				**431**		**30**						**148**	**15**
2018CPT.09.02.20291	Davidson	12	W. CENTER ST. EXT. SR 1242	W. CENTER ST. SR 1243 TO NC 150	5,7	2	2WU	NO	NO	4.784	varies 24-36	553	417	9.22		2,653	1,344		6,735	404	20	2	1	8		1,843	184
TOTAL FOR MAP NO. 12										**4.784**		**553**	**417**	**9.22**		**2,653**	**1,344**		**6,735**	**404**	**20**	**2**	**1**	**8**		**1,843**	**184**
2018CPT.09.02.20291	Davidson	13	ROWE RD. SR 1203	OLD US 64 TO US 64	4	2	2WU	NO	NO	0.607	19	73	120	1.21				646		43						243	24
TOTAL FOR MAP NO. 13										**0.607**		**73**	**120**	**1.21**				**646**		**43**						**243**	**24**
2018CPT.09.02.20291	Davidson	14	TYRO RD. SR 1213	OLD SALISBURY RD. SR 1147 TO NC 150	5	2	2WU	NO	NO	3.636	varies 22-23	436	264	7.27			511		4,863	292				8		1,454	145
TOTAL FOR MAP NO. 14										**3.636**		**436**	**264**	**7.27**			**511**		**4,863**	**292**				**8**		**1,454**	**145**
2018CPT.09.02.20291	Davidson	15	HARGRAVE LN. SR 3165	HARGAVE RD./ NC 47 TO E.O.M. AT PVMT JT. AT MASTERBRAND	1,2	2	2WU	NO	NO	0.405	varies 24-36	34	10	0.28	9,682				938	56			3	1		114	11
TOTAL FOR MAP NO. 15										**0.405**		**34**	**10**	**0.28**	**9,682**				**938**	**56**			**3**	**1**		**114**	**11**
2018CPT.09.02.20291	Davidson	16	LAMBETH RD. SR 2067	NC 109 PVMT. JT. TO E.OP. AT KENNEDY RD. SR 2066	5	2	2WU	NO	NO	0.111	varies 24-26	13	24	0.22		500	1,567		158	9						44	4
TOTAL FOR MAP NO. 16										**0.111**		**13**	**24**	**0.22**		**500**	**1,567**		**158**	**9**						**44**	**4**
2018CPT.09.02.20291	Davidson	17	OLD FARM RD. SR 2800	TOWER RD. SR 2062 TO RANDOLPH CO. LINE	4A	2	2WU	NO	NO	0.398	20		6					446		31							
TOTAL FOR MAP NO. 17										**0.398**			**6**					**446**		**31**							
2018CPT.09.02.20291	Davidson	18	SINGLE TREE LN. SR 2801	OLD FARM RD. SR 2800 TO END OF MAINTENANCE	4A	2	2WU	NO	NO	0.261	19		3					303		20							
TOTAL FOR MAP NO. 18										**0.261**			**3**					**303**		**20**							
2018CPT.09.02.20291	Davidson	19	SPLITRAIL CIR. SR 2805	OLD FARM RD. SR 2800 TO END OF MAINTENANCE	4A	2	2WU	NO	NO	0.076	20							110		8							
TOTAL FOR MAP NO. 19										**0.076**								**110**		**8**							
2018CPT.09.02.20291	Davidson	20	WAGON WHEEL RD. SR 2822	SINGLE TREE LN. SR 2801 TO RANDOLPH CO. LINE	4A	2	2WU	NO	NO	0.06	19		6					64		5				1			
TOTAL FOR MAP NO. 20										**0.06**			**6**					**64**		**5**				**1**			
2018CPT.09.02.20291	Davidson	21	OAK BUCKET RD. SR 2823	SINGLE TREE LN. SR 2801 TO RANDOLPH CO. LINE	4	2	2WU	NO	NO	0.06	20							67		5				1			
TOTAL FOR MAP NO. 21										**0.06**								**67**		**5**				**1**			
2018CPT.09.02.20291	Davidson	26	OLD US 64/RALEIGH RD. SR 2205	NC 8 TO SOUTH OF S. COUNTY HOME RD. SR 2222	1,2	2	2WU	NO	NO	2.385	varies 25-56	253	490	4.22	49,506				4,799	288	20		4	16	*	844	84
TOTAL FOR MAP NO. 26										**2.385**		**253**	**490**	**4.22**	**49,506**				**4,799**	**288**	**20**		**4**	**16**		**844**	**84**
2018CPT.09.02.20291	Davidson	27	E. 1ST ST SR 1001	FROM NC 109 TO MAIN ST. SR 2414	2	2	2WU	NO	NO	0.271	30				4,770				463	28		8	7	6			
TOTAL FOR MAP NO. 27										**0.271**					**4,770**				**463**	**28**		**8**	**7**	**6**			
2018CPT.09.02.20291	Davidson	28	FLOYD CHURCH RD. SR 2304/ PARKS RD. SR 2304	FROM NC 47 TO NC 8	6	2	2WU	NO	NO	5.872	varies 23-24	705	450	11.74					9,218	553	20			4		2,349	235
TOTAL FOR MAP NO. 28										**5.872**		**705**	**450**	**11.74**					**9,218**	**553**	**20**			**4**		**2,349**	**235**
TOTAL FOR PROJ NO. 2018CPT.09.02.20291										**20.156**		**2,215**	**2,084**	**36.63**	**63,958**	**3,153**	**3,422**	**3,075**	**27,174**	**1,840**	**60**	**10**	**15**	**45**		**7,383**	**736**
2018CPT.08.06.20761	Randolph	22	OLD FARM RD. SR 3152	DAVIDSON CO. LINE TO CEDAR TR. SR 3153	4	2	2WU	NO	NO	0.183	19		6					195		13							
TOTAL FOR MAP NO. 22										**0.183**			**6**					**195**		**13**							
2018CPT.08.06.20761	Randolph	23	WAGON WHEEL RD. SR 3207	DAVIDSON CO. LINE TO CEDAR TRAIL SR 3153	4	2	2WU	NO	NO	0.136	18		6					137		10				1			
TOTAL FOR MAP NO. 23										**0.136**			**6**					**137**		**10**				**1**			
2018CPT.08.06.20761	Randolph	24	OAK BUCKET RD. SR 3208	DAVIDSON CO. LINE TO END OF MAINTENANCE	4	2	2WU	NO	NO	0.105	19							156		11							
TOTAL FOR MAP NO. 24										**0.105**								**156**		**11**							
2018CPT.08.06.20761	Randolph	25	CEDAR TRAIL SR 3153	FROM END OF MAINTENANCE TO END OF MAINTENANCE	4	2	2WU	NO	NO	0.27	19		6					312		21							
TOTAL FOR MAP NO. 25										**0.27**			**6**					**312**		**21**							
TOTAL FOR PROJ NO. 2018CPT.08.06.20761										**0.694**			**18**					**800**		**55**				**1**			
GRAND TOTAL										**31.668**		**2,851**	**2,533**	**46.78**	**304,906**	**3,153**	**3,422**	**3,875**	**50,983**	**3,320**	**613**	**26**	**100**	**106**	**1**	**9,504**	**947**

NOTE: All Quantities listed include turn lanes and are estimates; Payment will be based on actual field measurements and quantities received.