From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions). Press 'NEXT' to advance to Preemption #3.

PREEMPTION #3 SETT INTERVAL/TIMING CLEA GRN YEL RED 123456 1 255 0.0 0.0 X X 2 0 0.0 0.0 3 0 0.0 0.0 4 0 0.0 0.0 4 0 0.0 0.0 5 0 0.0 0.0 EXIT CALLS	
PRIORITY (Y/N TO SELECT DELAY TIMER (0-255 SEC) MIN GREEN BEFORE PRE (0 PED CLEAR BEFORE PRE (0 YELLOW CLEAR BEFORE PRE (0 DWELL MIN TIMER (0-255 DWELL MAX TIMER (0-255 DWELL HOLD-OVER TIMER (LATCH CALL?	DEFAULT)1 DEFAULT)0 (O= DEFAULT)0 (O= DEFAULT)0.0 SEC)12 1-255MIN)0 0-255)0N NRN NRN ING DELAY?N PHASES?N ELLOW?N XTENSION?N L INTERVAL?N ERVAL?N

PRESS 'NEXT' TWICE

PREEMPTION #5 SETTINGS (NEXT:1-10) INTERVAL/TIMING : CLEAR/DWELL PHASES GRN YEL RED | 12345678910111213141516 1 255 0.0 0.0 | X X 2 0 0.0 0.0 | 3 0 0.0 0.0 4 0 0.0 0.0 5 0 0.0 0.0 EXIT CALLS PRIORITY (Y/N TO SELECT)MED DELAY TIMER (0-255 SEC) MIN GREEN BEFORE PRE (O= DEFAULT)....1 PED CLEAR BEFORE PRE (O= DEFAULT)....O YELLOW CLEAR BEFORE PRE (O= DEFAULT).0.0 RED CLEAR BEFORE PRE (0= DEFAULT)....0.0 DWELL MIN TIMER (0-255 SEC)7 DWELL MAX TIMER (0=OFF,1-255MIN)0 DWELL HOLD-OVER TIMER (0-255)0 LATCH CALL?N LINK TO NEXT PREEMPT?N ENABLE BACKUP PROTECTION?N HOLD CLEAR 1 PHASES DURING DELAY? ...N FAST GREEN FLASH DWELL PHASES?N PED CLEARANCE THROUGH YELLOW?N INHIBIT OVERLAP GREEN EXTENSION?N SERVICE DURING SOFTWARE FLASH?N REST IN RED DURING DWELL INTERVAL? .. N FLASH DWELL INTERVAL?N ALLOW PEDS IN DWELL INTERVAL?N RE-TIME DWELL INTERVAL?N OVERLAPS: ABCDEFGHIJKLMNOP DWELL INT FLASH YELLOW OMIT OVERLAPS:

PREEMPT PROGRAMMING COMPLETE


Program extend time on optical detector units for 5.0 sec for EVP3 and EVP5.

PROJECT REFERENCE NO. Sig. 2.3 U-4762

LOAD RESISTOR INSTALLATION DETAIL

(install resistors as shown below)

ACCEPTABLE VALUES VALUE (ohms) WATTAGE 1.5K - 1.9K | 25W (min) 2.0K - 3.0K 10W (min)



PREEMPT ONLY PHASE OMIT NOTE

(program controller as shown below)

From Main Menu press '2' (Phase Control). Then '1' (Phase Control Functions) Program Phase 5 for 'Omit Phase' and Phases 1, 2, 4, 6, and 8 for 'Startup Colls'. This is to prevent Phase 5 from being served when not in Preempt.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 04-0667 DESIGNED: January 2017 SEALED: 2/14/17 REVISED: N/A

Electrical Detail - Sheet 3 of 4

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared in the Offices of:

750 N.Greenfield Pkwy, Garner, NC 27529

NC 43 Bypass/ SR 1250 (Springfield Road)

US 64 Alternate

PLAN DATE: February 2017 REVIEWED BY: PREPARED BY: B. SIMMONS REVIEWED BY: KMMREVISIONS INIT. DATE

SIG. INVENTORY NO. 04-0667