

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

PROJ. REFERENCE NO.	SHEET NO.
U-2525C	X-1E

Quantities are approximate only. The Resident Engineer will re-cross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut
Y16	(cu. yd.)	(cu. yd.)	(cu. yd.)	LACFLY	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPA	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPC	(cu. yd.)	(cu. yd.)	(cu. yd.)
19+50.00	12	25	0	26+50.00	0	3726	0	21+00.00	3317	0	0	17+33.94	2247	0	0
20+00.00	34	14	0	27+00.00	0	3254	0	21+51.88	3773	0	0	17+80.00	2380	0	0
20+50.00	79	5	0	27+50.00	0	3188	0	22+26.68	5336	0	0	18+30.00	2869	0	0
20+62.00	21	0	0	28+00.00	0	1610	0	22+92.87	4073	0	0	18+70.00	2497	0	0
21+00.00	44	0	0					23+53.08	3184	0	0	19+10.00	2602	0	0
Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut
Y17	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4LPA	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPA	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPC	(cu. yd.)	(cu. yd.)	(cu. yd.)
				10+00.00	0	0	0	24+05.52	2290	0	0	19+50.00	2606	0	0
				11+39.00	0	0	0	24+60.97	1928	0	0	20+00.00	3219	0	0
				11+50.00	5	0	0	25+13.35	1476	0	0	20+60.00	3730	0	0
				12+00.00	40	8	0	25+64.04	1076	0	0	21+27.02	3733	0	0
				12+50.00	25	57	0	25+94.29	383	0	0	21+87.11	2814	0	0
				13+00.00	17	119	0					22+37.85	1859	0	0
				13+50.00	11	148	0					22+95.27	1726	0	0
				14+00.00	6	128	0					23+48.50	1380	0	0
				14+50.00	52	52	0					23+99.75	1081	0	0
				15+00.00	79	5	0					24+49.83	898	0	0
Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut
Y18	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4LPA	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4LPC	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y6LPA	(cu. yd.)	(cu. yd.)	(cu. yd.)
				14+50.00	10479	0	0	10+00.00	0	0	0	10+00.00	0	0	0
				15+00.00	7518	0	0	10+26.52	347	0	0	10+45.10	0	1902	0
				15+50.00	5667	0	0	10+76.45	661	0	124	10+95.22	0	1206	0
				16+00.00	4099	0	0	11+25.65	741	0	136	11+44.92	6	603	4
				16+50.00	3014	0	0	11+75.87	596	0	144	11+97.06	159	152	95
				17+00.00	2144	0	0	12+20.28	341	0	114	12+36.40	359	0	88
				17+50.00	1326	0	0	12+67.10	474	0	125	12+85.73	886	0	25
				18+00.00	795	0	0	13+09.29	681	0	129	13+25.64	1287	0	0
				18+30.25	300	0	0	13+50.00	1067	0	112	13+60.00	1721	0	0
Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut	Station	Uncl. Exc.	Embt	UnderCut
LACFLY	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPA	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y4RPC	(cu. yd.)	(cu. yd.)	(cu. yd.)	Y6RPA	(cu. yd.)	(cu. yd.)	(cu. yd.)
				15+50.00	1992	0	0	14+00.00	2179	0	71	14+00.00	2784	0	0
				16+00.00	1820	0	0	14+50.00	2239	0	61	14+50.00	4666	0	0
				16+50.00	1658	0	0	15+00.00	1922	0	85	15+00.00	5597	0	0
				17+00.00	1248	0	0	15+50.00	1992	0	206	15+50.00	5864	0	0
				17+50.00	899	0	0	16+00.00	1820	0	215	16+00.00	5860	0	0
				18+00.00	684	0	0	16+50.00	1658	0	291	16+50.00	5545	0	0
				18+30.25	300	0	0	17+00.00	1248	0	259	17+00.00	5009	0	0
								17+50.00	899	0	206	17+50.00	4718	0	0
								18+00.00	684	0	108	18+00.00	4292	0	0
								18+22.17	261	0	27	18+00.00	3620	0	0
												19+00.00	2965	0	0
												19+50.00	2965	0	0
												20+00.00	1618	0	0
												20+50.00	1618	0	0
												21+00.00	1618	0	0
												21+50.00	1618	0	0
												22+00.00	1618	0	0
												22+50.00	1618	0	0
												23+00.00	1618	0	0
												23+50.00	1618	0	0
												24+00.00	1618	0	0
												24+50.00	1618	0	0
												25+00.00	1618	0	0
												25+50.00	1618	0	0
												26+00.00	1618	0	0