


EMBEDDED PLATE ``B-1'' DETAILS FOR 63" MODIFIED BULB TEES

(2 REQ'D PER GIRDER)



(SEE NOTES)

\$					
\$DATE\$	DRAWN BY:	S.D. COOPER		DATE:	8-17
	CHECKED BY:	M.A. AVERETT	Ē	DATE:	8-17
Ψ	DESIGN ENGIN	EER OF RECORD: _	M.A. AVERETTE	DATE:	8-17

NOTES:

SPECIFICATIONS.

ANCHOR STUDS SHALL CONFORM TO AASHTO M169 GRADES 1010 THROUGH 1020 OR APPROVED EQUAL, AND SHALL MEET THE TYPE ``B'' REQUIREMENTS OF SUBSECTION 7.3 OF THE ANSI/AASHTO/AWS D1.5 BRIDGE WELDING CODE.

AT ENDS OF GIRDERS TO BE EMBEDDED IN CONCRETE DIAPHRAGMS OR END WALLS, PRESTRESSING STRANDS MAY EXTEND A MAXIMUM OF 2"BEYOND THE GIRDER ENDS. OTHERWISE, PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE GIRDER ENDS. THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE GIRDER SHALL BE DONE WHEN CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN 6,000 PSI. DEPENDING ON THE TYPE OF SYSTEM USED TO SUPPORT THE DECK SLAB FORMS, PRESET ANCHORS MAY BE NECESSARY IN THE PRESTRESSED CONCRETE GIRDER. THE TOP SURFACE OF THE GIRDER, EXCLUDING THE OUTSIDE 4", SHALL BE RAKED TO A DEPTH OF $\frac{1}{4}$ ". A 2" × 2" CHAMFER IS ALLOWED AT THE INTERSECTION OF THE WEB AND THE BOTTOM FLANGE.

THE CONTRACTOR HAS THE OPTION TO PROVIDE, AT NO ADDITIONAL COST TO THE DEPARTMENT, 2 ADDITIONAL STRANDS AT THE TOP OF THE GIRDER TO FACILITATE TYING OF THE REINFORCING STEEL. THESE STRANDS SHALL BE PULLED TO A LOAD 0F 4500 lbs.



ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW-RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL SHALL BE GRADE 60.

APPLY EPOXY PROTECTIVE COATING TO END OF GIRDER SURFACES INDICATED IN ELEVATION VIEW. EMBEDDED PLATE ``B-1'' SHALL BE GALVANIZED IN ACCORDANCE WITH THE STANDARD

	PROJECT NO. <u>U-2525C</u> <u>GUILFORD</u> county STATION: <u>470+43.12</u> -L-				
SHEET 2 OF 2					
D BY: ERS CLATES rive	DEPARTMENT OF TRANSPORTATION RALEIGH SUPERSTRUCTURE PRESSTRESSED CONCRETE GIRDER DETAILS				
(Fax) ngr.com 9/13/2017	RIGHT LANE REVISIONS SHEET NO.				
C-2521 9/13/2017	NO. BY: DATE: NO. BY: DATE: \$9-13				
ENT NOT CONSIDERED FINAL ALL SIGNATURES COMPLETED	1 3 TOTAL SHEETS 2 4 32				