

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

Kimley»Horn

P.O. BOX 33068
RALEIGH, N.C. 27636-3068

RIGHT-OF-WAY REV.

CONST. REV.

<small>PROJECT REFERENCE NO.</small>	<small>SHEET NO.</small>
--------------------------------------	--------------------------

<i>U-5828</i>	<i>EC-40</i>
---------------	--------------

<small>R/W SHEET NO.</small>	
------------------------------	--

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

K:\RAL_Roadway\012108004 - McCrinmon Parkway\Phase 1\Plan\Plan Sheets\Phase2_012108004_psh_EC_Details.dgn

8/28/2017