PROJECT NO.	TOTAL NO.
I-5937 45880.3.1	7

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000 WORK ZONE SIGNS (STATIONARY) SF	46000 LANE CLOSURE EA	4600000 RAMP/ LOOP CLOSURE EA	4510000 LAW ENFORCEMENT HR	44230000 WORK ZONE DIGITAL SPEED LIMIT SIGNS EA	4688000000-E 6" X 90 M WHITE THERMO LF	6" X 90 M YELLOW THERMO LF	4690000 6" X 120 M WHITE THERMO LF	4700000 12" X 90 M WHITE THERMO LF	471000 24" X 120 M WHITE THERMO LF	4725000000-E THERMO WRONG WAY RAMP ARROW 90 M EA	THERMO MRG ARROW 90 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	48050000 COLD APPLIED PLASTIC MRG ARROW EA	4815000000-E 6" WHITE PAINT LF	6" YELLOW PAINT LF	48250 12" WHITE PAINT LF	4845000000-N PAINT WRONG WAY ARROW EA	PAINT MRG ARROW EA	PAINT LT ARROW EA	PAINT RT ARROW EA	4847030000-E 6" X 20 M WHITE POLYUREA LF	6" X 20 M YELLOW POLYUREA LF	4855000 REMOVAL OF PM LINES (6") LF	487500000 REMOVAL OF PM SYMBOLS & CHARACTERS EA	4905000000-N SNOW PLOWABLE MARKERS EA
I-5937	Wilson	1	I-795 SBL	WAYNE/ WILSON COUNTY LINE TO US-264	1	2	MD	7.52	28	200	128	4	200	4	39,750	39,750	9,950	2,600			7			1	49,700	39,750	2,600		7			980	700	1,680	1	600
		2	I-795 NBL	WAYNE/ WILSON COUNTY LINE TO US-264	1	2	MD	7.7	28	200	128	4	200	4	40,660	40,660	10,170	2,600			6				50,830	40,660	2,600		6			1,370	1,020	2,390		600
		3	SBL ENTRY RAMP	SR-1643 TO I-795	3	1		0.16	24						864	864									864	864										
		4	SBL EXIT RAMP	I-795 TO SR-1643	3	1		0.3	24						1,573	1,573			55	1					1,573	1,573		1								14
		5	NBL ENTRY RAMP	SR-1643 TO I-795	3	1		0.16	24						873	873									873	873										
		6	NBL EXIT RAMP	I-795 TO SR-1643	3	1		0.32	24						1,680	1,680			55	1					1,680	1,680		1								14
		7	SBL ENTRY LOOP	US-301 TO I-795	4	1		0.2	22						1,186	1,003									1,186	1,003										
		8	SBL EXIT RAMP	I-795 TO US-301	3	1		0.36	24						1,850	1,850	250		40	1		2	2		1,850	1,850		1		2	2					30
		9	NBL ENTRY LOOP	US-301 TO I-795	4	1		0.2	22						1,282	1,061			40						1,282	1,061										
		10	NBL EXIT RAMP	I-795 TO US-301	3	1		0.36	24						2,034	2,034	600		50	1		3	6		2,034	2,034		1		3	6	180	180	360		70
GRAND TOTAL FOR PROJ NO. 45880.3.1								**17.28**		**400**	**256**	**8**	**400**	**8**	**91,753**	**91,349**	**20,970**	**5,200**	**240**	**4**	**13**	**5**	**8**	**1**	**111,873**	**91,349**	**5,200**	**4**	**13**	**5**	**8**	**2,530**	**1,900**	**4,430**	**1**	**1,328**
															183,102					**30**					**203,222**			**30**				**4,430**				