



GENERAL NOTE:
 CONTRACTOR TO MAINTAIN A MINIMUM OF SIX (6) FEET FROM EDGE OF PAVEMENT WHEN TRENCHING PARALLEL TO THE ROADWAY.

- | | | | | |
|--|--|---|---|--|
| <ul style="list-style-type: none"> 1 INSTALL REA, PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE 2 INSTALL REA, PE - 38, (FIGURE - 8) SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE 3 INSTALL 3-CONDUCTOR, CLASS B, STRANDED UNDERGROUND POWER CABLE 4 INSTALL SMFO CABLE 5 INSTALL CAT 5e COMMUNICATIONS CABLE 6 INSTALL FIBER OPTIC DROP CABLE 7 INSTALL TRACER WIRE 8 TRENCH 9 INSTALL PVC CONDUIT 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL 13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT 14 INSTALL POLYETHYLENE CONDUIT 15 DIRECTIONAL DRILL CONDUIT | <ul style="list-style-type: none"> 16 INSTALL BRIDGE MOUNTED FIBERGLASS CONDUIT, WITH FOUR-WAY INNERDUCT INSERT 17 INSTALL CABLE(S) IN EXISTING CONDUIT 18 INSTALL CABLE(S) IN NEW CONDUIT 19 INSTALL CABLE(S) IN EXISTING RISER 20 INSTALL CABLE(S) IN NEW RISER 21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS 22 INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE) 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE) 24 INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET 25 INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET 26 TERMINATE COMMUNICATIONS CABLE ON EXISTING TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET 27 INSTALL NEW TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPlice CABLE IN CABINET 29 INSTALL UNDERGROUND SPlice ENCLOSURE 30 INSTALL AERIAL SPlice ENCLOSURE | <ul style="list-style-type: none"> 31 INSTALL POLE MOUNTED SPlice CABINET 32 INSTALL BASE MOUNTED SPlice CABINET (336) WITH EXTEND BASE 33 REMOVE EXISTING SPlice CABINET 34 INSTALL CABINET FOUNDATION 35 REMOVE EXISTING CABINET FOUNDATION 36 INSTALL CCTV CAMERA ASSEMBLY 37 INSTALL CCTV CAMERA WOOD POLE 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION 39 INSTALL SPECIAL OVERSIZED JUNCTION BOX WITH 100 FEET OF COMMUNICATIONS CABLE 40 INSTALL OVERSIZED JUNCTION BOX 41 INSTALL BRIDGE MOUNTED JUNCTION BOX 42 INSTALL WOOD POLE 43 REMOVE EXISTING WOOD POLE 44 INSTALL AERIAL GUY ASSEMBLY 45 INSTALL STANDARD GUY ASSEMBLY 46 INSTALL SIDEWALK GUY ASSEMBLY | <ul style="list-style-type: none"> 47 INSTALL MESSENGER CABLE 48 REMOVE EXISTING COMMUNICATIONS CABLE AND MESSENGER CABLE 49 REMOVE EXISTING COMMUNICATIONS CABLE 50 INSTALL REEL END SPlice 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE 52 INSTALL DELINEATOR MARKER 53 STORE 50 FEET OF COMMUNICATIONS CABLE 54 LASH CABLE(S) TO EXISTING SIGNAL / COMMUNICATIONS CABLE 55 LASH CABLE(S) TO EXISTING MESSENGER CABLE 56 LASH CABLE(S) TO NEW MESSENGER CABLE 57 MODIFY EXISTING ELECTRICAL SERVICE 58 INSTALL NEW ELECTRICAL SERVICE FOR DMS 59 INSTALL NEW BASE MOUNTED CABINET (336) 60 SEAL ALL CONDUIT ENTERING JUNCTION BOXES AND CABINETS WITH MOLDABLE DUCT SEAL 61 INSTALL ETHERNET SWITCH | <ul style="list-style-type: none"> 62 LOCATE EXISTING JUNCTION BOX AND CONNECT WITH NEW CONDUIT 63 BOND MESSENGER CABLE AND RISER TO POLE GROUND |
|--|--|---|---|--|

	I-40 ITS FIBER CABLE ROUTE CABLE ROUTING PLANS		SEAL SEAL 031636 ENGINEER PAUL P. MARAK								
	DIV 3 NEW HANOVER CO. Near WILMINGTON PLAN DATE: January 2018 REVIEWED BY: G. Green PREPARED BY: L. Neal REVIEWED BY: P. Marak										
SCALE NTS	REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DESCRIPTION</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		NO.	DESCRIPTION	INIT.	DATE					SIGNATURE DATE 2/1/2018
NO.	DESCRIPTION	INIT.	DATE								