



COLOR CODE
TIA/EIA 598-A

- | | |
|------------|-------------|
| (1) BLUE | (7) RED |
| (2) ORANGE | (8) BLACK |
| (3) GREEN | (9) YELLOW |
| (4) BROWN | (10) VIOLET |
| (5) SLATE | (11) ROSE |
| (6) WHITE | (12) AQUA |

LEGEND

- X = FUSION SPLICE
- C = CAP IN TRAY
- EXPRESS = EXPRESS ENTIRE BUFFER TUBE THROUGH WITHOUT CUTTING

NOTES

- UNUSED FIBER SHALL BE LEFT COILED AND STORED IN THE SPLICE TRAY.
- UNUSED BUFFER TUBES SHALL BE LEFT COILED AND STORED IN THE SPLICE TRAY.
- ETHERNET TERMINATION CONFIGURATIONS ARE GENERIC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING AND ENSURING PROPER TERMINATION.

SPLICE ENCLOSURE AT I-140 and US 74

	FIBER OPTIC SPLICE DETAILS CCTV-2, DMS-1 & DMS-2		SEAL 031636
	DIVISION 03 BRUNSWICK/NEW HANOVER Near Wilmington PLAN DATE: JANUARY 2018 REVIEWED BY: G. GREEN PREPARED BY: L. NEAL REVIEWED BY: P. MARAK		
SCALE NTS	REVISIONS	INIT. DATE	CADD Filename: