



COLOR CODE
TIA/EIA 598-A

- | | |
|------------|-------------|
| (1) BLUE | (7) RED |
| (2) ORANGE | (8) BLACK |
| (3) GREEN | (9) YELLOW |
| (4) BROWN | (10) VIOLET |
| (5) SLATE | (11) ROSE |
| (6) WHITE | (12) AQUA |

LEGEND

- X = FUSION SPLICE
 C = CAP IN TRAY
 EXPRESS = EXPRESS ENTIRE BUFFER TUBE THROUGH WITHOUT CUTTING

NOTES

1. UNUSED FIBER SHALL BE LEFT COILED AND STORED IN THE SPLICE TRAY.
2. UNUSED BUFFER TUBES SHALL BE LEFT COILED AND STORED IN THE SPLICE TRAY.
3. ETHERNET TERMINATION CONFIGURATIONS ARE GENERIC. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING AND ENSURING PROPER TERMINATION.



FIBER OPTIC SPLICE DETAILS
CCTV-3

DIVISION 03 BRUNSWICK/NEW HANOVER Near Wilmington
 PLAN DATE: JANUARY 2018 REVIEWED BY: G. GREEN
 PREPARED BY: L. NEAL REVIEWED BY: P. MARAK

SCALE	REVISIONS	INIT.	DATE
NTS			

DocuSigned by:
 Paul P. Marak 2/1/2018
 SEAL
 031636
 ENGINEER
 PAUL P. MARAK
 CADD Filename: