

Pyramid Environmental & Engineering, P.C. Project # 2013-278
Preliminary Site Assessment (PSA) – Parcel 27, Charles Sutton

PRELIMINARY SITE ASSESSMENT
PARCEL 27, CHARLES SUTTON
1975 U.S. HIGHWAY 1 NORTH
ROCKINGHAM, RICHMOND COUNTY, NORTH CAROLINA
STATE PROJECT: R-2501C
WBS ELEMENT: 34437.1.1
JANUARY 21, 2014

Report prepared for:

Mr. Gordon Box, LG
GeoEnvironmental Project Manager
GeoEnvironmental Section
Geotechnical Engineering Unit
North Carolina Department of Transportation
1020 Birch Ridge Drive
Raleigh, NC 27610

Report prepared by:

Eric C. Cross, LG
NC License #2181



PYRAMID ENVIRONMENTAL & ENGINEERING, P.C.
P.O. BOX 16265
GREENSBORO, NC 27416-0265
(336) 335-3174

C-257 –Geology
C-1251 - Engineering

Report reviewed by:

Michael G. Jones, LG
NC License #1168



TABLE OF CONTENTS

Executive Summary of Results	1
1.0 Introduction.....	3
1.1 BACKGROUND INFORMATION	3
1.2 PROJECT INFORMATION	3
2.0 Site History	4
3.0 Geophysical Investigation	5
4.0 Soil Sampling Activities & Results	5
4.1 SOIL ASSESSMENT FIELD ACTIVITIES	5
4.2 SOIL SAMPLE ANALYTICAL RESULTS	6
4.3 TEMPORARY MONITORING WELL INSTALLATION	6
4.4 GROUNDWATER ANALYTICAL RESULTS	6
5.0 Conclusions and Recommendations.....	7
5.1 GEOPHYSICAL INVESTIGATION	7
5.2 LIMITED SOIL ASSESSMENT.....	7
5.3 LIMITED GROUNDWATER ASSESSMENT	7
5.4 RECOMMENDATIONS.....	7
6.0 Limitations.....	8
7.0 Closure	8

TABLE OF CONTENTS (Continued)

FIGURES

- Figure 1 : Topographic Map
- Figure 2 : Soil Boring Locations and QED Analysis Results

TABLES

- Table 1 : Summary of Soil Field Screening Results
- Table 2 : Summary of Soil Sample Analytical Results

APPENDICES

- Appendix A : Historical Aerial Photographs
- Appendix B : Geophysical Investigation Report
- Appendix C : Soil Boring Logs
- Appendix D : QROS QED HC-1 Hydrocarbon Analyzer
- Appendix E : Laboratory Report & Chain-of-Custody Form
- Appendix F : Personnel Logs

**PRELIMINARY SITE ASSESSMENT
PARCEL 27, CHARLES SUTTON
1975 N. US 1
ROCKINGHAM, RICHMOND COUNTY, NORTH CAROLINA**

EXECUTIVE SUMMARY OF RESULTS

Pyramid Environmental & Engineering P.C. (Pyramid) has prepared this Preliminary Site Assessment (PSA) report documenting background information, field activities, assessment activities, findings, conclusions, and recommendations for Parcel 27, the Charles Sutton property. The purpose of this assessment was to determine the presence or absence of underground storage tanks (USTs) and impacted soils at the subject property within the proposed right-of-way (ROW) and/or easement and edge of pavement (State Project R-2501C). The PSA was conducted with particular attention to the areas to be cut as indicated by slope stake lines and cross sections or to be excavated for the installation of drainage features. This preliminary site assessment was conducted on behalf of the North Carolina Department of Transportation (NCDOT) in accordance with Pyramid's October 16, 2013, technical proposal.

The following statements summarize the results of the PSA:

- **Site History:** A review of the North Carolina Department of Environment and Natural Resources (DENR) registered UST database and incident database indicated no environmental incidents were on file for the Charles Sutton property (Parcel 27). On November 26, 2013, Pyramid emailed the Richmond County R-2501C parcel addresses to Mr. Kenneth Currie, the Richmond County Incident Manager for the DENR UST Section, with a request to investigate any environmental incidents associated with the parcels. On December 2, 2013, Mr. Currie responded to the email and stated that site address 1975 N. US 1 (Parcel 27) does not have any environmental incidents in the DENR database.

On November 26, 2013, Pyramid Project Manager Eric Cross conducted an on-site interview with the property owner, Charles Sutton. Mr. Sutton indicated that he had owned the property since 2003, and utilized it as an auto repair facility. Mr. Sutton was not aware of any USTs at the property, with the exception of a septic tank on the north side of the building, outside of the area of investigation. He was not aware of any incidents associated with the property.

- **Geophysical Survey:** The geophysical investigation provided no evidence of metallic USTs within the existing and proposed ROW and/or easement.

- **Limited Soil Assessment:** A total of three borings were performed across the property and at least one soil sample from each boring was analyzed with the QED UVF HC-1 Analyzer system from QROS-US for total petroleum hydrocarbon (TPH) petroleum contamination. If field screening detected an elevated reading, then additional soil samples from each boring were selectively analyzed with the QED UVF HC-1 Analyzer. The QED did not detect TPH gasoline range organic (GRO) or TPH diesel range organic (DRO) concentrations above 10 milligrams per kilogram (mg/kg) in any of the soil samples analyzed. The DENR action levels for both TPH-GRO and TPH-DRO are 10 mg/kg. A duplicate of soil sample 27-2(5-7.5) was shipped to Pace Analytical for laboratory analysis. The laboratory results for soil sample 27-2(5-7.5) did not detect GRO or DRO concentrations above detection limits. No odors were detected during the field screening.
- **Limited Groundwater Assessment:** Based on field observations and the groundwater level observed at other parcels included in this PSA, Pyramid concluded that it was unlikely that groundwater would be encountered during the NCDOT excavation and construction activities at this parcel. Therefore, it was deemed unnecessary to install a temporary well and collect a groundwater sample.
- **Contaminated Soil Volumes:** No petroleum-impacted soils above 10 mg/kg were encountered during the PSA investigation at Parcel 27, nor was any evidence of probable or possible USTs recorded within the proposed right of way or easement. Therefore, no recommendations are necessary for the treatment or disposal of such materials. It should be noted that, if impacted soil is encountered during road construction outside of the area analyzed by this investigation, the impacted soil should be managed according to NC DENR Division of Waste Management (DWM) UST Section Guidelines and disposed of at a permitted facility.

1.0 Introduction

Pyramid Environmental & Engineering P.C. (Pyramid) has prepared this Preliminary Site Assessment (PSA) report documenting background information, field activities, assessment activities, findings, conclusions, and recommendations for Parcel 27, the Charles Sutton property. The Charles Sutton property is currently an automobile repair shop (Chuck's Trucks) and an ATV sales building located at 1975 N. US 1 in Rockingham, NC. This preliminary site assessment was conducted on behalf of the North Carolina Department of Transportation (NCDOT) in accordance with Pyramid's October 16, 2013, technical proposal.

The purpose of this assessment was to determine the presence or absence of underground storage tanks (USTs) and the potential for impacted soils at the subject properties within the proposed ROW and/or easement and edge of pavement (State Project R-2501C). The location of the subject site is shown on **Figure 1**.

1.1 Background Information

Based on the NCDOT's October 10, 2013, *Request for Technical and Cost Proposal*, the PSA was conducted in the proposed easement/proposed right of way (ROW) and the area between the existing NCDOT right of way and the edge of pavement, with emphasis on the areas to be cut as indicated by slope stake lines and cross sections or to be excavated for the installation of drainage features and/or other utilities, in accordance with the CADD files provided to Pyramid by the NCDOT. The PSA included the following:

- Research the properties for past uses and possible releases.
- Conduct a preliminary geophysical site assessment and limited soil assessment in the proposed easement and the area between the existing ROW and the edge of pavement with emphasis on the areas to be cut as indicated by slope stake lines and cross sections or to be excavated for the installation of drainage features and/or other utilities.
- Should groundwater be encountered at a depth that might impact the NCDOT construction activities, report the depth to groundwater for that site and attempt to obtain one groundwater sample for laboratory analysis by installing a temporary monitoring well.

1.2 Project Information

Prior to field activities, a Health and Safety Plan was prepared. Prior to drilling activities, the public underground utilities were located and marked by the North Carolina One-Call Service. A private utility locator, Northstate Utility Locating Incorporated of Colfax, North Carolina was used to mark the on-site private, buried utilities.

2.0 Site History

The NCDOT description of the parcel in the RFP provided to Pyramid on October 10, 2013, provided the following background information related to the site:

Two automotive repair businesses are located on this parcel on the north side of US 1. Chuck's Trucks, a 4X4 repair business, is located approximately 100 feet north of the existing US 1 centerline; the EHS Racing shop is located approximately 150 feet north of the existing US 1 centerline. A Facility ID has not been discovered for this site. Evidence of soil staining and/or USTs or UST removal was not observed during field reconnaissance along the project corridor on November 14, 2007. However, there may be environmental concerns with this site such as USTs, hydraulic lifts, or chemical concerns.

Pyramid completed a records review of the parcel, interviewed DENR personnel, interviewed property owners, and reviewed aerial photographs to assess past uses of the property. Pyramid reviewed historical aerial photographs dating back to 1938 available from the Richmond County Soil and Water Conservation office in Rockingham and on Google Earth. The 1938, 1956, 1975, 1993, 1999, 2005, 2008, 2011, and 2013 aerial photographs are included in **Appendix A**. Historical information reviewed as part of the PSA indicated that the Charles Sutton property was partially developed for commercial use between 1975 and 1993 (west building), and the east building was constructed between 1993 and 1999. The earliest aerial to show the west building was the 1993 aerial, and the earliest building to show the east building was the 1999 aerial. The 1938, 1956, and 1975 aerials show the property to be undeveloped agricultural land.

On November 26, 2013, Pyramid emailed the Richmond County R-2501C parcel addresses to Mr. Kenneth Currie, the Richmond County Incident Manager for the DENR UST Section, with a request to investigate any environmental incidents associated with the parcels. On December 2, 2013, Mr. Currie responded to the email and stated that site address 1975 N. US 1 (Parcel 27) does not have any environmental incidents in the DENR database.

On November 26, 2013, Pyramid Project Manager Eric Cross conducted an on-site interview with the property owner, Charles Sutton. Mr. Sutton indicated that he had owned the property since 2003, and utilized it as an auto repair facility. He also indicated that the previous owner utilized the property as an auto repair center for approximately 20 years. Aerial photographs indicate that the buildings were likely not constructed prior to that previous owner's use. Mr. Sutton was not aware of any USTs at the property, with the exception of a septic tank on the north side of the building, outside of the area of investigation. Mr. Sutton indicated that a private water well was present near the southwest corner of the property, which was observed during our site inspection. He was not aware of any environmental concerns associated with the property.

3.0 Geophysical Investigation

Pyramid performed an electromagnetic (EM) survey across the accessible portions of the Parcel. All of the EM61 anomalies detected could be attributed to visible objects at the ground surface such as signs and other cultural features. For this reason, a GPR survey was not required. No evidence was observed to indicate the presence of metallic USTs within the survey area.

The geophysical investigation did not record evidence of metallic USTs within the proposed ROW and/or easement.

The full details of the geophysical investigation are included in the Geophysical Investigation Report as **Appendix B**.

4.0 Soil Sampling Activities & Results

4.1 Soil Assessment Field Activities

On December 16, 2013, Pyramid mobilized to the site, drilled soil borings, and collected the proposed soil samples for the PSA. The soil borings were completed using a track mounted Geoprobe® Direct-Push rig. Three (3) soil borings (27-1, 27-2, and 27-3) were advanced on the subject property between the NCDOT proposed ROW and easements, and edge of pavement. The selected locations were chosen to avoid public utilities along U.S. 1 and private utilities associated with the business while remaining in the proposed right of way. The soil borings were installed parallel to U.S. 1 in an area proposed to be cut as indicated by the slope stake line. Boring 27-1 was installed at the location of a proposed drainage feature (NCDOT label 0804). The locations of the borings are shown on **Figure 2**.

Soil samples were continuously collected in four foot long disposable sleeves from each boring for geologic description, and visual examination for signs of contamination. Soil recovered from each sleeve was screened in the field using a Photo-Ionization Detector (PID) approximately every 2 feet depending on the soil recovery of each sleeve. In general, the soil sample with the highest PID reading was selected from each boring for laboratory analysis. If field screening detected elevated reading, then additional soil samples from each boring were selectively analyzed with the QED UVF HC-1 Analyzer. The soil boring logs with the soil descriptions, visual examination, and PID screening results are included in **Appendix C**. The PID field screening results are summarized in **Table 1**. To prevent cross contamination, new disposable nitrile gloves were worn by the sampling technician during the sampling activities, and were changed between samples. No odors were detected during the field screening.

The soil samples selected for Total Petroleum Hydrocarbon (TPH) analyses were analyzed utilizing the QED UVF HC-1 Analyzer system from QROS-US. The NCDOT has indicated that this instrument is an acceptable method to provide total petroleum hydrocarbon (TPH) results for soil analysis for the PSA projects. Pyramid's QED-certified technician performed the soil analyses. The soil samples selected for analysis using the QED Analyzer were analyzed for TPH as diesel range organics (DRO) and TPH as gasoline range organics (GRO). The soil samples selected for analysis using the QED were preserved in the field with methanol and were analyzed at the end of each day using the QED. One duplicate soil sample was selected for laboratory analysis from Parcel 27.

The duplicate soil sample selected for laboratory analyses 27-2(5-7.5) was placed in laboratory prepared containers and shipped to Pace Analytical in Huntersville, NC for analysis. The selected soil sample was analyzed for TPH as GRO by EPA Method 8015C and DRO by EPA Method 8015C/3541.

4.2 Soil Sample Analytical Results

The QED results for soil samples 27-1(1-2.5), 27-1(5-7.5), 27-2(1-2.5), 27-2(5-7.5) and 27-3(7.5-10) did not detect TPH-GRO or TPH-DRO concentrations above 10 mg/kg. The DENR action levels for both TPH-GRO and TPH-DRO are 10 mg/kg. The soil sample QED results are summarized in **Table 2**. A copy of the QED analysis report is included in **Appendix D**.

A duplicate of soil sample 27-2(5-7.5) was shipped to Pace Analytical for laboratory analysis. The laboratory results for soil sample 27-2(5-7.5) did not detect GRO or DRO concentrations above detection limits. A copy of the Pace Analytical laboratory report and chain-of-custody is included in **Appendix E**. To maintain consistency, the QED results are utilized in this report to determine the presence and level of potential contamination.

4.3 Temporary Monitoring Well Installation

Based on field observations and the groundwater level observed at other parcels included in this PSA, Pyramid concluded that it was unlikely that groundwater would be encountered during the NCDOT excavation and construction activities at this parcel. Therefore, it was deemed unnecessary to install a temporary well and collect a groundwater sample.

4.4 Groundwater Analytical Results

As discussed above, no groundwater sample was collected at the property, therefore, no analytical results are reported for this parcel.

5.0 Conclusions and Recommendations

As requested by NCDOT, Pyramid has completed a PSA at the Charles Sutton property located 1975 N. US 1, Rockingham, NC (Parcel 27). The following is a summary of the assessment activities and results.

5.1 Geophysical Investigation

The geophysical investigation provided no evidence of metallic USTs within the existing and proposed ROW and/or easement.

5.2 Limited Soil Assessment

The QED did not detect TPH gasoline range organic (GRO) or TPH diesel range organic (DRO) concentrations above 10 mg/kg in any of the soil samples analyzed. The DENR action levels for both TPH-GRO and TPH-DRO are 10 mg/kg. A duplicate of soil sample 27-2(5-7.5) was shipped to Pace Analytical for laboratory analysis. The laboratory results for soil sample 27-2(5-7.5) did not detect GRO or DRO concentrations above detection limits. To maintain consistency, the QED results are utilized in this report to determine the presence and level of potential contamination.

5.3 Limited Groundwater Assessment

Based on field observations and the groundwater level observed at other parcels included in this PSA, Pyramid concluded that it was unlikely that groundwater would be encountered during the NCDOT excavation and construction activities at this parcel. Therefore, it was deemed unnecessary to install a temporary well and collect a groundwater sample.

5.4 Recommendations

No petroleum-impacted soils above 10 mg/kg were encountered during the PSA investigation at Parcel 27, no odors were detected during the field screening, and there was no evidence of probable or possible USTs recorded within the proposed right of way or easement. Therefore, no recommendations are necessary for the treatment or disposal of such materials.

It should be noted that, if impacted soil is encountered during road construction outside of the area analyzed by this investigation, the impacted soil should be managed according to NC DENR Division of Waste Management (DWM) UST Section Guidelines and disposed of at a permitted facility.

6.0 Limitations

The results of this preliminary investigation are limited to the boring locations completed during this limited assessment and presented in this report. The laboratory results only reflect the current conditions at the locations sampled on the date this PSA was performed.

7.0 Closure


This report was prepared for, and is available solely for use by NCDOT and their designees. The contents thereof may not be used or relied upon by any other person without the express written consent and authorization of Pyramid Environmental & Engineering, P.C. (Pyramid). The observations, conclusions, and recommendations documented in this report are based on site conditions and information reviewed at the time of Pyramid's investigation. Pyramid appreciates the opportunity to provide this environmental service.

FIGURES

USGS TOPOGRAPHIC MAP

SITE: 1975 U.S. HIGHWAY 1 NORTH

LOCATION: ROCKINGHAM, NORTH CAROLINA



USGS IDENTIFICATION

SCALES

USGS 7.5 MINUTE MAP


HAMLET, N.C.

ORIGINAL DATE:

2002

PHOTOREVISION DATE:

NA




	PRIMARY HIGHWAY, HARD SURFACE
	SECONDARY HIGHWAY, HARD SURFACE
	LIGHT-DUTY ROAD HARD OR IMPROVED SURFACE
	UNIMPROVED ROAD
	STATE ROAD
	U.S. ROUTE
	INTERSTATE ROUTE

NOTES: TOPOGRAPHICAL CONTOUR INTERVAL = 10 FEET
 PHOTOREVISIONS DENOTED IN PURPLE

MAGNETIC NORTH

COUNTY MAP OF:
NORTH CAROLINA



COUNTY: **RICHMOND**
 APPROXIMATE SITE LOCATION




CLIENT: NC DOT R-2501C
 PROPERTY NAME: PARCEL 027, CHARLES SUTTON
 CITY: ROCKINGHAM STATE: NORTH CAROLINA
 TITLE: TOPOGRAPHIC MAP


SCALE: 1"=2000'
 DATE: 1/7/14
 DRAWING NAME: USGSTOPO

DRAWN BY: KAM
 CHECK BY: TDL
 JOB NO.: 2013-278
 TYPE: PSA
 FIGURE NUMBER: 1

NOTES
 TOPOGRAPHIC MAP USED IN THIS GRAPHIC IS MAPPED, EDITED, AND PUBLISHED BY THE UNITED STATES GEOLOGIC SURVEY, DEPARTMENT OF THE INTERIOR, RESTON VIRGINIA.
 THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS.



- ### LEGEND
- PUE PROPOSED UTILITY EASEMENT
 - EXISTING ROW
 - EXISTING PROPERTY BOUNDARY
 - PROPOSED ROW
 - PROPOSED CONST. EASEMENT
 - DUE PROP. DRAINAGE UTIL. EASEMENT
 - PROPOSED SS CUT LINE
 - PROPOSED SS FILL LINE
 - PROPOSED SS TRANSITION LINE
 - PROPOSED DRAINAGE PIPING
 - PDE PROPOSED DRAINAGE EASEMENT
- SOIL SAMPLE BORING LOCATION
 - BORING CONVERTED TO MW
- (<6.1) TPH-DRO concentration (mg/kg)
 [<6.1] TPH-GRO concentration (mg/kg)
 * Analytical data collected by the method of QROS, QED Analyzer



TITLE SOIL BORING LOCATIONS AND QED ANALYSIS RESULTS	
PROJECT NCDOT ROW PROJECT R-2501C (34437.1.1) CHARLES SUTTON PROPERTY - PARCEL 027 U.S. 1, RICHMOND COUNTY, NORTH CAROLINA	
503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 12-19-13	REVISION NO. 0
PYRAMID PROJECT NO. 2012-278	FIGURE NO. 2

TABLES

TABLE 1
Summary of Soil Field Screening Results
NCDOT Project R-2501C
1975 US Highway 1 North - Parcel 27
Rockingham, Richmond County, North Carolina

SOIL BORING	SAMPLE ID	DEPTH (feet bgs)	PID READINGS (PPM)
27-1	27-1(1-2.5)	1 to 2.5	4.2
	27-1(2.5-5)	2.5 to 5	3.1
	27-1(5-7)	5 to 7	8.2
	27-1(7.5-10)	7.5 to 10	2.4
27-2	27-2(1-2.5)	1 to 2.5	5.1
	27-2(2.5-5)	2.5 to 5	1.4
	27-2(5-7.5)	5 to 7.5	7.4
	27-2(7.5-10)	7.5 to 10	6.0
27-3	27-3(1-2.5)	1 to 2.5	2.6
	27-3(2.5-5)	2.5 to 5	5.0
	27-3(5-7.5)	5 to 7.5	5.6
	27-3(7.5-10)	7.5 to 10	7.6

bgs= below ground surface

PID= photo-ionization detector

PPM= parts-per-million

☐ = sampled for lab analysis &/or QROS-QED analysis

OVA= Organic Vapor Analyzer

TABLE 2
Summary of Soil Sample Analytical Results
 NCDOT State Project R-2501C
 1975 US Highway 1 North - Parcel 027
 Rockingham, Richmond County, North Carolina

SAMPLE ID	DATE	DEPTH (feet)	PID (ppm)	QROS - QED Analysis			Laboratory Analysis (Pace)	
				GRO (mg/kg) (C5-C10)	DRO (mg/kg) (C10-C35)	TPH (mg/kg) (C5-C35)	EPA Method 3550 DRO (mg/kg)	EPA Method 5035 GRO (mg/kg)
27-1(1-2.5)	12/16/2013	1 to 2.5	4.2	<0.4	0.9	0.9	-----	-----
27-1(5-7.5)	12/16/2013	5 to 7.5	8.2	<0.5	<0.5	<0.5	-----	-----
27-2(1-2.5)	12/16/2013	1 to 2.5	5.1	<0.4	<0.4	<0.4	-----	-----
27-2(5-7.5)	12/16/2013	5 to 7.5	7.4	<0.5	<0.5	<0.5	<5.9	<4.6
27-3(7.5-10)	12/16/2013	7.5 to 10	7.6	<0.5	<0.5	<0.5	-----	-----
NC Initial Action Level - UST Section for 5035/5030-GRO; 3550-DRO				10	10	NA	10	10

PID= photo-ionization detector
 PPM= parts-per-million

GRO= Gasoline Range Organics
 DRO= Diesel Range Organics
 mg/kg= milligrams-per-kilogram

TPH= Total Petroleum
 Hydrocarbons (GRO + DRO)

NA= Not Applicable
 "-----" = No Laboratory Analysis

* Bold values indicate concentrations above initial action levels

APPENDIX A



Parcel 27

1

126 ft

© 2013 Google


Google earth

2013

Google earth

feet
meters





Parcel 27

126 ft

Image © 2013 DigitalGlobe

Google earth
2011

Google earth

feet 300
meters 90





Parcel 27

1


126 ft

Google earth
2008

Google earth

feet
meters





Parcel 27

126 ft

Google earth

2005

Google earth

feet 300
meters 90





Parcel 27

126 ft

Image U.S. Geological Survey

Google earth

1999

Google earth

feet 300
meters 90





Parcel 27

126 ft

Image U.S. Geological Survey

Google earth

1993

Google earth

feet 300
meters 90



Parcel 27



1975



Parcel 27

LS-1

730

575

1956

Parcel 27



9

2

1938

APPENDIX B



PYRAMID ENVIRONMENTAL & ENGINEERING
(PROJECT 2013-278)

GEOPHYSICAL SURVEY

PARCEL 027 – CHARLES SUTTON
1975 N. US 1
NCDOT PROJECT R-2501C (34437.1.1)

ROCKINGHAM, RICHMOND COUNTY, NC

JANUARY 13, 2013

Report prepared for: Mr. Gordon Box
GeoEnvironmental Project Manager
Geotechnical Engineering Unit
1020 Birch Ridge Drive
Raleigh, NC 27610

Prepared by: _____

Eric C. Cross, P.G.
NC License #2181

Reviewed by: _____

Douglas A. Canavello, P.G.
NC License #1066

503 INDUSTRIAL AVENUE, GREENSBORO, NC 27406

P: 336.335.3174 F: 336.691.0648

C257: GEOLOGY C1251: ENGINEERING

GEOPHYSICAL INVESTIGATION REPORT
Parcel 027, 1975 N. US 1
Rockingham, Richmond County, North Carolina

Table of Contents

Executive Summary 1
Introduction..... 2
Field Methodology 2
Discussion of Results..... 3
Summary and Conclusions 4
Limitations 4

Figures

- Figure 1 – Parcel 027 – Geophysical Survey Boundaries and Site Photographs
- Figure 2 – Parcel 027 – EM61 Bottom Coil & Differential Results Contour Maps
- Figure 3 – Parcel 027 – Overlay of EM61 Contour Map On Engineering Plans

EXECUTIVE SUMMARY

Project Description: Pyramid Environmental conducted a geophysical investigation for the North Carolina Department of Transportation (NCDOT), at the Charles Sutton property, Parcel 027, 1975 N. US 1, Rockingham, Richmond County, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project R-2501C). The geophysical survey boundaries at the project site were designed to include the portions of the property between the existing edge of pavement and the proposed ROW and easements, whichever distance was greater. The geophysical investigation consisted of an electromagnetic (EM) induction-metal detection survey.

Geophysical Results: All of the EM61 anomalies detected could be attributed to visible objects at the ground surface such as signs, fences, and other cultural features. The geophysical investigation did not record evidence of any metallic USTs at the property.

INTRODUCTION

Pyramid Environmental conducted a geophysical investigation for the North Carolina Department of Transportation (NCDOT), at the Charles Sutton property, Parcel 027, 1975 N. US 1, Rockingham, Richmond County, NC. The survey was part of an NCDOT Right-of-Way (ROW) investigation (NCDOT Project R-2501C). The geophysical survey boundaries at the project site were designed to include the portions of the property between the existing edge of pavement and the proposed ROW and easements, whichever distance was greater. The survey grid spanned approximately 300 feet from west to east and approximately 60 feet from north to south. Conducted on December 3, 2013, the geophysical investigation was performed to determine if unknown, metallic underground storage tanks (USTs) were present beneath the survey area.

The site contained an auto repair shop and ATV sales store, and otherwise consisted primarily of open grassy and gravel areas. It should be noted that dense vegetation on the eastern half of the survey area prevented a portion of the parcel from being surveyed with the geophysical equipment. Aerial photographs showing the survey area boundaries and ground-level photographs are shown in **Figure 1**.

FIELD METHODOLOGY

Prior to conducting the geophysical investigation, a 20-foot by 10-foot survey grid was established across the geophysical survey areas using measuring tapes and water-based marking paint. These grid marks were used as X-Y coordinates for location control when collecting the geophysical data and establishing base maps for the geophysical results.

The geophysical investigation consisted of an electromagnetic (EM) induction-metal detection survey. The EM survey was performed on December 3, 2013, using a Geonics EM61 metal detection instrument. According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. The EM61 data were digitally collected at approximately 0.8 foot intervals along north-south trending or east-west trending, parallel survey

lines spaced five feet apart. The data were downloaded to a computer and reviewed in the field and office using the Geonics DAT61 and Surfer for Windows Version 11.0 software programs.

GPR data were not required due to all EM anomalies being directly attributable to cultural features at the ground surface (see discussion below).

DISCUSSION OF RESULTS

Contour plots of the EM61 bottom coil and differential results obtained across survey area at the property are presented in **Figure 2**. The bottom coil results represent the most sensitive component of the EM61 instrument and detect metal objects regardless of size. The bottom coil response can be used to delineate metal conduits or utility lines; small, isolated metal objects, and areas containing insignificant metal debris. The differential results are obtained from the difference between the top and bottom coils of the EM61 instrument. The differential results focus on the larger metal objects such as drum and UST-size objects and ignore the smaller insignificant metal objects.

Discussion of EM Anomalies: The high amplitude EM feature spanning the entire survey area from west to east at Y=50 was the result of a chain link fence at that location. A metal carport on the west side of the survey area resulted in the EM response surrounding that structure. The EM feature at X=115, Y=55 was the result of a metal sign. The EM anomalies at X=120, Y=25 and X=234, Y=25 were the result of metal mailboxes. The EM feature at X=250, Y=80 was the result of an adjacent parked vehicle outside of the survey area. The EM anomaly at X=275, Y=75 was associated with visible metal debris at the ground surface. The EM response at the east boundary of the survey area was the result of a metal fence extending from south to north at that location. As discussed above, it should be noted that an area of dense vegetation on the eastern half of the survey area (shown on **Figure 2**) was not surveyed due to inaccessibility. **Figure 3** provides an overlay of the bottom coil EM contour map on the NCDOT engineering plans for reference.

GPR data were not required due to all EM anomalies being directly attributable to cultural features at the ground surface. The geophysical investigation did not record evidence of any metallic USTs at the property.

SUMMARY & CONCLUSIONS

Our evaluation of the EM61 data collected across Parcel 027 in Rockingham, North Carolina, provides the following summary and conclusions:

- The EM61 survey provided reliable results for the detection of metallic USTs within the accessible portions of the geophysical survey area.
- All of the EM61 anomalies detected could be attributed to visible objects at the ground surface such as signs, fences, and other cultural features.
- The geophysical investigation did not record evidence of any metallic USTs at the property.

LIMITATIONS

Geophysical surveys have been performed and this report prepared for the NCDOT in accordance with generally accepted guidelines for EM61 and GPR surveys. It is generally recognized that the results of the EM61 and GPR surveys are non-unique and may not represent actual subsurface conditions. The EM61 and GPR results obtained for this project have not conclusively determined the definitive presence or absence of metallic USTs, but that the evidence collected is sufficient to result in the conclusions made in this report. Additionally, it should be understood that areas containing extensive vegetation, reinforced concrete, or other restrictions to the accessibility of the geophysical instruments could not be fully investigated.




Approximate Boundaries of the Geophysical Survey Area



View of East Portion of Survey Area
(Facing Approximately East)



View of West Portion of Survey Area
(Facing Approximately West)


TITLE		PARCEL 027: GEOPHYSICAL SURVEY BOUNDARIES AND SITE PHOTOGRAPHS	
PROJECT		NCDOT PROJECT R-2501C (34437.1.1) ROCKINGHAM, RICHMOND COUNTY, NC	
		503 INDUSTRIAL AVENUE GREENSBORO, NC 27460 (336) 335-3174 (p) (336) 691-0648 (f) License # C1251 Eng. / License # C257 Geology	
DATE	1/6/2014	CLIENT	NCDOT
PYRAMID PROJECT #:	2013-278	FIGURE 1	




NO EVIDENCE OF METALLIC USTs OBSERVED

The contour plots show the bottom coil (most sensitive) and differential results of the EM61 instrument in millivolts (mV). The bottom coil response shows buried metallic objects regardless of size. The differential response focuses on larger, buried metallic objects such as drums and USTs and ignores smaller miscellaneous buried, metal debris. The EM61 data were collected on December 3, 2013 using a Geonics EM61 instrument. Ground penetrating radar (GPR) data were not required due to all anomalies being explained by cultural features at the ground surface.


EM61 Bottom Coil Results





EM61 Differential Results



EM61 Metal Detection Response (millivolts)




TITLE	PARCEL 027: EM61 BOTTOM COIL & DIFFERENTIAL RESULTS CONTOUR MAPS	
PROJECT	NCDOT PROJECT R-2501C (34437.1.1) ROCKINGHAM, RICHMOND COUNTY, NC	
	503 INDUSTRIAL AVENUE GREENSBORO, NC 27460 (336) 335-3174 (p) (336) 691-0648 (f) License # C1251 Eng. / License # C257 Geology	
	DATE	1/6/2014
PYRAMID PROJECT #:	2013-278	FIGURE 2



LEGEND

- PUE PROPOSED UTILITY EASEMENT
- EXISTING ROW
- EXISTING PROPERTY BOUNDARY
- PROPOSED ROW
- PROPOSED CONST. EASEMENT
- PROP. DRAINAGE UTIL. EASEMENT
- PROPOSED SS CUT LINE
- PROPOSED SS FILL LINE
- PROPOSED SS TRANSITION LINE
- PROPOSED DRAINAGE PIPING
- PROPOSED DRAINAGE EASEMENT
- YELLOW ZONE REPRESENTS GEOPHYSICAL SURVEY AREA, CONTOURS ARE EM61 RESULTS (METALLIC RESPONSES)



TITLE OVERLAY OF EM61 CONTOUR MAP ON ENGINEERING PLANS	
PROJECT NCDOT ROW PROJECT R-2501C (34437.1.1) CHARLES SUTTON PROPERTY - PARCEL 027 U.S. 1, RICHMOND COUNTY, NORTH CAROLINA	
503 INDUSTRIAL AVENUE GREENSBORO, NC 27406 336.335.3174 (p) 336.691.0648 (f) License # C1251 Eng. / #C257 Geology	
DATE: 12-19-13	REVISION NO. 0
PYRAMID PROJECT NO. 2012-278	FIGURE NO. 3

APPENDIX C

APPENDIX D



Hydrocarbon Analysis Results

Client: NCDOT Richmond County
Address: PARCEL 027
1975 US Highway 1 North
Rockingham, NC

Samples taken
Samples extracted
Samples analysed

Five Samples
Five Samples
Five Samples

Contact:

Operator
Tim Leatherman

Project: NCDOT Richmond R-2501C

Matrix	Sample ID	Dilution used	BTEX (C6 - C9)	GRO (C5 - C10)	DRO (C10 - C35)	TPH (C5 - C35)	Total Aromatics (C10-C35)	16 EPA PAHs	BaP	Ratios % light % mid % heavy	HC Fingerprint Match
S	27-3(7.5-10)	9.5	<0.5	<0.5	#DIV/0!	#DIV/0!	< 0.48	< 0.05	< 0.024	0 0 100	Match not possible
S	27-1(1-2.5)	8.5	<0.4	<0.4	0.9	0.9	0.76	0.07	< 0.021	82.4 14.2 3.4	Match not possible
S	27-2(5-7.5)	10.5	<0.5	<0.5	<0.5	<0.5	< 0.53	< 0.05	< 0.026	0 0 100	Match not possible
S	27-3(7.5-10)	9.5	<0.5	<0.5	<0.5	<0.5	< 0.48	< 0.05	< 0.024	0 0 100	Match not possible
S	27-1(5-7.5)	10.1	<0.5	<0.5	<0.5	<0.5	< 0.51	< 0.05	< 0.025	0 0 100	Match not possible
S	27-2(1-2.5)	8.8	<0.4	<0.4	<0.4	<0.4	< 0.44	< 0.04	< 0.022	0 0 100	Match not possible

Initial Calibrator QC check

Low Range Calibrator Final check
High Range Calibrator Final check

Results generated by a QED HC-1 analyser

Concentration values in mg/kg for soil samples and mg/L for water samples.

Soil values are not corrected for moisture or stone content

Fingerprints provide a tentative hydrocarbon identification based on operator selected library matches

Fingerprint match abbreviations Est = Specific calibrator not used, result estimated (PFM)= Poor library fingerprint match

(SBS)= site specific background subtracted (LBS)= Library background subtracted % = match confidence

APPENDIX E

December 31, 2013

Chemical Testing Engineer
NCDOT
Materials & Tests Unit
1801 Blue Ridge Road
Raleigh, NC 27607

RE: Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

Dear Chemical Engineer:

Enclosed are the analytical results for sample(s) received by the laboratory on December 20, 2013. The results relate only to the samples included in this report. Results reported herein conform to the most current TNI standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

Analyses were performed at the Pace Analytical Services location indicated on the sample analyte page for analysis unless otherwise footnoted.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,



Jon D Bradley

jon.bradley@pacelabs.com
Project Manager

Enclosures

cc: Tim Leatherman, Pyramid



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

CERTIFICATIONS

Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

Charlotte Certification IDs

9800 Kinsey Ave. Ste 100, Huntersville, NC 28078
North Carolina Drinking Water Certification #: 37706
North Carolina Field Services Certification #: 5342
North Carolina Wastewater Certification #: 12
South Carolina Certification #: 99006001

Florida/NELAP Certification #: E87627
Kentucky UST Certification #: 84
West Virginia Certification #: 357
Virginia/VELAP Certification #: 460221

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

SAMPLE ANALYTE COUNT

Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
92184266001	27-2 (5-7.5)	EPA 8015 Modified	NU1	2	PASI-C
		EPA 8015 Modified	GAW	2	PASI-C
		ASTM D2974-87	TNM	1	PASI-C

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

PROJECT NARRATIVE

Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

Method: EPA 8015 Modified
Description: 8015 GCS THC-Diesel
Client: NCDOT East Central
Date: December 31, 2013

General Information:

1 sample was analyzed for EPA 8015 Modified. All samples were received in acceptable condition with any exceptions noted below.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 3546 with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..

PROJECT NARRATIVE

Project: Richmond Co. 027 #34437.1.1

Pace Project No.: 92184266

Method: EPA 8015 Modified
Description: Gasoline Range Organics
Client: NCDOT East Central
Date: December 31, 2013

General Information:

1 sample was analyzed for EPA 8015 Modified. All samples were received in acceptable condition with any exceptions noted below.

Hold Time:

The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:

The samples were prepared in accordance with EPA 5035A/5030B with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):

All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:

All criteria were within method requirements with any exceptions noted below.

Internal Standards:

All internal standards were within QC limits with any exceptions noted below.

Surrogates:

All surrogates were within QC limits with any exceptions noted below.

Method Blank:

All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:

All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:

All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..

ANALYTICAL RESULTS

Project: Richmond Co. 027 #34437.1.1

Pace Project No.: 92184266

Sample: 27-2 (5-7.5) **Lab ID: 92184266001** Collected: 12/16/13 13:15 Received: 12/20/13 14:11 Matrix: Solid

Results reported on a "dry-weight" basis

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015 GCS THC-Diesel		Analytical Method: EPA 8015 Modified Preparation Method: EPA 3546						
Diesel Components	ND	mg/kg	5.9	1	12/20/13 18:42	12/23/13 15:07	68334-30-5	
Surrogates								
n-Pentacosane (S)	87	%	41-119	1	12/20/13 18:42	12/23/13 15:07	629-99-2	
Gasoline Range Organics		Analytical Method: EPA 8015 Modified Preparation Method: EPA 5035A/5030B						
Gasoline Range Organics	ND	mg/kg	4.6	1	12/30/13 14:50	12/30/13 21:11	8006-61-9	
Surrogates								
4-Bromofluorobenzene (S)	102	%	70-167	1	12/30/13 14:50	12/30/13 21:11	460-00-4	
Percent Moisture		Analytical Method: ASTM D2974-87						
Percent Moisture	15.0	%	0.10	1		12/28/13 10:37		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..

QUALITY CONTROL DATA

Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

QC Batch: GCV/7658 Analysis Method: EPA 8015 Modified
QC Batch Method: EPA 5035A/5030B Analysis Description: Gasoline Range Organics
Associated Lab Samples: 92184266001

METHOD BLANK: 1114325 Matrix: Solid
Associated Lab Samples: 92184266001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Gasoline Range Organics	mg/kg	ND	6.0	12/30/13 20:25	
4-Bromofluorobenzene (S)	%	103	70-167	12/30/13 20:25	

LABORATORY CONTROL SAMPLE: 1114326

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Gasoline Range Organics	mg/kg	49.7	49.5	100	70-165	
4-Bromofluorobenzene (S)	%			103	70-167	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1114327 1114328

Parameter	Units	92184283001 Result	MS		MSD		MS		MSD		% Rec Limits	RPD	Qual
			Spike Conc.	MS Result	MSD Spike Conc.	MSD Result	% Rec	% Rec					
Gasoline Range Organics	mg/kg	ND	34.7	34.7	38.2	38.4	110	111	47-187	1			
4-Bromofluorobenzene (S)	%						107	102	70-167				

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



QUALITY CONTROL DATA

Project: Richmond Co. 027 #34437.1.1
 Pace Project No.: 92184266

QC Batch: OEXT/25303 Analysis Method: EPA 8015 Modified
 QC Batch Method: EPA 3546 Analysis Description: 8015 Solid GCSV
 Associated Lab Samples: 92184266001

METHOD BLANK: 1111061 Matrix: Solid
 Associated Lab Samples: 92184266001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Diesel Components	mg/kg	ND	5.0	12/23/13 12:23	
n-Pentacosane (S)	%	89	41-119	12/23/13 12:23	

LABORATORY CONTROL SAMPLE: 1111062

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Diesel Components	mg/kg	66.7	49.8	75	49-113	
n-Pentacosane (S)	%			81	41-119	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 1111063 1111064

Parameter	Units	92184266001 Result	MS		MSD		% Rec		% Rec Limits	RPD	Qual
			Spike Conc.	Spike Conc.	Result	Result	% Rec	% Rec			
Diesel Components	mg/kg	ND	78.4	78.4	54.8	62.2	68	77	10-146	13	
n-Pentacosane (S)	%						77	82	41-119		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
 without the written consent of Pace Analytical Services, Inc..

QUALITY CONTROL DATA

Project: Richmond Co. 027 #34437.1.1

Pace Project No.: 92184266

QC Batch:	PMST/6122	Analysis Method:	ASTM D2974-87
QC Batch Method:	ASTM D2974-87	Analysis Description:	Dry Weight/Percent Moisture
Associated Lab Samples:	92184266001		

SAMPLE DUPLICATE: 1113487

Parameter	Units	92184176001 Result	Dup Result	RPD	Qualifiers
Percent Moisture	%	99.0	99.0	0	

SAMPLE DUPLICATE: 1113488

Parameter	Units	92184283002 Result	Dup Result	RPD	Qualifiers
Percent Moisture	%	6.7	6.2	7	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..

QUALIFIERS

Project: Richmond Co. 027 #34437.1.1

Pace Project No.: 92184266

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to changes in sample preparation, dilution of the sample aliquot, or moisture content.

ND - Not Detected at or above adjusted reporting limit.

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PRL - Pace Reporting Limit.

RL - Reporting Limit.

S - Surrogate

1,2-Diphenylhydrazine (8270 listed analyte) decomposes to Azobenzene.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Acid preservation may not be appropriate for 2-Chloroethylvinyl ether, Styrene, and Vinyl chloride.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

LABORATORIES

PASI-C Pace Analytical Services - Charlotte

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Pace Analytical Services, Inc.
205 East Meadow Road - Suite A
Eden, NC 27288
(336)623-8921

Pace Analytical Services, Inc.
2225 Riverside Dr.
Asheville, NC 28804
(828)254-7176

Pace Analytical Services, Inc.
9800 Kinsey Ave. Suite 100
Huntersville, NC 28078
(704)875-9092

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: Richmond Co. 027 #34437.1.1
Pace Project No.: 92184266

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
92184266001	27-2 (5-7.5)	EPA 3546	OEXT/25303	EPA 8015 Modified	GCSV/16310
92184266001	27-2 (5-7.5)	EPA 5035A/5030B	GCV/7658	EPA 8015 Modified	GCV/7661
92184266001	27-2 (5-7.5)	ASTM D2974-87	PMST/6122		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, Inc..



Client Name: Pyramid Environmental

Courier: Fed Ex UPS USPS Client Commercial Pace Other _____

Custody Seal on Cooler/Box Present: yes no Seals intact: yes no

Optional
 Proj. Due Date:
 Proj. Name:

Packing Material: Bubble Wrap Bubble Bags None Other _____

Thermometer Used: IR Gun T1102 **T1301** Type of Ice: **Wet** Blue None Samples on ice, cooling process has begun

Temp Correction Factor T1102: No Correction T1301: No Correction

Corrected Cooler Temp.: 2.3 °C Biological Tissue is Frozen: Yes No **N/A**

Date and Initials of person examining contents: 12/20/13

Temp should be above freezing to 6°C

Comments:

Chain of Custody Present:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	1.
Chain of Custody Filled Out:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	2.
Chain of Custody Relinquished:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	3.
Sampler Name & Signature on COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	4.
Samples Arrived within Hold Time:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	5.
Short Hold Time Analysis (<72hr):	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	6.
Rush Turn Around Time Requested:	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> N/A	7.
Sufficient Volume:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	8.
Correct Containers Used:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	9.
-Pace Containers Used:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
Containers Intact:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	10.
Filtered volume received for Dissolved tests	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	11.
Sample Labels match COC:	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	12.
-Includes date/time/ID/Analysis Matrix:		
All containers needing preservation have been checked.	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	13.
All containers needing preservation are found to be in compliance with EPA recommendation.	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
exceptions: VOA, coliform, TOC, O&G, WI-DRO (water)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Samples checked for dechlorination:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	14.
Headspace in VOA Vials (>6mm):	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	15.
Trip Blank Present:	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	16.
Trip Blank Custody Seals Present	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> N/A	
Pace Trip Blank Lot # (if purchased):		

Client Notification/ Resolution:

Field Data Required? Y / N

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

SCURF Review: JDB Date: 12/20/13
 SRF Review: JDB Date: 12/21/13

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)

WO# : 92184266

 92184266
 (if no label available)



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

Section A Required Client Information: Company: <u>Pyramid Environmental</u> Address: <u>P.O. Box 16265</u> <u>Greensboro, NC 27416</u> Email To: <u>Jim</u> Phone: <u>336-335-3174</u> Fax: Requested Due Date/TAT: <u>None</u>		Section B Required Project Information: Report To: <u>Jim Leatherman - Pyramid</u> Copy To: <u>NC.DOT</u> Purchase Order No.: <u>WBS# 34437.1.1</u> Project Name: <u>NC DOT Richmond County Parcel 027</u> Project Number: <u>2013-278 / #34437.1.1</u>		Section C Invoice Information: Attention: <u>NC DOT</u> Company Name: <u>NC DOT</u> Address: Pace Quote Reference: <u>WBS# 34437.1.1</u> Pace Project Manager: <u>Jon Bradley</u> Pace Profile #:	
Section D Required Client Information Matrix Codes MATRIX / CODE Drinking Water DW Water WT Waste Water WW Product P Soil/Solid SL Oil OL Wipe WP Air AR Tissue TS Other OT SAMPLE ID (A-Z, 0-9 / , -) Sample IDs MUST BE UNIQUE		REGULATORY AGENCY <input type="checkbox"/> NPDES <input type="checkbox"/> GROUND WATER <input type="checkbox"/> DRINKING WATER <input checked="" type="checkbox"/> UST <input type="checkbox"/> RCRA <input type="checkbox"/> OTHER _____ Site Location STATE: <u>NC</u>		Page: <u>1</u> of <u>1</u> <u>1667363</u>	

ITEM #	Matrix Codes	COLLECTED		SAMPLE TYPE (G=GRAB C=COMP)	MATRIX CODE (see valid codes to left)	RELINQUISHED BY / AFFILIATION		ACCEPTED BY / AFFILIATION		DATE	TIME	DATE	TIME	SAMPLE CONDITIONS
		COMPOSITE START	COMPOSITE END/GRAB			DATE	TIME	DATE	TIME					
1	27-2(5-75)			SLG		12/16/13	13:15							
2														
3														
4														
5														
6														
7														
8														
9														
10														
11														
12														

ADDITIONAL COMMENTS <u>Pyramid Environmental</u> <u>Pyramid</u> <u>Pyramid</u>		Relinquished By / Affiliation <u>Pyramid Environmental</u> <u>Pyramid</u> <u>Pyramid</u>		Accepted By / Affiliation <u>Pyramid Environmental</u> <u>Pyramid</u> <u>Pyramid</u>		Date <u>12/20/13</u> <u>14/11</u> <u>14/11</u>		Time <u>11:20</u> <u>14:15</u> <u>14:11</u>		Date <u>12/20/13</u> <u>14/11</u> <u>14/11</u>		Time <u>11:20</u> <u>14:15</u> <u>14:11</u>		SAMPLE CONDITIONS Received on Ice (Y/N) <input type="checkbox"/> <input checked="" type="checkbox"/> Custody Sealed Cooler (Y/N) <input type="checkbox"/> <input checked="" type="checkbox"/> Samples Intact (Y/N) <input type="checkbox"/> <input checked="" type="checkbox"/>	
Residual Chlorine (Y/N) <u>W1</u>															
Pace Project No./ Lab I.D. <u>92184264</u>															

ORIGINAL

SAMPLER NAME AND SIGNATURE

PRINT Name of SAMPLER: Timothy D. Leatherman
 SIGNATURE of SAMPLER: [Signature]
 DATE Signed (MM/DD/YY): 12/20/13

APPENDIX F
