PROJECT NO.	SHEET NO.
2019CPT.10.01.10901.1, etc.	39

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW EXC.	SOIL CEMENT BASE (FULL DEPTH RECLAMATION)	PORTLAND CEMENT FOR SOIL CEMENT BASE	INCIDENTAL STONE BASE	SHOULDER RECON.	1½" MILLING	2" MILLING	0" TO 1.5" MILLING	0" TO 2" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	INTERMEDIATE COURSE, I19.0C	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, S9.5C	LEVELING COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, MATCOAT, #78M STONE	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	ASPHALT SURFACE TREATMENT, DOUBLE SEAL	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	RETROFIT EXISTING CURB RAMP (STD. 848.06)	6" DRIVEWAYS (STD. 848.02 and/or 848.03)	ADJ. OF DROP INLET	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOX	PORTABLE LIGHTING	TEMP. SILT FENCE	STONE FOR EROSION CONTROL, CLASS B	SEDIMENT CONTROL STONE	WATTLE	POLYACRYLAMIDE (PAM)	INDUCTIVE LOOP SAWCUT
										MI	FT	CY	SY	TON	TONS	SMI	SY	SY	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	SY	SY	SY	GAL	WK	EA	SY	EA	EA	EA	LS	LF	TN	TN	LF	LB	LF
2019CPT.10.01.10901.1	Union	1	NC 75/ROUTE 30000075	FROM SR 1007 ROCKY RIVER ROAD TO SR 1157 FLETCHER BROOME RD MILEPOST 9.53 TO 10.73	1	2	2WU	NO	NO	1.2	24	385			80	2.40					432					2,124	459	155	476		16,704		5,850	0.84							179	24	12	179		
2019CPT.10.01.10901.1	Union	2	NC 75/ROUTE 30000075	FROM SR 1327 POTTER ROAD TO SR 1007 ROCKY RIVER ROAD MILEPOST 6.83 TO 9.53	2,8,10	2	2WU	YES	NO	2.7	24	1,757			150	5.40			840		475		5,415			3,660		480	1,076							125		2	1		404	54	27	404	1	
TOTAL FOR PROJ NO. 2019CPT.10.01.10901.1										**3.9**		**2,142**			**230**	**7.80**			**840**		**907**		**5,415**			**5,784**	**459**	**635**	**1,552**		**16,704**		**5,850**	**0.84**		**125**		**2**	**1**		**583**	**78**	**39**	**583**	**1**	
																			840																											
2019CPT.10.01.10901.2	Union	3	NC 200/ROUTE 30000200	FROM 1626 TOMBERLIN ROAD TO SR 1681 OLD CAMDEN ROAD MILEPOST 23.78 TO 25.58	2,3	2	2WU	YES	NO	1.8	24	735			200	3.60			400		288		3,830			2,358		325	720							50					270	36	18	270	1	
TOTAL FOR PROJ NO. 2019CPT.10.01.10901.2										**1.8**		**735**			**200**	**3.60**			**400**		**288**		**3,830**			**2,358**		**325**	**720**							**50**					**270**	**36**	**18**	**270**	**1**	
2019CPT.10.01.20901.1	Union	4	SR 1408 MCLENDON ROAD/ROUTE 40001408	FROM SR 1357 POTTER ROAD TO SR 1487 LINDENWOOD DRIVE MILEPOST 0 TO 0.7	4	2	2WU	NO	NO	0.7	20	72			125	1.40					167			500				34	280	8,231				2,470	0.41							105	14	7	105		
2019CPT.10.01.20901.1	Union	5	SR 1474 SENCONEE ROAD/ROUTE 40001474	FROM SR 1408 MCLENDON ROAD TO DEAD END MILEPOST 0 TO 0.18	4	2	2WU	NO	NO	0.18	20	18			40	0.40					120			149				10	75	2,089				630	0.10							27	4	2	27		
2019CPT.10.01.20901.1	Union	6	SR 1475 MATOKA TRAIL/ROUTE 40001475	FROM SR 1474 SENCONEE ROAD TO DEAD END MILEPOST 0 TO 0.2	4	2	2WU	NO	NO	0.2	20	21			55	0.40					112			146				10	90	2,407				725	0.12							30	4	2	30		
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.1										**1.08**		**111**			**220**	**2.20**					**399**			**795**				**54**	**445**	**12,727**				**3,825**	**0.63**							**162**	**22**	**11**	**162**		
2019CPT.10.01.20901.2	Union	7	SR 1483 PILGRIM FOREST DRIVE/ROUTE 40001483	FROM SR 1162 GOLDMINE ROAD TO END OF MAINTENANCE MILEPOST O TO 0.39	4	2	2WU	NO	NO	0.39	20	48			25	0.80					112			276				18	156	4,557				1,370	0.91							59	8	4	59		
2019CPT.10.01.20901.2	Union	8	SR 1484 BRADFORD STREET/ROUTE 40001484	FROM SR 1483 PILGRIM FOREST TO CUL DE SAC MILEPOST O TO 0.2	4	2	2WU	NO	NO	0.2	19	20			10	0.40					112			127	66			13	76	2,105				635	0.42							30	4	2	30		
2019CPT.10.01.20901.2	Union	9	SR 2609 CARLY SCOTT DRIVE/ROUTE 40002609	FROM SR 1162 GOLDMINE ROAD TO END OF MAINTENANCE MILEPOST O TO 0.2	4	2	2WU	NO	NO	0.2	18	18				0.40					112			142	83			15	88	2,352				710	0.12							33	4	2	33		
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.2										**0.79**		**86**			**35**	**1.60**					**336**			**545**	**149**			**46**	**320**	**9,014**				**2,715**	**1.45**							**122**	**16**	**8**	**122**		
2019CPT.10.01.20901.3	Union	10	SR 1003 WHITE STORE ROAD/ROUTE 40001003	FROM SR 1957 OLD MONROE-MARSHVILLE ROAD TO PVMT JOINT AT US 601 MILE POST 11 TO 12.6	5,7,8	2	2WU	NO	NO	1.6	22-33	250			105	3.20	77		165		272					2,231	748	179	850							225					255	34	17	255	1	
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.3										**1.6**		**250**			**105**	**3.20**	**77**		**165**		**272**					**2,231**	**748**	**179**	**850**							**225**					**255**	**34**	**17**	**255**	**1**	
2019CPT.10.01.20901.4	Union	11	SR 1681 OLD CAMDEN ROAD/ROUTE 40001681	FROM SR 1637 E. LAWYERS ROAD TO NC 200 MILEPOST 0 TO 2.1	9	2	2WU	NO	NO	2.1	21	435			215	4.20					261					3,305	824	248	1,070							175					321	43	21	321	1	
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.4										**2.1**		**435**			**215**	**4.20**					**261**					**3,305**	**824**	**248**	**1,070**							**175**					**321**	**43**	**21**	**321**	**1**	
2019CPT.10.01.20901.5	Union	12	SR 1194 JAARS ROAD/ROUTE 40001194	FROM SR 1113 DAVIS ROAD TO SR 1106 WALKUP ROAD MILEPOST 0 TO 1.45	8	2	2WU	NO	NO	1.45	20	219			170	2.90	249				240					1,600	129	104	290						8.00	25					218	29	15	218	1	
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.5										**1.45**		**219**			**170**	**2.90**	**249**				**240**					**1,600**	**129**	**104**	**290**						**8.00**	**25**					**218**	**29**	**15**	**218**	**1**	
2019CPT.10.01.20901.6	Union	13	SR 1357 POTTER ROAD/ ROUTE 40001357	FROM SR 1009 OLD MONROE ROAD ENDING 570 FT SOUTH/RESUME 630 FT FROM THE INTERSECTION OF SR 1364 AND SR 1357 ENDING AT SR 1362 MILEPOST 0 TO 1.17	5,6,7,8, 20	2	2WU	NO	NO	1.17	24-48	238			65	1.50			2,400		830					1,928	340	136	405							125		2	15	*	135	18	9	135		
2019CPT.10.01.20901.6	Union	14	SR 1364 PLEASANT PLAINS ROAD/ROUTE 40001364	FROM MECKLENBURG COUNTY LINE ENDING 1,560 FT EAST/RESUME 415 FT FROM THE INTERSECTION OF SR 1364 AND 1357 ENDING AT SR 1009 MILEPOST 0 TO 0.79	9,11,12, 13, 20	2	2WU	NO	NO	0.79	21-48	60			55	0.60				1,400	819	125			1,150	198	87	216								1.00	75		1	8	*	144	10	5	144		
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.6										**1.96**		**298**			**120**	**2.10**			**2,400**	**1,400**	**1,649**	**125**				**3,078**	**538**	**223**	**621**						**1.00**	**200**		**3**	**23**	*	**279**	**28**	**14**	**279**		
2019CPT.10.01.20901.7	Union	15	SR 1371 SOUTH FORK ROAD/ROUTE 40001371	FROM SR 1009 OLD MONROE ROAD TO SR 1008 WAXHAW-INDIAN TRAIL ROAD MILEPOST 0 TO 0.73	8	2	2WU	NO	NO	0.73	21	111			90	1.50					243					852	321	70	292							125		2	1		110	15	7	110		
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.7										**0.73**		**111**			**90**	**1.50**					**243**					**852**	**321**	**70**	**292**							**125**		**2**	**1**		**110**	**15**	**7**	**110**		
2019CPT.10.01.20901.8	Union	16	SR 1519 YOUNTS ROAD/ROUTE 40001519	FROM PVEMT JT 530 FT FROM SR 1520 ENDING 1405 FT SOUTHEAST/RESUME AT PVMT JT 780 FT FROM BROWN LN TO SR 1367 MILEPOST 0 TO .88	7,8,20	2	2WU	NO	NO	0.88	24-36	95			70	1.20			1,175		365					1,053	371	85	405							100					93	12	6	93		
TOTAL FOR PROJ NO. 2019CPT.10.01.20901.8										**0.88**		**95**			**70**	**1.20**			**1,175**		**365**					**1,053**	**371**	**85**	**405**							**100**					**93**	**12**	**6**	**93**		
2019CPT.10.01.20901.9	Union	17	SR 1657 HAIGLER GIN ROAD/ROUTE 40001657	FROM NC 200 TO NC 218 MILEPOST 0 TO 1.5	8	2	2WU	NO	NO	1.5	21	229			90	3.00					254					1,724	660	143	750							150					225	30	15	225	1	