

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.05.16.10921.1,etc.	13	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE S	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BORROW	AGGREGATE SHOULDER BORROW (ASB)	SHOULDER GRADING	INCIDENTAL STONE BASE	1½" MILLING	0" TO 1.5" MILLING	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJ. OF DROPPINGS	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOXES	TEMP. SILT FENCE	WATTLE	SEED & MULCHING	INDUCTIVE LOOP SAW-CUT		
									MI	FT	CY	TON	SMI	TONS	SY	SY	SY	TONS	TONS	TON	TONS	EA	EA	EA	LF	LF	AC	LF		
2018CPT.05.16.10921.1	Wake	1	BUS 64/NC 96 - N ARENDELL AVE	NC 97 - E GANNON AVE TO US 64/264	4	4	NO	NO	0.78	40-68					19,903		142	1,729		116	100		4	17				1,660		
		2	NC 96 - ZEBULON RD / N ARENDELL AVE	.1 MI N OF SR 1001 - PEARCES RD TO SR 2315 - DOYLE RD	2	2	NO	NO	4.237	25	212	407	8.47	212				3,912	5,771		387	250	1	2	12	308	780	3.00		
		3	NC 96 - S ARENDELL AVE	JOHNSTON CO TO RR TRACKS	2	2	NO	NO	2.1	25-42	142	68	3.55	89			3,312	1,181	3,012		202	100		5	1	206	520	2.00		
		4	NC 97 - NC 97 HWY/W GANNON AVE	US 64 BUS - WENDELL BLVD TO US 64 BUS - MACK TODD RD	2	2	NO	NO	4.82	24-32	376	181	9.00	235			549	2,817	7,301		489	250		3	3	547	1,370	5.00		
		5	BUS 64 WB - NEW BERN AVE	BRIDGE # 0170 TO I - 440	5	3	NO	NO	2.663	40-50	185			3.69	92	73,155			262		6,493	390	100				268	680	2.68	2,116
		6	BUS 64 EB - NEW BERN AVE	I - 440 TO BRIDGE # 0169	5	3	NO	NO	2.668	40-60	190			3.81	95	72,345			980		6,485	389	100				277	700	2.77	2,260
TOTAL FOR PROJ NO. 2018CPT.05.16.10921.1									17.268		1,105	656	28.52	723	165,403	3,861	9,294	17,813	12,978	1,973	900	1	14	33	1,606	4,050	15.45	6,036		
2018CPT.05.16.20921.1	Wake	7	SR 2911 - WB NEW BERN AVE	I-440 - TO BRIDGE # 0001	5	3	NO	NO	0.27	38-50	14		0.28	7	7,502		731		728	44	50				20	60	0.20	472		
		8	SR 2911 - EB NEW BERN AVE	BRIDGE # 0538 TO I- 440	5	3	NO	NO	0.27	50-60	14			0.27	7	9,466		316		865	52	50				20	50	0.20	890	
		9	SR 2357 - S HOLLYBROOK AVE	SR 2355 - E THIRD ST TO JOHNSTON CO	2	2	NO	NO	2.042	20	163	87	4.08	102				222	2,108		141	100		4	12	238	600	2.38		
		10	SR 2537 - CREECH RD	SR 2564 - SANDERFORD RD TO SR 2542 - ROCK QUARRY RD	1	2	NO	NO	0.87	26-40	19			0.37	9	17,580		1,107	1,624		109	45				27	70	0.27	408	
		11	SR 2542 - ROCK QUARRY RD	SR 2537 - CREECH RD TO WCPS DR.	6	2	NO	NO	1.05	52-100	53			1.05	26	37,318		1,779		3,449	207	50				76	200	0.76		
		12	SR 2542 - ROCK QUARRY RD	SR 2537 -CREECH RD TO SR 2544 - SUNNYBROOK RD	6	2	NO	NO	1.07	36-65	85	41	2.14	53	37,390			111		3,315	199	55				124	320	1.00	993	
		13	SR 2555 - AUBURN-KNIGHTDALE RD	SR 2511 - GRASSHOPPER RD TO SR 2552 - BATTLE BRIDGE RD	2	2	NO	NO	2.6	22-31	130	250	5.20	130				760	2,991		200	130				189	480	2.00		
		14	SR 2555 - AUBURN-KNIGHTDALE RD	SR 2552 - BATTLE BRIDGE RD TO 800 FEET BEFORE US 70	1	2	NO	NO	2.86	22-35	143	275	5.72	143	37,449			864	3,337		224	145				208	520	2.08		
		15	SR 2555 - RAYNOR RD	SR 2700 - WHITE OAK RD TO 800 FEET SOUTH OF US 70	2	2	NO	NO	1.52	25-40	11	21	0.43	11			6,132	437	1,983		133	90				16	40	0.16		
		16	SR 2604 - EVA MAE DR	SR 5233 - OLD POOLE RD TO END MAINT	4	2	NO	NO	0.23	23-34							3,289		129	298		20	30							
		17	SR 2921 - RALEIGH BLVD	BRIDGE # 1096 - TO I - 440	4	4	NO	NO	0.593	52-84							20,958		1,198	1,923		129	107						986	
		18	SR 2204 - RALEIGH BLVD	I 440 TO JOINT EAST OF BRENTWOOD RD	4	5	NO	NO	0.494	52-75							18,768		565	1,678		112	195						1,034	
		19	SR 2921 - ROCK QUARRY RD	WCPS DR. TO SR 2921 - S RALEIGH BLVD	7,3	2	NO	NO	0.331	64-100							16,762		429		1,518	91	40						1,266	
TOTAL FOR PROJ NO. 2018CPT.05.16.20921.1									14.200		632	674	19.54	488	206,482	6,132	8,648	15,942	9,875	1,661	1,087		4	12	918	2,340	9.05	6,049		
GRAND TOTAL									31.468		1,737	1,330	48.06	1,211	371,885	9,993	17,942	33,755	22,853	3,634	1,987	1	18	45	2,524	6,390	24.50	12,085		