PROJ. REFERENCE NO.	SHEET NO.
B-2506	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	3	5
11+00.00	2	14
11+50.00	1	30
12+00.00	0	64
12+50.00	0	138
13+00.00	0	129
13+50.00	0	77
14+00.00	0	181
14+50.00	0	263
15+00.00	0	332
15+50.00	3	358
16+00.00	3	319
16+50.00	0	344
17+00.00	0	272
17+50.00	0	141
17+98.81	0	81

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+26.19	0	0
19+50.00	2	28
20+00.00	9	72
20+50.00	17	81
21+00.00	20	76
21+50.00	17	78
22+00.00	7	88
22+50.00	0	103
23+00.00	0	118
23+50.00	0	120
24+00.00	0	82
24+50.00	1	36
25+00.00	2	16
25+50.00	2	15

INDEX OF SHEETS

LINE	STATIONS	SHEETS
-L-	STA 10+00.00 TO STA 25+50.00	X-1 THRU X-8