PROJECT REFERENCE NO.	SHEET NO.
B-4448	EC-3A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

PERMANENT SOIL REINFORCEMNT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
5	-Y1RPB-	14+32	18+12	RT	345
5	-Y1RPC-	15+75	22+92	RT	805
5	-Y1RPD-	19+49	21+03	RT	140
			SUBTOTAL		1290
	ADDITIONAL PSRM TO BE INSTALLED				205
				TOTAL	1495
				SAY	1500

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)