PROJECT NO.	SHEET NO.	TOTAL NO.
I-5811	10	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4400000 WORK ZONE SIGNS (STATIONARY)	4420000 PORTABLE CMS	4430000 DRUMS	4600000 LANE CLOSURE	4600000 RAMP / LOOP CLOSURE	4688000000-E 6" X 90 M WHITE THERMO	4688000000-E 6" X 90 M YELLOW THERMO	46900000 6" X 120 M WHITE THERMO	4697000 8" X 120 M WHITE THERMO	4700000 12" X 90 M WHITE THERMO	4702000 12" X 120 M WHITE THERMO	4710000 24" X 120 M WHITE THERMO	47210 THERMO MSG ONLY 120 M	4725000000-E THERMO RT ARROW 90 M	4725000000-E THERMO LT ARROW 90 M	4725000000-E THERMO RAMP ARROW	4725000000-E THERMO MERGE LEFT ARROW 90 M	4725000000-E THERMO STR & LT ARROW 90 M	4725000000-E THERMO STR ARROW 90 M	4815000000-E 6" WHITE PAINT	4815000000-E 6" YELLOW PAINT	482000 8" WHITE PAINT	48250000 12" WHITE PAINT	48350 24" WHITE PAINT	48400 PAINT MSG ONLY	4845000000-N PAINT RT ARROW	4845000000-N PAINT LT ARROW	4845000000-N PAINT MERGE LEFT ARROW	4845000000-N PAINT STR & LT ARROW	4845000000-N PAINT STR ARROW	4847030000-E POLY-UREA PM LINES (YELLOW) (6", 20 MILS) HRM	4847030000-E POLY-UREA PM LINES (WHITE) (6", 20 MILS) HRM	48470700 POLY-UREA PM LINES (WHITE) (12", 20 MILS) HRM	48550000 REM. OF PM LINES (6")	49050000 SNOW-PLOW-ABLE PAV. MARKERS CRYSTAL/RED	4960...-N REPLACE BARRIER WALL DELINEATORS "CRYSTAL"	4960...-N REPLACE BARRIER WALL DELINEATORS "YELLOW"
								MI	FT	SF	EA	EA	EA	EA	LF	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	EA	EA	EA
I-5811	Guilford	1	I-40 EB	73 TO EAST OF HOLDEN ROAD (NS) OVERPASS	1	4	MD	0.384	78	700	2	50	165	12	24,910	24,910	12,455		3,481	4,393		32	16						74,730	49,820		15,748		64	32					727	1,117	120	1,964	1,404	36	229
		"	"	BRIDGE (SKIP)	1	2	MD	0.056	78																																						
		"	"		1	2	MD	0.112	78																																						
		"	"		1	2	MD	0.036	94																																						
		"	"		1	2	MD	0.292	60																																						
		"	"		1	2	MD	0.075	94																																						
		"	"		1	2	MD	0.282	71																																						
		"	"		1	2	MD	0.026	85																																						
		"	"		1	2	MD	0.169	66																																						
		"	"		1	2	MD	0.047	87																																						
		"	"		1	2	MD	0.313	71																																						
		"	"		1	2	MD	0.08	75																																						
		"	"		1	2	MD	0.132	93																																						
		"	"		1	2	MD	0.225	71																																						
		"	"		1	2	MD	0.022	85																																						
		"	"		1	2	MD	0.101	67																																						
		"	"		1	2	MD	0.03	87																																						
		"	"		1	2	MD	0.036	73																																						
		"	"		1	2	MD	0.779	73																																						
		"	"		1	2	MD	0.091	77																																						
		"	"	BRIDGE (SKIP)	1	2	MD	0.033	77																																						
		"	"		1	2	MD	0.124	78																																						
		"	"		1	2	MD	0.064	92																																						
		"	"		1	2	MD	0.258	59																																						
		"	"	BRIDGE (SKIP)	1	2	MD	0.047	59																																						
		"	"		1	2	MD	0.905	59																																						
TOTAL FOR MAP NO. 1								**4.719**		**700**	**2**	**50**	**165**	**12**	**24,910**	**24,910**	**12,455**		**3,481**	**4,393**		**32**	**16**						**74,730**	**49,820**		**15,748**		**64**	**32**					**727**	**1,117**	**120**	**1,964**	**1,404**	**36**	**229**
I-5811	Guilford	2	OFF LOOP RAMP	FROM EB 40 TO SR 1546 (GUILFORD COLLEGE ROAD)	2	2	MD	0.073	31							388	373				56	8	4	8	1				373	388			56	16	4	8									31		
		"	"		2	2	MD	0.039	46																																						
		"	"		2	2	MD	0.005	94																																						
TOTAL FOR MAP NO. 2								**0.117**								**388**	**373**				**56**	**8**	**4**	**8**	**1**				**373**	**388**			**56**	**16**	**4**	**8**									**31**		
I-5811	Guilford	3	ON RAMP	(GUILFORD COLLEGE ROAD) TO EB 40	2	2	MD	0.006	46						1,165	995	278				16					5			1,443	995			16				5								8		
		"	"		2	2	MD	0.014	37																																						
		"	"		2	2	MD	0.025	32																																						
		"	"		2	2	MD	0.117	33																																						
		"	"		2	2	MD	0.071	27																																						
TOTAL FOR MAP NO. 3								**0.233**							**1,165**	**995**	**278**				**16**					**5**			**1,443**	**995**			**16**				**5**								**8**		
I-5811	Guilford	4	OFF RAMP	FROM EB 40 TO SR 1541 (WENDOVER AVENUE)	2	2	MD	0.112	28						592	620	132	138			56	8	4		1				724	620	138		56	8	4										20		
		"	"		2	2	MD	0.108	67																																						
TOTAL FOR MAP NO. 4								**0.22**							**592**	**620**	**132**	**138**			**56**	**8**	**4**		**1**				**724**	**620**	**138**		**56**	**8**	**4**										**20**		
I-5811	Guilford	5	OFF LOOP RAMP	FROM EB 40 TO SR 1541 (WENDOVER AVENUE)	2	2	MD	0.093	31							435	160	88			35		6		1				160	435	88		35		6										22		
		"	"		2	2	MD	0.052	26																																						
		"	"		2	2	MD	0.015	26																																						
TOTAL FOR MAP NO. 5								**0.16**								**435**	**160**	**88**			**35**		**6**		**1**				**160**	**435**	**88**		**35**		**6**										**22**		
I-5811	Guilford	6	ON RAMP	TO EB 40 FROM SR 1541 (WENDOVER AVENUE)	2	2	MD	0.018	40						1,088	690	195	127	115				1			4			1,283	690	127	115			1		4								15		
		"	"		2	2	MD	0.076	28																																						
		"	"		2	2	MD	0.057	29																																						
		"	"		2	2	MD	0.073	26																																						
TOTAL FOR MAP NO. 6								**0.224**							**1,088**	**690**	**195**	**127**	**115**				**1**			**4**			**1,283**	**690**	**127**	**115**			**1**		**4**								**15**		
5811	uilford	7	OFF RAMP	FROM EB 40 TO SR 4239 (PATTERSON STREET)	2	2	MD	0.068	38						2,770	2,770													2,770	2,770																25	7
		"	"		2	2	MD	0.027	30																																						
		"	"		2	2	MD	0.174	22																																						