

CE TRAY IN SURING	 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM, CONTACT THE CITY OF HIGH POINT'S SIGNAL SYSTEM ENGINEER, JAMES BAKER AT (336) 883-8540 TO ARRANGE FOR THE CITY OF HIGH POINT TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE SIGNAL SYSTEM ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS. ETHERNET SWITCH TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING \ ENSURING PROPER TERMINATIONS. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING: REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE" SPLICE LOCATION 2) DATE 3) COMPANY NAME 4) NAME OF INDIVIDUAL PERFORMING THE SPLICING PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN 	Mott Mott Mott Mott Mott Mott Mott Mott	Prepared
SURING	PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.		

PROJECT F	REFERENCE NO.	SHEET	NO.
\bigcup –	2412A	SCP-	10

ed for the Offices of:		High Point Signal System Splicing Details		SEAL CARO SEAL		
		Division 7 Guilford PLAN DATE: February 2018 PREPARED BY: B. LEHAN	County Reviewed by: R. THO Reviewed by:	High OMPSON	Point	- 045256 -
SCALE		REVISIONS		INIT.	DATE	- DocuSigned by ! / / / / / / / / / / / / / / / / / /
	NTS					Brendan Lehan 3/20/2018