


PHASING DIAGRAM




- PHASING DIAGRAM DETECTION LEGEND**
- ➔ DETECTED MOVEMENT
 - ➔ UNDETECTED MOVEMENT (OVERLAP)
 - ➔ UNSIGNALIZED MOVEMENT
 - ➔ PEDESTRIAN MOVEMENT

TABLE OF OPERATION

SIGNAL FACE	PHASE		
	Ø2+6	Ø4	FLIGHT
21	↑	R	Y
22	G	R	Y
41	R	G	R
42	R	G	R
61,62	↑	R	Y

SIGNAL FACE I.D.
All Heads L.E.D.



OASIS 2070 LOOP & DETECTOR INSTALLATION


ZONE	SIZE (FT)	INDUCTIVE LOOPS			DETECTOR PROGRAMMING						
		DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	PHASE	CALLING EXTENSION	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD	
2A	*	300	*	*	2	Y	Y	1.6	-	-	*
2B	*	90	*	*	2	Y	Y	-	-	-	*
4A	*	0	*	*	4	Y	Y	-	-	-	*
4B	*	0	*	*	4	Y	Y	-	-	-	*
4C	*	0	*	*	4	Y	Y	-	-	15	*
6A	*	300	*	*	6	Y	Y	1.6	-	-	*
6B	*	90	*	*	6	Y	Y	-	-	-	*
S1	*	+200	*	*	-	Y	Y	-	-	-	Y *
S2	*	+200	*	*	-	Y	Y	-	-	-	Y *

* Multi-Zone Microwave Detection

2 Phase Fully Actuated (High Point Signal System)

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- Reposition existing signal for late night flashing operation unless otherwise directed by the Engineer.
- Set all detector units to presence mode.
- A multiple zone microwave detection system is used to provide traffic detection during the temporary phase on approaches where the existing loops and lead-ins have been rendered inoperable by construction. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the direction schemes shown on the Signal Design Plans.
- Pavement markings are existing unless otherwise shown.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.




LEGEND

- | PROPOSED | EXISTING |
|----------|----------|
| ○➔ | ●➔ |
| ○➔ | N/A |
| ⊥ | ⊥ |
| ⊥ | ⊥ |
| ○ | ○ |
| ○ | ○ |
| ⊠ | ⊠ |
| ⊠ | ⊠ |
| - - - | - - - |
| N/A | - - - |
| ➔ | ➔ |
| N/A | — — |
| N/A | ⤴ |
| ■ | ■ |
| ■ | ■ |
| ○ | ○ |
| ○ | ○ |
| Ⓐ | Ⓐ |
| Ⓑ | Ⓑ |
| Ⓒ | Ⓒ |
| Ⓓ | Ⓓ |
| Ⓔ | Ⓔ |

OASIS 2070 TIMING CHART

FEATURE	PHASE		
	2	4	6
Min Green 1*	12	7	12
Extension 1*	2.0	2.0	2.0
Max Green 1*	90	30	90
Yellow Clearance	4.6	3.7	4.5
Red Clearance	1.0	1.9	1.2
Walk 1*	-	-	-
Don't Walk 1	-	-	-
Seconds Per Actuation*	-	-	-
Max Variable Initial*	-	-	-
Time Before Reduction*	-	-	-
Time To Reduce*	-	-	-
Minimum Gap	-	-	-
Recall Mode	MIN RECALL	-	MIN RECALL
Vehicle Call Memory	YELLOW	-	YELLOW
Dual Entry	-	-	-
Simultaneous Gap	ON	ON	ON

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.



PROPOSED STOP BAR LOCATION DIAGRAM

Project #: 170908

HOME OFFICE:
119 BROOKSTOWN AVENUE, SUITE PH1
WINSTON-SALEM, NC 27101
336.744.1636 www.davenportworld.com
NCBELS FIRM LICENSE NO. C-2522

Signal Upgrade - Temporary Design 5; TMP-29

750 N. Greenfield Pkwy, Garner, NC 27529

NC 68 (Eastchester Drive)
at
I-74 EB/ US 311 SB Ramps

Division 7 Guilford County High Point

PLAN DATE: May 2018 REVIEWED BY: L. Boyer

PREPARED BY: A. Ravipati REVIEWED BY: R. Hinshaw

REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

DocuSigned by: Royal Hinshaw 05/18/2018

SIGNATURE DATE

SIG. INVENTORY NO. 07-162415