


PROJECT REFERENCE NO.	SHEET NO.
U-5169	Sig. 12.0

INSTALLATION						
PROGRAMMING						
Full Time Delay	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD		
-	-	10	-	*		
-	-	15	-	*		
-	1.6	-	-	*		
-	-	-	-	*		
-	1.6	-	-	*		
-	-	-	-	*		
-	-	-	-	*		
-	-	-	-	*		

## 3 Phase Fully Actuated (High Point Signal System)

## <u>NOTES</u>

- 1. Refer to "Roadway Standard Drawings NCDOT" dated January 2018 and "Standard Specifications for Roads and Structures" dated January 2018.
- 2. Do not program signal for late night flashing operation unless otherwise directed by the Engineer.
- 3. Phase 1 may be lagged.
- 4. Renumber existing signal head 41 as 81.
- 5. Reposition existing signal heads numbered 61, 62, 63, and 81 and signs 'A' and 'B'.
- 6. Set all detector units to presence mode.
- 7. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- 8. A multiple zone microwave detection system is used to provide traffic detection during this temporary phase on approaches where the existing loops and lead-ins have been rendered inoperable by construction. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the direction schemes shown on the Signal Design Plans.
- 9. Pavement markings are existing unless otherwise shown.
- 10. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.
- 11. Reposition existing "Combined Through and Left Arrow" sign (R3-6L)



ynal Upgrade	- Temporary Design 3; TMP-22, 22A, and 27	DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
Prepared for:	NC 68 (Eastchester Driv at I-74 WB/ US 311 NB Ram	CARO MARCARO
Greenfield Pkwy.Garner,NC 27525	PLAN DATE: May 2018 REVIEWED BY: L. BO	igh Point 032117
SCALE 0 40 1"=40'	REVISIONS INIT	